

REQUEST FOR PROPOSAL #27-25

FLEET STREET AND MONROE COMPLETE STREETS PROJECT MOA88B21

Proposals Due by 2:00 P.M. EST on Friday, December 05, 2025

ISSUED BY: TJ Ellison, CPPB Procurement Department City of Rockville, City Hall 111 Maryland Avenue Rockville, Maryland 20850 Phone: (240) 314-8436 Fax: (240) 314-8439

> ISSUED ON: October 24, 2025

A DBE goal of 0% has been assigned for this project.

Any individual with a disability who would like to receive the information in this publication in another form may contact the ADA Coordinator at 240-314-8100, TDD 240-314-8137

MFD-V Outreach Program

It is the intent of the City of Rockville to increase opportunities for minority, female, disabled, or veteran (MFD-V) owned businesses to compete effectively at supplying goods, equipment, and services to the City, within the constraints of statutory purchasing requirements, departmental needs, availability, and sound economical considerations, including subcontracting or mentoring opportunities. Suggested changes and MFD-V enhancements to this solicitation's requirements for possible consideration and/or inclusion in future solicitations are strongly encouraged. Any questions regarding MFD-V outreach or questions/concerns regarding the City's bidding process should be addressed to procurement@rockvillemd.gov or 240-314-8430.



REQUEST FOR PROPOSAL #27-25 Fleet Street and Monroe Complete Streets Project MOA88B21

RECEIPT AND HANDLING OF PROPOSALS

Sealed proposals will be received electronically via a City designated bid/proposal receipt software solution until **2:00 P.M. EST, December 05, 2025**. The offeror assumes full responsibility for the timely delivery of a proposal via the designated solution. Proposals delivered in any other fashion will not be considered. Properly submitted proposals will be opened in a virtual environment after the time set for receipt of proposals.

Submission of a proposal electronically is consent by the offeror to conduct any or all elements of the procurement by electronic means, in accordance with the terms of this request for proposals.

The RFP documents will be made public via the City's Collaboration Portal and eMarylandMarketplaceAdvantage, however, proposals will <u>only</u> be accepted electronically via the City's Collaboration Portal.

Proposals presented after the proposal receiving deadline will not be accepted for any reason. The official time clock for receiving proposals will be that of the City's third-party software solution providers located at Rockville City Hall.

ATTENTION: OFFERORS ARE HEREBY NOTIFIED THAT THE CITY'S THIRD-PARTY SOFTWARE SOLUTION PROVIDER'S COMPUTER SERVER TIME MAY DIFFER FROM THAT OF OTHER ELECTRONIC DEVICES, COMPUTER SOFTWARE AND COMPUTER HARDWARE THAT MAY BE USED TO ELECTRONICALLY SUBMIT THE PROPOSAL. OFFERORS ARE RESPONSIBLE FOR ALLOWING ADEQUATE TIME TO SUCCESSFULLY DELIVER THE PROPOSAL TO THE REQUIRED ELECTRONIC LOCATION BY THE REQUIRED TIME.

In accordance with Chapter 17 of the City's Procurement Ordinance, competitive sealed proposals are not publicly opened or otherwise handled so as to permit disclosure of the identity of any offeror or the contents of any proposal to competing offerors during the evaluation process. The proposals, except for information identified by the offeror as proprietary, shall be open for public inspection after the contract award.

Proposals must be submitted electronically. Proposals will not be opened publicly.

If a Joint Venture (JV) responds to this RFP, City of Rockville will not accept separate Proposals from the JV constituents. A firm will not be permitted to submit on more than one (1) JV for this RFP. Also, a firm that responds to this RFP as a prime or a prime JV constituent may not be included as a designated subcontractor to another firm that responds as a prime to this RFP. Multiple responses under any of the foregoing situations may cause the rejection of <u>all</u> responses of the firms involved. The above does not preclude a firm that has not submitted as a prime from being set forth as a designated subcontractor to more than one (1) prime responding to this RFP.

All proposals received for this contract will be reviewed on a competitive basis. The Firm that submits the highest rated Technical Proposal will be requested to submit a Price Proposal. Salary, Payroll Burden, and Overhead limitations have been eliminated. Salaries shall be actual per-hour salary rates as supported by Certified Payroll Rosters while Prime and Subconsultants' Payroll Burden and Overhead rates shall be supported by either a Maryland Department of Transportation Modes approval letter or by an annual overhead audit performed by an independent Certified Public Accountant in accordance with Federal Acquisition Regulations 48 Code of Federal Regulation 1, Part 31 and applicable MDOT guidelines. The annual overhead audit shall identify separate rates for

both home office overhead and field overhead. If negotiations with the Firm is timely and successful, a contract may be awarded to the Firm.

The City of Rockville shall comply with procurement requirements established in State and local laws, regulations, policies and procedures that are not addressed by or are not in conflict with applicable Federal regulations, as specified in 2CFR Part 1201. When state and local procurement laws, regulations, policies, or procedures are in conflict with applicable Federal laws and regulations, a contracting agency shall comply with Federal requirements to be eligible for Federal-Aid reimbursement, as specified in 2CFR200.102.

Each Offeror is requested to indicate its eMMA vendor number in the Transmittal Letter (cover letter) submitted at the time of its Proposal submission to this RFP.

Before a business entity can do business in the State of Maryland, it must be registered with the State Department of Assessments and Taxation (SDAT). SDAT is located at State Office Building, Room 803, 301 West Preston Street, Baltimore, Maryland 21201. The SDAT website is http://sdat.dat.maryland.gov/RealProperty/Pages/default.aspx, It is strongly recommended that any potential Offeror complete registration prior to the due date for receipt of Proposals. An Offeror's failure to complete registration with SDAT may disqualify an otherwise successful Offeror from final consideration and recommendation for contract award.

Technical Proposals must be submitted in the format outlined within the SHA Standard Request for Proposals guidelines. The SHA Standard Request for Proposals guidelines can be found on the SHA Web Page at https://roads.maryland.gov/mdotsha/pages/Index.aspx?PageId=767 by navigating to the Standard Request for Proposals link.

The SHA, in accordance with the provisions of Title VI of the Civil Rights Act of 1964 (78 Stat. 252, 42 U.S.C §§ 2000d to 2000d-4) and the Regulations, hereby notifies all offerors that it will affirmatively ensure that any contract entered into pursuant to this RFP, Disadvantaged Business Enterprises (DBE) will be afforded full and fair opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin, in consideration for an award.

Consultants interested in submitting a Technical Proposal must comply with the SPECIAL PROVISIONS, AFFIRMATIVE ACTION REQUIREMENTS, UTILIZATION OF DISADVANTAGED BUSINESSES, THE SURFACE TRANSPORTATION AND UNIFORM RELOCATION ASSISTANCE ACT OF 1987, ISTEA OF 1991, MAP 21 OF 2012, FAST ACT 2015, AND INFRASTRUCTURE INVESTMENT AND JOBS ACT OF 2021 located at https://roads.maryland.gov/mdotsha/pages/Index.aspx?PageId=767 and selecting Standard Request for Proposals link).

City of Rockville hereby notifies all bidders/offerors that regarding any contract entered into pursuant to this RFP, the contractor, sub recipient or subcontractor shall not discriminate on the basis of race, color, national origin, or sex in the performance of this contract. The contractor shall carry out applicable requirements of 49 CFR part 26 in the award and administration of DOT-assisted contracts. Failure by the contractor to carry out these requirements is a material breach of this contract, which may result in the termination of this contract or such other remedy as the recipient deems appropriate, which may include, but is not limited to:

- (1) Withholding monthly progress payments;
- (2) Assessing sanctions;
- (3) Liquidated damages; and/or
- (4) Disqualifying the contractor from future bidding as non-responsible.

It is the goal of MDOT that disadvantaged business enterprises (DBE) participate in all federal-aid contracts. Each contract will be evaluated for the placement of a goal for DBE participation on a contract-by-contract basis. MDOT certified DBE firms are encouraged to respond to this solicitation. The MDOT MBE website is https://www.mdot.maryland.gov/tso/pages/index.aspx?pageid=91.

Technical Proposals received after the deadline time will not be accepted, no matter how transmitted, and will be returned unopened to the Consultant.

SHA reserves the right to reject any and all Proposals received in response to this request and is not liable for any cost incurred by any Firm in connection with the preparation and presentation of Proposals.

REQUEST FOR PROPOSALS (RFP) DOCUMENTS

The RFP documents are available via the City's Collaboration Portal and via eMarylandMarketplaceAdvantage under BPM053811:

Contract Insight - Collaboration Portal (rockvillemd.gov)

https://emma.maryland.gov/

PRE-PROPOSAL MEETING AND WALK-THROUGH

A virtual, telepresence pre-proposal meeting will be held on TUESDAY, NOVEMBER 04, 2025, AT 02:00 PM (EDT). Offerors must register below in order to attend the meeting. This meeting is not mandatory; however, offerors are strongly encouraged to attend. Individuals interested in viewing the vicinity of the work are encouraged to do so independently, and in a socially distanced manner, prior to the pre-proposal meeting. Offerors shall assume complete responsibility and liability for any and all visits.

Register for Virtual Pre-Proposal Meeting Here: Register

SUBMITTAL OF QUESTIONS

Technical and contractual questions pertaining to this RFP may be directed to Jonathan Pierson, CPSM, C.P.M., Assistant Director, via the City's Collaboration Portal no later than **WEDNESDAY**, **NOVEMBER 12**, **2025**, **BY 2:00 P.M. EDT**. Oral answers to questions relative to interpretation of requirements or the proposal process will not be binding on the City.

To ensure fair consideration for all offerors, any interpretation made to prospective offerors will be expressed in the form of an addendum to the requirements, if such information is deemed necessary for the preparation of proposals or if the lack of such information would be detrimental to the uninformed offeror. Such addendums, if issued, will posted at the City's Collaboration Portal listed below and in the eMarylandMarketplaceAdvantage portal under BPM053811:

Contract Insight - Collaboration Portal (rockvillemd.gov)

https://emma.maryland.gov/

Please note, that it is the proposer's responsibility to check this site frequently for Addendums, which may impact pricing, this documents requirements, terms and/or conditions. Failure to sign and return an Addendum with your response may result in disqualification of proposal.

PROJECT DESCRIPTION

The City of Rockville is seeking consultant assistance to perform professional engineering services to design a shared-use path along the southside (eastbound) of Fleet Street between Maryland Avenue and the westernmost entrance to Richard Montgomery High School and along the westside (southbound) of Monroe Street between E. Middle Lane and Fleet Street as part of city's pedestrian and bicycle safety capital improvement program. The project's scope of work includes Planning, Preliminary Design, and Final Design services. SHA may award one project-specific contract for these services. The duration of the contract will not exceed thirteen (13) months. The total funding authority for this contract shall not exceed \$390,945.00. No minimum amount of work or funds is guaranteed under this contract. All work performed under this contract must be for services as outlined in the contract scope of work and in conformance with all contract terms and conditions and payment provisions.

AWARD

Upon receipt of technical proposals, the City of Rockville shall rate and rank the proposals on the basis of the evaluation factors published in the Request for Proposal and select the offeror whose professional qualifications and proposed services are deemed most meritorious. The City will then review the selected offeror's price proposal,

after which, negotiations shall then be conducted, with the offeror. If a contract satisfactory and advantageous to the City can be negotiated at a price considered fair and reasonable, the award shall be made to that offeror. If price negotiations with the offeror ranked first are not successful, negotiations shall be formally terminated and negotiations conducted with the offeror ranked second most meritorious, and so on, until such a contract can be negotiated at a fair and reasonable price.

NOTICE TO OFFERORS/PROPOSERS

"Pursuant to 7-201 et seq of the Corporations and Associations Article of the Annotated Code of Maryland, corporations not incorporated in the State shall be registered with the State Department of Assessments and Taxation, 301 West Preston Street, Baltimore, MD 21201 before doing any interstate of foreign business in this State. Before doing any intrastate business in this State, a foreign corporation shall qualify with the Department of Assessments and Taxation." Offerors must supply with their bids their US Treasury Department Employer's Identification Number as such number is shown on their Employer's Quarterly Federal Tax Return (US Treasury Department Form No. 941). Companies located outside Maryland should call 1-410-767-1006, or e-mail: charterhelp@dat.state.md.us.

QUALIFICATIONS TO CONTRACT WITH PUBLIC BODY

Offerors must be qualified to bid in the state in accordance with Section 14-308 of the State Finance and Procurement Article of the Annotated Code of Maryland which ordains that any person convicted of bribery (upon acts committed after July 1, 1977) in furtherance of obtaining a contract from the State or any subdivision of the State of Maryland shall be disqualified from entering into a contract with the City.

EXPENSES ASSOCIATED WITH RESPONSE

The City of Rockville will not be responsible for any expenses incurred by a firm in preparing and submitting a proposal. All proposals shall provide a straightforward, concise delineation of the firm's capabilities to satisfy the requirements of this request. Emphasis should be on completeness and clarity of content.

REJECTION OF PROPOSALS

The City reserves the right to reject any or all proposals in part or in full and to waive any technicalities or informalities as may best serve the interests of the City.

DISABILITY INFORMATION

Any individuals with disabilities who would like to receive the information in this document in another form may contact the ADA Coordinator at (240) 314-8100; TDD (240) 314-8137.

W-9 FORM REQUIRED

Successful respondents are required to complete and submit a W-9 Form. The W-9 form can be accessed at: http://www.irs.gov/pub/irs-pdf/fw9.pdf?portlet=3. It is the successful respondent's responsibility to act upon this instruction for submitting a W-9 form. The City will not be able to process payments if this form is not completed and submitted to the Purchasing Division.

NO CONTACT POLICY

Unless otherwise stated, any contact with any City official, employee, agent, or other representative concerning this Request for Proposals other the assigned buyer or procurement representative is prohibited. Any such unauthorized contact may disqualify the proposer from this procurement.



Section 1: Project Overview

_	of Work and Technical Requirements	09
	al Instructions for Proposal Preparation and Delivery	21
Section 4: Evalua A.Proposal Evalua	tion Criteria	28
Attachments		
Attachment A	Feasibility Study	
Attachment B	City of Rockville Maryland General Conditions And Instructions	19
Attachment C	Insurance	205
Attachment D	Certification for Contracts, Grants, Loans, and Cooperative Agreements	20
Attachment E	References	
Attachment F	Affidavit	209
Attachment G	Questionnaire	210



CITY OF ROCKVILLE ROCKVILLE, MARYLAND

REQUEST FOR PROPOSAL #27-25 FLEET STREET AND MONROE COMPLETE STREETS PROJECT MOA88B21

SECTION 1

PROJECT OVERVIEW

The City of Rockville is issuing this Request for Proposals (RFP) for the Fleet Street and Monroe Street Shared-use Path design Project. The City of Rockville seeks professional engineering services to design a shared-use path along the southside (eastbound) of Fleet Street between Maryland Avenue and the westernmost entrance to Richard Montgomery High School and along the westside (southbound) of Monroe Street between E. Middle Lane and Fleet Street as part of city's pedestrian and bicycle safety capital improvement program. The Consultant Firms shall be proficient in the services listed in this RFP and shall bring an experienced and expert staff to the contracts as required. Firms interested in being considered must submit a complete Standard Form (SF) 330 concurrent with the technical proposal.

City of Rockville anticipates awarding one project-specific contract for these services. The duration of the Contract will not exceed thirteen (13) months. The total funding authority for this contract shall not exceed \$390,945.00. City of Rockville reserves the right to modify the total funding authority. No minimum amount of work or funds is guaranteed under this Contract. The Contract will be funded with Federal Aid Highway Program (FAHP) grant funds administered by the Federal Highway Administration, with assistance from the Maryland State Highway Administration.

An Offeror, either directly or through its subcontractor(s), must be able to provide all services and meet all the requirements requested in this solicitation and the successful Offeror (the Contractor) shall remain responsible for Contract performance regardless of subcontractor participation in the work. Firms interested in being considered for work on these contracts must submit a Technical Proposal for the contract as set forth herein.

The procurement of engineering and design related services funded by FAHP funds shall be conducted in with competitive negotiation (qualifications-based selection) procedures in accordance with the Brooks Act codified under 40 U.S.C. 1101-1104. The Contract resulting from this solicitation shall be structured as project-specific and payment methods shall include cost plus fixed fee and unit cost rates. Additional information regarding payment methods will be provided to the selected firm in the Request for Price Proposal. To standardize the method of proposal submission, and to facilitate distribution of proposal materials, it shall be necessary that all firms observe the following procedures.

Consultant Services Required

The services to be performed under this contract will provide final engineering designs for the shared-use path based on the preferred alternative taken from the previously prepared feasibility study and prepare construction documents to be bid publicly by the City of Rockville.

Through a Metropolitan Washington Council of Governments Transportation Land Use Connections project, a consultant conducted a feasibility study for a complete streets/road diet project to provide bicycle facilities along the project extents. This study included analysis of traffic patterns and increased congestion, conceptual design, and public outreach. Repurposing a motor vehicle travel lane and installing a shared-use path along these sections will provide an enhanced pedestrian connection and a new bicycle connection to multiple Rockville Town Center destinations, including a Metrorail Station, county and city offices, a public high school, multiple older adult

residential communities, a residential community for persons with disabilities, and retail and commercial offices. The completed feasibility study is attached herein (Attachment A).

The consultant prepared two concept alternatives: an on-street separated cycle track and an on-street side path. This study was completed in June 2023. The city deemed the "side path" option as the preferred alternative, with support from the community. Also proposed in this alternative included signal and intersection improvements to the intersections Fleet Street and Monroe Street and Monroe Street and E. Jefferson Street (MD 28), a state owned and maintained intersection.

To accommodate the shared-use path, a motor vehicle travel lane will be repurposed from both Fleet Street and Monroe Street. A new roadway alignment is required as are modifications to the traffic signals and phasing at Fleet and Monroe streets and Monroe and E. Jefferson (MD 28) streets. Signal plans should provide for non-motorized users while minimizing impact to motorists. The intersection of Monroe and E. Jefferson (MD 28) streets should consider a bicycle signal if approved by the Maryland Department of Transportation.

The shared-use path should be designed to be at least ten feet wide. The west terminus of the Fleet Street shared-use path should allow a transition between on-road bicycles to use the trail and separate pedestrians and bicyclists as much as possible at the transition. The east terminus of the Fleet Street shared-use path should seamlessly connect into the existing shared-use path along Fleet Street in front of Richard Montgomery Highschool. The north terminus of the Monroe Street shared-use path should lead pedestrians and bicyclists to the existing E. Middle Lane crossing just west of Monroe Street.

All the plans should be prepared in accordance with the latest standards, specifications, book of standards, and guidelines of the Maryland State Highway Administration and other latest road design guidelines.

The Contractor shall prepare and submit construction plans, cost estimates, and construction specifications for the complete streets/road diet project for Fleet Street and Monroe Street. The documents shall include the removal of a travel lane on each roadway, the installation of a shared-use path on the south side of Fleet Street and on the west side of Monroe Street, and intersection improvements and signal modifications at the intersections of Fleet Street and Monroe Street, and Monroe Street and E. Jefferson Street (MD 28). The construction plans shall include general notes; typical sections; construction details; roadway plans showing the revised curb and gutter, shared use path, landscape buffer, and storm drain; storm drain profiles and structure and pipe schedule; signing and marking plans, vertical profiles, as necessary; streetlight plans, utility relocation plans, maintenance of traffic plans, traffic signal plans, Forest Conservation Plan (FCP), erosion and sediment control plans, storm water management plans, landscape plans, and all other plans necessary to complete the project.

All pedestrian facilities, such as sidewalk ramps, crosswalks, sidewalks, and shared-use paths shall be designed for compliance with the most recent ADA regulations and PROWAG standards.

It is expected that this project will be completed within 13 months from the date of purchase order and would approximately follow the project schedule listed below.

The firm may be authorized to subcontract for specialty services with prior approval of City of Rockville. The firm shall be proficient in the services and shall bring an experienced and expert staff to the project.

Listed below is the Scope of Services and Examples of Work, Certifications and Engineering Standards and Guidelines.

SECTION 2 Scope of Work and Technical Requirements

Scope of Services and Examples of Work:

The plans shall utilize the recommended concept #1 from the Fleet and Monroe Streets feasibility study, as well as City's standard notes, borders, and details when applicable. The design shall include the shared use path alignment and all associated proposed grading as a result of the shared use path. The plans shall provide details for all restoration to include the repair of driveway aprons, curb and gutter, pavements, and all disturbed areas. All impacts to trees, landscaping, utilities, or any other appurtenances shall be noted in the plans with instruction to the Consultant. Limits of disturbance shall be included and will be based on the proposed grading. Attention must be placed on existing utilities in order to effectively plan the design around their locations, or alternatively to coordinate relocation of utilities with utility companies during the design process. The plans must be prepared and sealed by a Professional Engineer, licensed in the state of Maryland.

The Consultant shall clearly state whether they intend to sub-contract any portion of the work herein. The names of all subconsultants together with a description and anticipated percentage of the work being sub-contracted are to be provided. The description also shall include a detailed breakdown of the cost with hours and rates for the tasks to be completed by the subconsultant. The Consultant assumes full liability for the performance of all subconsultants.

As part of this Task Order, the Consultant must warrant that it will not engage in providing consulting or other services to any private entity regarding the property within the project area during the term of the project. This requirement is intended to avoid the appearance of any conflict of interest that may arise.

DPW will assist the successful Consultant by providing applicable background information from record files, if available; as well as general guidance and liaison services to other City agencies.

Services to be provided will include:

1) Field Visit and Background Review

A thorough review of the existing conditions and background research is necessary. The Consultant shall:

- a) Review the completed feasibility study.
- b) Conduct a thorough field visit with City staff to identify existing conditions, evaluate existing infrastructure, determine constraints, and discuss layout options. The consultant is responsible for field verification.
- c) Conduct a discussion with Maryland Department of Transportation State Highway Administration staff to identify existing conditions, constraints, and possible signal, phasing, and intersection improvements for the intersection of Monroe Street and E. Jefferson Street (MD 28).

2) Survey

A detailed survey of the project vicinity showing existing conditions and features is required. Refer to "Attachment A" for the survey project limits. The survey should include both sides of the road. The survey should include the complete rights-of-way along Fleet Street and along Monroe Street and should extend beyond the rights-of-way to other areas where there might be drainage issues, tree impacts, or temporary property easements.

Survey services to be provided shall include the preparation and submittal of utility information request letters to any and all utility companies who have existing or known proposed facilities within the project limits. It may be necessary to coordinate beyond the initial letter with utility companies in order to collect utility information. The design should account for all utilities to allow for planning and coordinating possible relocations during the design phase.

The Consultant will need to enter adjacent private property to obtain survey information for this project. Consultant is responsible for notifying affected property owners via a door hanger or other written notification 48 hours prior to accessing private property. Written notification shall include a phone number and email contact for property owners who wish to 'opt out' and deny the Consultant access to their property. Consultant shall also attempt to notify property owners the day of surveying by knocking on the door prior to entering the

property for surveying. The Consultant shall provide the City with a plan or list of those properties to be notified.

Digital files shall be provided to the City in Microstation CAD or AutoCAD format, and in PDF. Surveys must be completed and signed by a Professional Land Surveyor, duly registered in the State of Maryland.

The survey shall include the following:

a) Detailed Survey:

- i) Public right-of-way and easement lines;
- ii) Property lines, addresses and owners;
- iii) Elevations and topography;
- iv) Roadway features (streetlights, medians, pavement markings, crosswalks, speed bumps, curb and gutter, pavement, sidewalks, signal poles, signal boxes, signal loops, signs, handicap ramps, driveways, aprons and lead walks, etc.);
- v) Environmental features (trees, shrubs, landscaping, etc.);
- vi) Existing utilities (water lines and valves, water meters, sewer lines, manholes, cleanouts, water and sewer house connections, storm drain pipes and inlets, gas lines and valves, power poles, guy wires, overhead wires, etc.);
- vii) All other features (fences, steps, walls, handrails, etc.);
- viii) Survey must be completed by a Professional Land Surveyor, registered in the State of Maryland;
- ix) Elevations and topography must be based upon a field run survey;
- x) The horizontal datum of the survey shall be based on grid north, Maryland State Plan Coordinate System North American Datum 1983/1991. The vertical datum shall be based on North American Vertical Datum, 1988 adjustment (NAVD 1988);
- xi) Provide two permanent benchmarks (outside of the project LOD) with horizontal and vertical control for construction and stakeout by others;
- xii) Existing contours at 1' intervals;
- xiii) Use standard base sheets provided by the City to plot final construction drawings at 20 scale or some other appropriate scale approved by the City; DPW's current CAD system is AutoCAD Civil 3D 2014.

b) Utilities:

- i) Subsurface Utility Engineering Quality Level B, as defined here: http://www.fhwa.dot.gov/programadmin/sueindex.cfm
- ii) All surface utility features (valves, valve boxes, manholes, inlets, etc.) must have top elevations, and inlet size of throat.
- iii) Sanitary Sewer and Storm Drain Systems must have field recorded invert elevations in and out, pipe size and material type.
- iv) MISS UTILITY must be called to locate all utilities prior to field surveying.

c) Tree Survey:

- i) All trees within fifty (50) feet of the LOD should be surveyed.
- Locate, identify and show all trees 2" or greater in diameter (DBH) located within the right of way and all trees 6" or greater DBH within 25' from the anticipated limits of disturbance.
- iii) Graphically show the critical root zones (CRZ's) for the above trees under #18 as 1.5 foot of CRZ radius for every 1.0" of DBH.
- iv) Include separate tree tables (right of way trees and private trees) showing the tree number corresponding to the plan with the type (common name), size (DBH) and condition rating.
- v) Provide a Natural Resources Inventory (NRI), consistent with the City of Rockville requirements.
- vi) The tree survey shall be prepared by an ISA Certified Arborist and will be reviewed by the City Forester's office. The tree survey may be prepared on separate sheets to enable readability of the plan.

3) Design Plan

The design plans at all submissions (30%, 60%, and 90%) shall utilize the city's standard notes, borders, and details when applicable. The plans shall use a base plan based on all detailed surveys, existing plans, and aerial maps. Plans should be inclusive of a title sheet, general notes sheets, necessary construction plan sheets for each roadway, intersection, and applicable details and standards.

The Consultant shall submit design plans at all submissions (30%, 60%, and 90%) in Microstation CAD or AutoCAD format and viewable in PDF.

The design plan shall include the following:

Compliance with construction specifications and standards, including all subsequent addenda, amendments, errata, and updates.

- Maryland Department of Transportation, State Highway Administration, "Standard Specifications for Construction and Materials", latest edition. MDSHA Book of Standards for Highway and Incidental Structures.
- Montgomery County Department of Transportation, "Montgomery County Road Construction Code and Standard Specifications."
- Montgomery County, "Complete Streets Design Guide."
- Montgomery County Storm Drain Design Criteria.
- Standard Specifications of WSSC dated July 2013, or latest edition.
- Montgomery County Department of Transportation, "Design Standards."
- Maryland Department of the Environment "2011 Standards and Specifications Soil Erosion and Sediment Control."
- The State of Maryland Department of Transportation, "Manual on Uniform Traffic Control Devices."
- American Association of State Highway and Transportation Officials, "AASHTO Design Guidelines", latest edition
- American Association of State Highway and Transportation Officials, "Guide for the Development of Bicycle Facilities,"
- Montgomery County Noise Ordinance.
- Rockville City Code.

a) Civil Plans

- i) Grade establishment
 - (1) Horizontal and vertical geometric alignments of the roadway, sidewalk, shared-use path, and all facilities within the right of way.
 - (2) Roadway centerlines with stationing at 50 foot intervals. Include all right-of-way lines, property lines, curb and gutter and paving lines. Include the paving and right of way width, as well as the sidewalk and driveway widths. Include the stations of PC, PT of fillets, high and low points.
 - (3) Proposed stations and centerline elevations at 50 foot intervals, and at 25 foot intervals in vertical curves. Include proposed stations and centerline elevations at intersections, and connections with proposed roads and existing roads. Include the stations and elevations of PVC, PVT, and PVI. Include the stations and elevations of high points, low points, and grade breaks. Include existing and proposed culverts and pipe crossings. Proper sight distance and vertical curve length shall be based on AASHTO requirements.
 - (4) Stations shall increase in south-to-north and west-to-east fashion
 - (5) Cross sections shall be prepared through the right of way and beyond tying the proposed grade to existing grade and showing all horizontal dimensions, material, grade breaks, slopes, and elevations. The sections shall be prepared at each driveway and at high and low points of the road's centerline, or at a minimum spacing of 50 feet.

ii) Streetscape

- (1) Utility/streetlight pole location.
- (2) Existing/planned trees.
- (3) All proposed landscaping and buffers.
- (4) Parking meter locations and street furniture

- (5) Bus stops and bus stop facilities.
- (6) Shared-use path, sidewalks and curb ramps, and retaining walls.
- (7) Curb and gutter.
- (8) Limit of Disturbance

iii) Storm drain and paving

The Consultant shall prepare and submit public improvement plans for City utilities utilizing the following assumptions and minimum requirements:

- (1) All existing curbs and gutters, paving, and sidewalks, as well as all utilities and infrastructure, and buildings. Make existing features lighter or screened from proposed improvements.
- (2) Streams, drainage ways, wetlands, and the 100-year floodplain.
- (3) Drainage area map including all areas, right-of-way and offsite, which drain through project limits.
- (4) Storm drain pipe size shall be sized to convey the 10-year storm event.
- (5) Storm drain pipe schedule showing lengths, pipe sizes, materials, and class or gauge. Include a structure schedule showing structure types, stations, offsets from centerline elevations, dimensions. Include structure numbers on plan to match structure schedule, pipe profiles, and drainage study. Show the 10- and 100-year WSEL at sump inlets and overflow path for runoff. Include details of special structures. Show direction of safe over land flow with flow arrows.
- (6) Storm drain profiles with structure numbers to match the plan, structure schedule, and drainage study. Show pipe lengths by stationing at each structure. Include the pipe size, material, slope, and class or gauge for each run. Include pipe inverts, discharge, velocity, and friction slope. Show existing and proposed grades. Label streets at the centerline where the pipe crosses the street. Show the hydraulic gradient. Provide a minimum of one foot clearance between all pipes (storm drain, water, sewer, dry utilities). Provide adequate cover over pipes. Show 10-year and 100-year WSEL at outfalls
- (7) Adequate inlet spacing, sizing, spread, stable discharge area, storm drain pipe computations and spread computations for the 10-year Hydraulic Grade Line for any new storm drainage system.
- (8) Assume no downstream improvements are required.
- (9) All necessary storm drain computations shall be submitted as a design study and report.
- (10) City of Rockville DPW standard notes, details, and Paving and/or Storm Drain Plan Review checklist shall be utilized.
- (11) Proposed storm drain must be designed in accordance with Montgomery County Drainage Design Criteria.
- iv) The Consultant shall submit, obtain approval, and receive any required permits, including access and maintenance of traffic permits, for construction within the MDOT SHA right-of-way from the MDOT SHA District 3 Office of Construction for the proposed project.

b) Optional Task: Water and Sewer

At this point in time, it is unclear if water and sewer will require relocation. Following detailed survey with locations of existing utilities, and the preliminary curb and shared-use path alignment as developed, the determination for water and sewer relocation will need to be made. Should water and sewer relocations be necessary, the Consultant shall prepare and submit public improvement plans for City utilities utilizing the following assumptions and minimum requirements:

- i) Proposed water and sewer relocation requirements:
 - (1) Existing watermains shall be relocated outside of the proposed shared use path and curb line so as to be accessible for maintenance. Watermains should be located seven (7) feet off centerline of proposed curb and gutter.
 - (2) Existing fire hydrants shall be relocated into the proposed grass buffer in accordance with WSSC Pipeline Design Manual and Standard Details for Construction, 2' from the face of curb or no more than 7' from the face of curb.

- (3) Proposed water and sewer must be designed in accordance with WSSC Pipeline Design Manual and Standard Details for Construction. City of Rockville DPW standard notes, details, and Water and Sewer Review checklist shall be utilized.
- ii) Water and Sewer Pipe and Structure Schedule with material list.

c) Stormwater Management (SWM)

The Consultant shall prepare and submit a Combined Pre-Application and Development SWM Concept, in accordance with Chapter 19 of the City Code, including the requirement to provide SWM via Environmental Site Design (ESD) to the Maximum Extent Practicable (MEP). The SWM Concept shall be developed utilizing the following assumptions:

- i) The project will be considered a "Redevelopment" for the SWM Ordinance purposes.
- ii) SWM must be provided for the new and replaced impervious areas within the project Limit of Disturbance.
- iii) At a minimum, SWM control must be provided for Water Quality Volume (WQv), Channel Protection Volume (Cpv), and Overbank Flood Protection Volume (Qp10). Extreme flood control SWM is not required.
- iv) SWM must be provided in accordance with priorities established by the code in Sec. 19-44. ESD is the first priority, followed by a structural water quality system and then Alternatives as described in Sec. 19-50, including monetary contribution.
- v) For development of the concept, the Consultant shall investigate underground structural facilities. Include information to support the vertical aspects of the SWM System which may include existing and proposed inverts at critical locations and/or schematic profiles based on field verified information. Water quality storm drain devices must be located to allow easy access and maintenance and may not be located on a trunk line. Provide adequate utility clearances, including minimum of one foot clearance between all pipes (storm drain, water, sewer, dry utilities).
- vi) Provide adequate justification if it is not feasible to provide ESD or other SWM measures within the right-of-way.
- vii) Geotechnical testing will not be required during SWM concept stage. The concept should utilize the USDA NRCS web soil survey map and data to identify soil type. Section I Geotechnical Report, as detailed in the Stormwater Management Concept Checklist, will not be required.
- viii) The concept should present measures to treat the target P_E but a minimum of 1-inch must be treated by ESD measures, structural systems, alternatives or a combination of the three.

Minimum SWM requirements shall be established by the City of Rockville Chief of Engineering in conjunction with the review and approval of the Combined SWM Concept.

d) Optional Task: Approved Storm Water Design

Until concept approval, the extent of effort for the SWM design is unknown. The proposal shall include the following task as an optional item:

- i) Preparation of construction drawings, specifications, and cost estimates for SWM shall be provided as a separate cost for all approved SWM measures and alternatives. When the concept is approved, if necessary, the relevant option(s) will be authorized, and the design will be completed for those elements, at the cost provided.
- ii) Based on the approved Stormwater Management design plan, the consultant shall prepare and submit a Stormwater Management Permit Application to the Engineering Division of DPW.

e) Forest Conservation Plan

- i) The Forest Conservation Plan (FCP) is to be included in and submitted with all submissions. The submission shall include the FCP checklist and application.
- ii) Limits of disturbance including staging areas, locations of sediment control measures and tree protection fence, proposed grading, utility relocations, any other improvements proposed by the project (signs, aprons, etc.).
- iii) Existing trees from the Tree Survey and all tree removals. All trees within fifty (50) feet of the LOD shall be surveyed.

- iv) Tree mitigation measures such as root pruning, crown elevating, etc., as applicable, for trees to be saved.
- v) An updated tree table showing the disposition as either "save" or "remove" for all trees shown on the Tree Survey as well as the number of replacement trees owed (right of way trees replaced at 1:1, private trees replaced per the City's Forest and Tree Preservation Ordinance).
- vi) Tree replacement planting locations and a plant list with specific tree types and sizes (2.5" caliper for shade and ornamental trees and 7-8' high for evergreen trees) for all replacement trees owed.
- vii) This project is not subject to afforestation.
- viii) The Forest Conservation Plan shall demonstrate compliance with the City of Rockville Forest and Tree Preservation Ordinance (FTPO) and Forest Conservation Manual.
- ix) The NRI/FSD or existing conditions plan should accompany the Forest Conservation Plan.
- x) Based on the approved Forest Conservation Plan, the consultant shall prepare and submit a Forestry Permit Application to forestry reviewers within the Department of Community Planning and Development Services in accordance with the application requirements.

f) Utilities

- i) Non-City Utilities: At the onset of the project, the Consultant shall request as-built plans from utility companies (PEPCO, Washington Gas, Comcast, and Verizon). The Consultant's design plans shall include all utilities existing along the right-of-way and beyond within surveyed area. At the 30% design phase, utility conflicts shall be identified and shared with private utilities. Final plans shall incorporate private utility relocation plans, if necessary. In the event of impact to utilities within the State Highway Administration right-of-way, the Consultant shall determine the date the right-of-way was acquired by the utility company (or the date said utility was installed), and the date the State/Public acquired the right-of-way.
- ii) City Utilities Water and Sewer: Rockville provides water and sewer along both Fleet Street and Monroe Street. Consultant must coordinate with each utility to ensure proper relocations, as necessary. See section 3b for further discussion of water and sewer.
- iii) Hiring of a utility consultant should be considered by the applicant if they do not have the expertise inhouse

g) Signing and Marking

- i) Existing signs, pavements markings, traffic control devices, parking spaces, buffers, etc.
- ii) Proposed signs and pavement markings, traffic control devices, parking spaces, transition areas, buffers, etc.

h) Traffic Signal

- i) Traffic signal plans for Fleet Street & Monroe Street and for Monroe Street & E. Jefferson Street (MD 28).
- ii) Existing and proposed traffic equipment, signs, and wire.
- iii) Right-of-way.
- iv) Phasing diagrams.
- v) Wiring diagrams.
- vi) Interim approvals per MUTCD for potential improvements, if necessary.
- vii) The Consultant shall submit, obtain approval, and receive any required permits for the traffic signal plans from the MDOT SHA, Montgomery County Department of Transportation, and the MDOT SHA District 3 Office of Construction for the intersection of Monroe Street and E. Jefferson Street (MD 28).

i) Erosion and Sediment Control Plan (SCP)

As part of the construction drawings, the consultant shall propose measures for adequate sediment and erosion control during the construction of this project. The erosion and sediment control plans shall be submitted with the 60% and 90% design plan submissions and shall include:

- i) limits of disturbance,
- ii) sediment control measures (silt fence, inlet protection, etc.),
- iii) sequence of construction, including construction access, phasing, staging and detailed description of steps to complete the project.
- iv) appropriate sediment control notes and details.

v) Owner/developer certifications and must be coordinated with the Forest Conservation Plan and utilize the same scale.

Based on the approved Preliminary Sediment Control Plan, the consultant shall prepare and submit a Sediment Control Permit Application to DPW along with the sediment control plans, appropriate checklists, and computations for review and approval by DPW Engineering Division.

The plans must be prepared and sealed by a Professional Engineer, licensed in the state of Maryland.

j) Maintenance of Traffic (Traffic control plan)

- i) To be submitted with the 60% and 90% design plan submissions.
- ii) Flow of traffic for motor vehicles, pedestrians, bicyclists, and transit.
- iii) Detours for all modes according to construction phasing.
- iv) Proposed construction access to site and site utilization (stockpiles, employee parking, etc.)
- v) Pedestrian and vehicular access to adjacent buildings and property must be maintained throughout construction.

k) Cost Estimate

- i) To be submitted with all submissions.
- ii) Final cost estimate shall match the itemized pay items and estimated quantities included in the plan, and exactly as shown on the bid sheet.

4) Meetings

- a) Kick-off meeting to be hosted virtually by Consultant within three weeks of purchase order.
- b) Monthly status meetings hosted by virtually by Consultant for the duration of the project.
- c) 30% design review meeting hosted by virtually by Consultant.
- d) 60% design review meeting hosted by virtually by Consultant.
- e) 90% design review meeting hosted by virtually by Consultant.

f) 30% design public meeting.

- i) Prepare slide presentation for one virtual public meeting to occur after 30% design review meeting.
- ii) Attend public meeting and compile meeting notes including all submitted public comments.

g) 90% design public meeting

- i) Prepare one set of printed plans.
- ii) Attend in-person public meeting and support city staff, including taking notes and recording comments from the public.
- iii) In-person public meeting will be held as a "walk-n-roll-the-block" style meeting.

5) Technical Specifications and Bid Documents

- a) To be submitted at 60%, 90% and with the final design plan submission.
- b) City will be responsible for compiling the Invitation For Bid (IFB),
- c) Consultant to prepare the technical specifications and methods of measurement for all proposed pay items to comprise Section 4 of the city's standard IFB.
- d) Consultant shall provide the city with any unique special provisions for the project, should they be necessary to convey the intent of the work required, which will be incorporated into Section 3 of the city's standard IFB.
- e) Consultant shall provide the pricing bid sheet of all pay items and estimated quantities for use in the final IFB, based on the format as provided by the city.

6) Construction Phase Tasks

Some construction phase involvement is requested. As the amount of involvement necessary is not currently known, estimates of hours for the project engineer to be included in the quote and proposal have been included below. If after award, it becomes apparent that these amounts need to be modified, a change to the purchase order can be made. The following tasks shall be included in the submitted quote and proposal as optional services:

a) Optional Task: Review of shop drawings

Review drawings for any aspect of the engineer's design prior to any fabrication, if required. Allocate 40 hours of time to be used, as necessary.

b) Optional Task: Construction Inspection Services

Provide construction inspection services during construction. Allocate 200 hours of time to be used, as necessary, for attendance at the pre-construction meeting, monthly progress meetings, responding to questions during construction, review/approve change orders, develop punch list, making site visits when requested, and the development of plan revisions.

Note: It is the engineer's responsibility to identify and include any additional items in the submitted Cost Proposal necessary to complete the work anticipated by this task order. The City recommends the proposers visit these intersections prior to submitting the Cost Proposal to identify any items beyond those listed in this request for quote. Items added must be clearly identified in the tasks and cost proposal.

Expected Deliverables

All design plan elements listed above are to be submitted at the 30%, 60%, 90%, and final design submissions, unless noted above.

1) Submittal One – 30% Design

This submittal shall be 30% design plans that incorporate the concept plans developed previously for a road diet and shared use path along Fleet Street between Maryland Avenue and Richard Montgomery High School, and along Monroe Street between Fleet Street and E. Middle Lane. The City will require the Consultant to address all comments from the 30% plans identified through the City's review of the submittal. City approval of these plans will allow the Consultant to proceed with the preparation of the 60% plan.

2) Submittal Two – 60% Design

This submittal shall address all issues and/or comments raised during the City review of the 30% design. It shall include complete construction plans including all details, notes, and specifications required to complete the project, and an updated estimate. It shall also include the first draft of the technical specifications and other bid documents. The City will require the Consultant to address all comments from the 60% plans identified through the City's review of the submittal. City approval of these plans will allow the Consultant to proceed with the preparation of the 90% plans.

3) Submittal Three – 90% Design

This submittal shall address all issues and/or comments raised during the City review of the 60% design. It shall include complete construction plans including all details, notes, and specifications required to complete the project, and an updated estimate. City approval of these documents and plans allow the Consultant to proceed with the preparation the final construction plans and bid documents. Design plans, construction specifications and cost estimates shall be included in the 90% Design submittal.

4) Submittal Four – Final Design

Final Design: The final submittal shall address all issues and/or comments raised during the City reviews of previous submittals. The final design package shall include the following:

- (1) Digital submittals of all documents, including Microstation CAD or AutoCAD version, and PDF.
- (2) Sealed Technical Specifications and construction estimates.
- (3) Any other final reports generated during the design process other bid related documents.

Anticipated Schedule

Milestone	Date
Submit Quote/proposal	December 2025
Contract Award/Issue Purchase Order	April 2026
Kickoff Meeting	April 2026
Submittal One – 30% Design Plan	May 2026
30% Design Public Meeting	June 2026
Submittal Two – 60% Design Plan	August 2026
Submittal Three – 90% Design Plan	October 2026
90% Design Public Meeting	November 2026
Submittal Four – Final Design Plan, Bid documents	January 2027

The Firm selected for contract award may be required to develop a knowledge and project transition plan that outlines a step-by-step process to reach a smooth transition from the current project delivery and support team to new Firms. The transition plan may include a combination of a series of meetings, documents, checklists, or other means to gather the information and project history and background to move forward effectively and efficiently without delay.

The Firms must use Bentley ProjectWise for data storage and management for all project files or propose an alternative system for City of Rockville consideration and approval.

The Consultants shall, at their own cost, provide industry-standard software applications and platforms to perform all services required in this RFP. These applications and platforms may need to be compatible with City of Rockville systems and may include, but are not limited to, the following functions:

- a. Microsoft Office Suite
- b. Adobe Suite;
- c. Bluebeam Construction Software;

Periodically, new guidelines, processes, laws, and mandates may require additional activities not clearly cited in the RFP. All activities required to deliver a project or program, whether new or existing, unless otherwise controlled by regulation or statute, will be completed under this contract. If special skills or services are identified that are beyond the expertise of the consultant, then new subconsultants may be required to be added to the contract to support project delivery.

This is not an all-inclusive list as this contract may include other professional services related to the scope outlined above.

There may be instances when City of Rockville requires the consultant to provide emergency response times for a given project. Therefore, the consultant may be required to provide those services within twenty-four (24) hours of notification or as otherwise directed by the City of Rockville.

3. Certifications

Individuals supplied by the Consultants shall have the following Certifications:

Professional Engineer (PE) for engineering activities, American Institute of Certified Planners (AICP) accreditation for planning activities, and Professional Land Surveyor (PLS) for surveying activities. The cost to achieve the various certifications, re-certifications, and Core Training, including course costs, time and mileage to attend the training/testing, shall be paid for by the Consultant Firms or the individual Consultants, not City of Rockville. Other related training may also be required based on changing City of Rockville policies. Consultants are expected to make reasonable accommodations for their staff to attend training.

4. Safety Items

The Consultants shall supply all required personal protective equipment and safety items necessary to perform the scope of work. All equipment must comply with SHA's High Visibility Apparel Policy, SHA's

Office of Construction's Directive on Personal Protective Equipment (PPE), and all OSHA and MOSH regulations.

5. Equipment

The consultant shall supply all necessary tools, equipment, and items needed to perform the scope of work.

The consultant will be required to supply all other tools and equipment not listed in order to perform the scope of work referenced in the solicitation.

6. Engineering Standards and Guidelines

The Consultants shall perform all contract engineering services in accordance with good industry practice, all applicable laws and regulations, and the current editions of the following references, their interim specifications, their successor replacement references, and all other pertinent guidelines and memoranda as released by FHWA, AASHTO, and SHA including, but not limited to the following publications:

- a. MDOT "General Conditions for Consulting Services" dated January 1989;
- b. SHA "Specifications for Consulting Engineers' Services" dated April, 1986;
- c. SHA "Request for Proposal" dated April, 2002;
- d. SHA Transportation Alternatives Program Manual
- e. SHA Development Guide for Local Public Agencies and Other Sub-Recipients of Federal Funds
- f. Maryland Department of Transportation, State Highway Administration, "Standard Specifications for Construction and Materials", latest edition. MDSHA Book of Standards for Highway and Incidental Structures.
- g. Montgomery County Department of Transportation, "Montgomery County Road Construction Code and Standard Specifications."
- h. Montgomery County, "Complete Streets Design Guide."
- i. Montgomery County Storm Drain Design Criteria.
- j. Standard Specifications of WSSC dated July 2013, or latest edition.
- k. Montgomery County Department of Transportation, "Design Standards."
- 1. Maryland Department of the Environment "2011 Standards and Specifications Soil Erosion and Sediment Control."
- m. The State of Maryland Department of Transportation, "Manual on Uniform Traffic Control Devices."
- n. American Association of State Highway and Transportation Officials, "AASHTO Design Guidelines", latest edition
- o. American Association of State Highway and Transportation Officials, "Guide for the Development of Bicycle Facilities,"
- p. Montgomery County Noise Ordinance.
- q. Rockville City Code.

7. General Requirements

The Consultants shall not enter onto private property for any purpose until authorized by City of Rockville. The Consultants must notify City of Rockville immediately if damage occurs to property and shall be responsible for any such damage. The Consultants may also be authorized to subcontract for specialties with prior approval of SHA as direct expenses that shall be discussed during the price proposal negotiations for selected awardees. Examples may include field surveys, tree identification, etc.

No payment for overtime work shall be made without authorization from City of Rockville. When overtime is required and authorized, and when payment therefore may involve premium costs, there shall be no payroll additive.

Premium overtime costs are reimbursable as a direct cost when an employee works more than forty (40) hours per week on City of Rockville projects based upon the Consultant's work week. Regularly scheduled paid company holidays may be included in the calculation of "hours worked", but time off for any other leave (e.g. vacation, personal, compensatory or sick leave) is to be excluded from "hours worked" when calculating premium time reimbursement. The fact that an employee works more than eight (8) hours in a single day does not necessarily mean that premium overtime costs are allowable as a direct cost since

reimbursement is determined on a weekly basis. Any premium overtime paid to employees, but not directly billable under this policy, may not be allowed as an indirect cost.

8. Special Requirements – Disadvantaged Business Enterprise (DBE) Provisions:

The MDOT hereby notifies all proposers that with regard to any contract entered pursuant to this solicitation, Disadvantaged Business Enterprise (DBE) firms will be afforded full opportunity to participate in response to this solicitation. DBE is a for-profit small business concern (1) That is at least 51 percent owned by one or more individuals who are both socially and economically disadvantaged or, in the case of a corporation, in which 51 percent of the stock is owned by one or more such individuals; and (2) Whose management and daily business operations are controlled by one or more of the socially and economically disadvantaged individuals who own it (49 CFR 26.5).

A socially and economically disadvantaged individual is one who is a citizen (or lawfully admitted permanent resident) of the United States and who has been subjected to racial or ethnic prejudice or cultural bias within American society because of his or her identity as a member of groups and without regard to his or her individual qualities. The social disadvantage must stem from circumstances beyond the individual's control. (49 CFR 26.5)

The MDOT hereby notifies all eligible proposers that with regard to any contract entered pursuant to this solicitation, Disadvantaged Business Enterprise (DBE) firms will be afforded full opportunity to participate in response to this solicitation and will not be subject to discrimination on the basis of race, color, national origin, age, sex or disability in consideration for an award (23 CFR § 200, 49 CFR § 21 and 26, and 49 CFR 27.19 and Section 504 of the Rehabilitation Act of 1973).

It is the goal of MDOT that certified DBE businesses participate in all federal-aid contracts. Each contract may contain a goal for DBE participation, on a contract-by-contract basis. Consultants interested in submitting a Technical Proposal in response to this solicitation must comply with the SPECIAL PROVISIONS, AFFIRMATIVE ACTION REQUIREMENTS, UTILIZATION OF DISADVANTAGED BUSINESSES, THE SURFACE TRANSPORTATION AND UNIFORM RELOCATION ASSISTANCE ACT OF 1987, ISTEA 1991, MAP 21 OF 2012, FAST Act 2015, AND INFRASTRUCTURE INVESTMENT AND JOBS ACT OF 2021.

To comply with the aforesaid SPECIAL PROVISIONS, Consultants who submit Technical Proposals must clearly set forth the DBE Prime firm(s) *and* DBE subcontractor(s) proposed for goal attainment indicating:

- a. Firm's name and address,
- b. The proposed work,
- c. Percentage of total work,
- d. MDOT certification number, and
- e. Applicable NAICS Codes

NOTE #1: DBE firms must be certified for the specific work to be performed to count their participation towards meeting the DBE participation goal. Only include the applicable NAICS Code(s) for the services/work the DBE firm is proposed to perform in support of the contract.

NOTE #2: DBE firms must be certified by MDOT in those NAICS code(s) at the time of the Technical Proposal submission and remain certified through contract award by MDOT to participate on federally funded contracts.

NOTE #3: Guidelines Regarding DBE Prime Self-Performance. Please note that when a certified DBE firm participates as a prime contractor (including a prime participating as a JV) on a contract, a procurement agency may count the distinct, clearly defined portion of the work of the contract that the certified DBE firm performs with its own forces.

A current directory of certified DBE firms is available through the MDOT Office of Minority Business Enterprise, 7201 Corporate Center Drive, Hanover, MD 21076. The phone numbers are (410) 865-1269, 1-800-544-6056, or TTY (410) 865-1342. The directory is also available on the MDOT website at https://marylandmdbe.mdbecert.com/. The most current and up-to-date information on DBE firms is available via this website. **Only MDOT-certified DBEs may be used to meet the DBE goals.**

The Consultant's failure to submit all the required DBE information, in the specified areas, will result in the Consultant being disqualified from further consideration on these contracts, unless it is in the best interest of the State to seek clarification or additional information from the Consultant Firm.

a. Contract Goals

An overall goal has been established for DBE participation for this Contract located in Section 3 G of this RFP. DBE proposers must meet the established DBE goal by either their own forces or approved DBE Subconsultant(s). When an DBE performs as a participant in a JV (as described in 49 CFR Part 26.5), they may count a portion of the total dollar value of the contract equal to the distinct and clearly defined portion of the work that the DBE performs with its own forces, toward the DBE goals and the proposed participation must be listed in Section 3 11 of SF 330.

In addition to listing the DBEs, Consultants must also list each non-DBE firm proposed in Section 3 of the SF 330 including the proposed work and percentage of work in Section 3 11 of SF 330.

The Contractor is encouraged to use a diverse group of subcontractors from any/all of the various DBE classifications to meet the overall DBE participation goal.

- b. The following DBE participation instructions, and forms are provided on SHA's website at https://www.roads.maryland.gov/mdotsha/pages/index.aspx?PageId=767 to assist Offerors/Offerors:
 - MDOT Federal DBE Form A DBE Utilization and Fair Solicitation Affidavit (must submit with Technical Proposal)
 - MDOT Federal DBE Form B DBE Participation Schedule (must submit with Technical Proposal)
 - MDOT Federal DBE Form C Outreach Efforts Compliance Statement
 - MDOT Federal DBE Form D DBE Subcontractor Contract Participation Affidavit
 - MDOT Federal DBE Form E Good Faith Efforts Guidance and Documentation

By submitting a response to this solicitation, the Offeror acknowledges the overall DBE subcontractor participation goal, and commits to achieving the goal by utilizing MDOT certified disadvantaged business enterprises. A Bidder/Offeror must make Good Faith Efforts to meet the DBE goal set for this procurement. If a Bidder/Offeror is unable to achieve the goal, the MDOT DBE Form E – Good Faith Efforts Guidance and Documentation must be completed within ten (10) Working Days from notification that it is the recommended awardee or from the date of the actual award, whichever is earlier, as required in COMAR 21.11.03.11.

As set forth in COMAR 21.11.03.12-1, once the contract work begins, the work performed by a certified DBE firm, including a DBE prime, can only be counted towards the DBE participation goal(s) if the DBE firm is performing a commercially useful function on the contract.

SECTION 3

Technical Proposal Required Information

U.S. Government forms are to be completed with standard size typing and are not to be photo reduced. Computer generated forms are acceptable; however, the format and spacing is to be identical to that of the Standard Forms 330.

With the exception of Government forms and the Organizational Chart, all pages included with your Technical Proposal submission are required to be standard 8½ x 11 size paper with a minimum of a one-inch margin on all sides and no smaller than 10-point Times New Roman font. Attachments to the Proposal are unacceptable.

SHA must be notified in writing, by email to Bryan Barnett-Woods, <u>bbwoods@rockvillemd.gov</u>, of any deletions, additions, and/or substitutions of proposed Subconsultants after Technical Proposals have been submitted.

A. <u>Cover Letter</u>

Cover Letter on the Firm's/JV's letterhead – limited to 2 pages, which must contain:

- i. The names, contact numbers and email addresses of the Primary Liaison, Disadvantaged Business Enterprise (DBE) Consultant Liaison Officer for Minority Affairs, and your firm's contact person for this procurement process. The Primary Liaison, DBE Liaison Officer, and the firm's procurement contact may be the same or different individuals.
- ii. The e-mail address of the contact person for this contract. Future correspondence related to this contract, prior to award of a contract, may be transmitted via e-mail.
- iii. The information that the Firm/JV have the financial capacity to provide the services and has measures of protection for the State against errors and omissions.
- iv. Certification that the Firm/JV have read and fully understand the requirements set forth to be provided for this RFP.
- v. Certification that the Firm/JV and proposed team possesses the expertise, resources, knowledge, and technical ability to perform all elements of the contract's scope and deliver all the requirements set forth through its own forces and those of its subcontractors.
- vi. Certification that Key Staff individuals meet the education, experience, certification/registration and expertise requirements set forth in this RFP.
- vii. This letter shall be signed by the person or persons able to legally bind the Firm to the proposal.
- viii. Corporate Resolutions shall be included if signed by anyone other than the President of the Firm or Executive for the JV.

B. Scope

The Consultant must submit a maximum of two (2) page document certifying the contract's Scope can be performed in its entirety through its own forces and those of its subconsultants. This section of the proposal should provide information to confirm the Offeror has a reasonable probability of success in meeting the project's quantity, quality and schedule requirements.

C. Work Plan

The Consultant must submit a maximum of six (6) page work plan detailing their ability to perform the consultant services required, scope of work, etc. to make up their Work Plan submission. Work Plan shall include, at a minimum, the following information:

- i. Has read and fully understands the requirements set forth to be provided for this contract;
- ii. The Consultant team possess the experience, resources, knowledge and technical ability to perform and deliver all the requirements set forth in this contract;
- iii. Acknowledges this is a project-specific contract and understands the requirements for schedules and/or deadlines to provide deliverables, services, etc.;
- iv. Has a detailed work plan in place to ensure schedules and/or deadlines will be met as well as achieving the DBE goal;
- v. The work plan includes comprehensive quality assurance and quality control program; and
- vi. Other statements are at the discretion of the Consultant as this is not an all-inclusive list.

D. Standard Form 330 Parts I and Parts II

Completed US Government Standard Forms (SF) 330 Parts I and Parts II for the Prime and for each proposed subcontractor. The SF 330 forms must be completed in their entirety paying special attention to the following:

- Outside Key Consultants (Sub-Consultants) should be documented in Part I, Section C of the SF 330. Please follow the directions provided in Section 8 within "Special Requirements – DBE Provisions" to complete Section C 11 for MDOT certified DBE firms.
- ii. The Organizational Chart required for Part I, Section D of SF 330 shall be placed within the *Standard Form 330 Parts I and Parts II* of the Technical Proposal and must contain, at a minimum, the Key Personnel and defining team organization with supplemental support personnel. In addition, for every individual proposed for this contract and shown on the organization chart, the chart shall clearly show their company affiliation and their permanent office location. The Organization Chart shall be limited to an 11 x 17-inch page with Times New Roman Font size 10-point or larger.

In addition, a two (2) page matrix style of support personnel shall be included in the *Standard Form 330 Parts I and Parts II* of the Technical Proposal. Matrix style is defined as names listed on the vertical axis and Relative Experience identified on the horizontal axis. The support personnel descriptions are limited to six (6) lines per individual. The support personnel Matrix shall be limited to an 11 x 17-inch page with no smaller than 10-point Times New Roman Font size and one-inch margins.

- iii. Part I, Section E of the SF 330, Key Staff. A separate Section E form should be completed for each Key Staff individual proposed. Provide a resume for each of the Key Staff individuals outlined below, limited to one (1) Key Staff per page, not to exceed eight (8) pages total. The experience for each individual Key Staff as described below shall be recent experience performed within the last five (5) years. Years of experience and applicable licenses and certifications, such as a professional Engineer license, American Institute of Certified Planners or similar, shall be clearly documented on each resume.
- iv. SF 330 Section F Example Projects Which Best Illustrate Proposed Team's Qualifications: Limited to four (4) example projects one (1) example project per page for a total not to exceed four (4) pages. Photos are acceptable; however, all photos count in the overall space limitations for the page and are considered illustrations and are not rated. The Example Projects set forth shall be recent relevant experience performed within the past five (5) years. (Information provided in this section shall become part of the rating/evaluation criteria for this project).

Example projects should include 100% design plans for shared use paths, on-road cycle tracks, and sidewalks, as well as complete streets design project along a corridor with signalized intersections.

v. SF 330 Section H – This section shall be limited to one (1) page and must certify that the Key Staff individuals meet the education, experience, registration/licensure, expertise, and all other professional qualifications specified in this advertisement. Please exclude any confidential personal information.

Additional Information regarding Key Staff replacements after Final Selection:

Key Staff changes may only be requested after final selection if the Key Staff is no longer available to perform on the contract or at the request/agreement of City of Rockville. A letter outlining the reason for the change and the names of the Key Staff involved in the replacement request must be in writing on the firm's/JV's letterhead along with a one (1) page resume per the requirements outlined in this RFP.

Substitutions will be evaluated using the same qualifications-based technical rating criteria and the Key Staff replacement's score must be equal or higher than the original Key Staff's score in order to be accepted/approved by SHA. All scores will remain confidential by SHA. Instructions for completing a resume are included in Section 9 D – *Standard Forms Part I and II* of this RFP.

E. Technical Questions:

Technical question responses shall not exceed a total of five (5) pages, limited to one (1) page per question.

Reference the question number at the top of each page and use the remainder of the page for the response to the question (for example, "Question #1:"):

- a. Question #1: What steps should a firm take during the shared-use path design process to evaluate, propose, and design a signalized intersection? What standards must be followed, and which agency must be involved?
- b. Question #2: What criteria are considered for designing shared-use paths along roadways? How are the criteria prioritized?
- c. Question #3: What elements need to be considered for surveying roadways segments and the surrounding area for an urban shared-use path project?
- d. Question #4: What plans are necessary to carry out a shared-use path construction project in an urban setting?
- e. Question #5: What steps can a firm take during the design phase to reduce or eliminate the number of change order requests during construction?

F. Subcontractors Commitment – no page limits as this section may vary:

The Technical Proposals are to be explicit with respect to the work to be performed by all subcontractors proposed. A Letter of Commitment is required for each proposed Sub-Consultant. While the format and overall content is at the firm's discretion, a Letter of Commitment must at a minimum:

- Be on the Sub-Consultant's letterhead;
- List the services proposed to be provided;
- Certify the firm is able to provide the required resources, services, etc.;
- List the applicable NAICS Codes for the services/work to be performed in support of the contract, and overall percentage of work to be performed for the contract;

- NAICS Codes must be the same as those listed in Section C 11 of the SF 330 for each subconsultant;
- Be signed and dated by the Principal/President of the firm; and
- If a firm is a MDOT Certified DBE, include the MDOT Certification number and applicable NAICS codes consistent with the work to be performed.

G. <u>DBE Compliance – the Consultant shall include the executed "MDOT DBE Forms (A&B)" – no page limits as this section may vary:</u>

There is a **zero percent (0%)** DBE goal established for this contract. DBE proposers must meet the established DBE goal by either their own forces or approved DBE subcontractor(s).

This section must include an introduction letter listing all the proposed MDOT Certified DBE firms, associated MDOT Certification Numbers, proposed work and percentages, NAICS codes applicable to the work to be performed, and the name and contact information of the DBE Consultant Liaison Officer for Minority Affairs. The introduction letter is not required to be on the firm's/JV's letterhead or signed and dated. The format is at the firm's discretion.

H. <u>Time Distribution – not to exceed 1 page consisting of the following:</u>

The Consultant shall include a 1 page listing of those classifications proposed for services and the percentages of time estimated for each classification. Percentages shall total one hundred percent (100%). The Consultant <u>shall not</u> include man-hour estimates in the Technical Proposal. A column of percentages of time estimated for each classification are to be shown for the Prime Consultant, for each subcontractor proposed, and one (1) column showing totals which add up to 100%. When multiple firms are used, the total for each firm must add up to something less than 100%. These percentages are applicable to the total dollar amount of the Price Proposal to be developed separately by the selected firm(s). The percentages are not applicable to time estimates. The Consultant shall indicate the number of simultaneous project assignments the Consultant and each Subconsultant could handle individually.

The following classifications and estimated percentages of time to be used for the contract assignments are:

Classification	Est. Office (%)	Est. Field (%)	Total (%)
Principal	0.4	0.0	0.4
Project Manager	3.4	1.0	4
Senior Engineer	18.9	1.0	20
Junior Engineer	45.9	2.0	48
Arborist	1.8	2.0	4
Technician	16.4	1.0	17
Surveyor	1.2	5.0	6
Total	88	12	100

I. Financial Responsibility and Insurance Requirements:

- 1. The consultant shall include a letter addressed to SHA setting forth evidence that the consultant has the financial capacity to provide the services and has measures of protection for the State against errors and omissions.
- 2. The Consultant shall include a copy of the firm's current certification(s) of insurance, which should contain, at minimum, the following:

- Carrier (name and address)
- Type of insurance
- Amount of coverage, which must include at a minimum of [\$1,000,000] per occurrence of Professional Liability
- Period covered by insurance; and
- Any exclusions

Insurance coverage will be one (1) of the areas evaluated when Technical Proposals are reviewed. Failure of the Consultant to submit satisfactorily to these requirements may result in SHA rejecting the proposal(s).

SHA requires the following minimum levels of insurance coverage for this contract:

a. Worker's Compensation and Employer's Liability

The Contractor shall, at all times, maintain and keep in force such insurance as will protect him from claims under the Worker's Compensation Act of the State of Maryland and maintain and keep Employer's Liability Insurance at a limit of One Million Dollars ([\$1,000,000]). The \$1,000,000 employer liability can be satisfied by an Umbrella/Excess Policy, as long as it is specific to "Employer's Liability".

b. Commercial General Liability Insurance

The Contractor shall maintain Commercial General Liability Insurance in the amount of at least One Million Dollars (\$1,000,000) Combined Single Limit for Bodily Injury Liability and Property Damage Liability Insurance per occurrence, and One Million Dollars (\$1,000,000) in the aggregate.

c. Comprehensive Automobile Liability Insurance

The Contractor shall maintain Comprehensive Automobile Liability Insurance (including all automotive equipment owned, operated, rented, or leased), in the amount of at least One Million Dollars (\$1,000,000). Combined Single Limit for bodily injury and property damage.

d. Professional Liability Insurance

The Contractor shall maintain Professional Liability Insurance in the amount of at least One Million Dollars (\$1,000,000).

In addition, the City of Rockville requires:

e. Excess/Umbrella Liability for each occurrence/aggregate in the amount of at least One Million Dollars (\$1,000,000). City to be listed as additional insured and provided 30 day notice of cancellation or material change in coverage.

Please see Attachment C for full City of Rockville insurance requirements.

J. <u>Proposal Affidavits:</u>

As per State Finance and Procurement Article 17-701 – 17-707 of the Annotated Code of Maryland, a firm engaging in investment activities with companies appearing on the Investment Activities in Iran list is ineligible for bid/proposal/award. The Investment Activities list is located at www.bpw.state.md.us of the Maryland Board of Public Works (BPW) website. As per the BPW Advisory No.: 2013-1, Date Issued January 1, 2013, an officer of the Firm shall provide a signed original certification as per language stated on the BPW Advisory page. If the Firm is a JV, officers

from all companies forming the JV shall provide a signed original certification. NOTE – the Investment Activities in Iran certification is included in the bid/proposal affidavit.

In preparing its proposal on this contract, the Offeror has considered all proposals submitted from qualified, potential subcontractors and suppliers, and has not, in the solicitation, selection, or commercial treatment of any subcontractor, vendor, or supplier, refused to transact or terminated business activities, or taken other actions intended to limit commercial relations, with a person or entity on the basis of Israeli national origin, or residence or incorporation in Israel and its territories. The Offeror also has not retaliated against any person or other entity for reporting such refusal, termination, or commercially limiting actions. Without limiting any other provision of the solicitation for proposals for this contract, it is understood and agreed that, if this certification is false, such false certification will constitute grounds for the State to reject the proposal submitted by the Offeror on this contract, and terminate any contract awarded based on the bid/proposal.

All offerors are required to submit the following completed affidavits with their technical proposal within the *Proposal Affidavits* section. Both documents are available on the SHA OPCM website at https://roads.maryland.gov/mdotsha/pages/Index.aspx?PageId=767

- Bid / Proposal Affidavit
 - o Form is located under "Affidavits" section of the website
- Certification Regarding Discriminatory Boycotts of Israel
 - Form is located under the "Certification Regarding Discriminatory Boycotts of Israel" section of the website

9. <u>Services/Materials to be provided by City of Rockville:</u>

The City's Department of Public Works (DPW) will provide the successful Consultant with existing traffic signal plans, general guidance, and liaison services to other City agencies. The City's DPW will assist the successful Consultant by providing guidance and background material. This is not an all-inclusive list. City of Rockville may provide additional services/materials as appropriate.

10. Progress Reports:

The Consultant must submit monthly progress reports including a detailed account of work performed that is being billed, outstanding issues, summary of additional work requests, percent completed, any anticipated delays, etc. This report must be submitted with the monthly invoice.

11. Records, Tasks and Notice to Proceed:

The Consultant shall keep accurate records documenting the time, material, and transportation utilized, etc. Contract payment(s) to the Consultant for work completed will be made on this basis only.

The Consultant must be able to provide prompt consultant services within 14 working days of the contract's Notice to Proceed.

No work shall be performed on contract by the Consultant until a written Notice to Proceed (NTP) is received by the Consultant from City of Rockville.

The Consultant must provide the required services within five (5) working days of an NTP for an approved assignment.

12. Completion Date:

The contract will terminate on the expiration date.

13. Prompt Payment

Pursuant to 49 CFR §26.29, MDOT requires prime contractors to pay subcontractors, at any tier, for satisfactory performance of their contracts no later than 30 days from receipt of each payment that City of Rockville makes to the prime contractor. When City of Rockville has made an incremental acceptance of a portion of a prime contract, the work of a subcontractor covered by that acceptance is deemed to be

satisfactorily completed. To the extent that it is not inconsistent with federal law, all prime contractors shall also comply with all Maryland laws and regulations regarding the prompt payment to subcontractors.

14. <u>Due Date Deadline for Submissions</u>

RESPOND BY FRIDAY, DECEMBER 05, 2025, PRIOR TO 2:00 PM (EST). Only City Collaboration Portal submissions of the Technical Proposals submitted through <u>Contract Insight - Collaboration Portal</u> (rockvillemd.gov) will be accepted as described above.

The Procurement Officer and sole point of contact for this solicitation, unless directed otherwise within this solicitation or by SHA, is:

Jonathan Pierson, CPSM, C.P.M.
Assistant Director
Procurement Department
City of Rockville, City Hall
111 Maryland Avenue
Rockville, Maryland 20850
Phone: (240) 314-8433

SECTION 4

Evaluation Criteria

The major factors/criteria and their relative weight of importance to be used in evaluating Technical Proposals are:

Item	Score
Technical Questions	40%
Key Staff	30%
Work Plan	30%


The following items will be rated as either one of the following:

- (A) Acceptable-Response demonstrates they meet requirements
- (U) Unacceptable-Response fails to demonstrate they meet requirements
- (N) Neutral-Lacks prior SHA experience. Not a barrier to award
- a. Scope of Services;
- b. Example Projects;
- c. Compatibility of the size of the firm with the size of the proposed project;
- d. Past Performance working on City of Rockville task orders when prior work history is available, including Quality and Timeliness. (Lack of prior experience with City of Rockville is in no way considered a barrier to receiving an award);
- e. Capacity to accomplish the proposed work in required time;
- f. Insurance;
- g. Financial Responsibility; and
- h. Measures of protection for the State against errors and omissions.

^{*}Please Note: If an offeror receives a rating of "unacceptable" on three (3) of the rating criteria above, the offeror will not be further considered. The offerors' proposal will be rejected as "not susceptible of being selected for award." COMAR 21.06.02.03(2)









City of Rockville

Fleet and Monroe Streets, Complete Streets Study



PREPARED FOR THE CITY OF ROCKVILLE BY

FUNDED BY THE METROPOLITAN WASHINGTON COUNCIL OF GOVERNMENTS TRANSPORTATION LAND-USE CONNECTIONS PROGRAM







Table of Contents

INTRODUCTION	2
Project Need, Goals, And Objectives	2
Objective	2
Goals	2
PROJECT INFLUENCES AND PRIOR PLANNING EFFORTS	2
Stakeholders	3
CONCEPT DEVELOPMENT	3
Opportunities and Constraints	3
Design Process & Study Methodology	3
Field Observations:	4
Traffic Impacts of a 4-lane to 3 Lane Road Diet	5
Initial Concept Development and Stakeholder Discussion	6
Initial Stakeholder Comments	10
Finalized Concepts	11
Concept 1: Bike Path behind curb	12
Concept 2: Two-way inroad cycletrack	15
IMPACTS ANALYSIS	17
Parking and traffic impacts	17
Construction Costs	18
Public Meeting	18
DESIGN CONSIDERATIONS AND NEXT STEPS	19
Design Summary and Future Considerations	19
Preferred Option and Next Steps in the Design Process	20
FLINDING OPPORTUNITIES	21

Appendix A: Traffic counts
Appendix B: HCM Reports
Appendix C: Conceptual Plans
Appendix D: Cost Breakdown
Appendix E: Public Presentation



INTRODUCTION

The City of Rockville received funding through MWCOG's Transportation Land Use Connections (TLC) technical assistance program to study the feasibility and impacts of expanding dedicated and separated bike facilities out from the Town Center core, leveraging previous dedicated biking infrastructure to reach more destinations and amenities.

Dedicated biking facilities along Monroe Street and Fleet Street will extend planned bike lanes along East Middle Lane southward to the Rockville Metro Station pedestrian bridge, Richard Montgomery Highschool (and the shared used path that surrounds it), and to Maryland Ave and points south. When complete, these facilities will provide a comfortable and safe dedicated connection for cyclists and micromobility commuters, complementing the existing sidewalk and street grid, allowing residents and visitors convenient non-vehicular access to and throughout the Town Center.

Project Need, Goals, And Objectives

The City of Rockville seeks to extend its biking infrastructure and to increase connectivity to the Rockville Metro Station, County office buildings and local schools. This feasibility study explores potential options for expanding dedicated bike facilities, separated from vehicle traffic, and analyze the impacts, benefits, and constructability of each.

Objective

Connect under-construction bike lanes on Middle Lane to Fleet Street and Monroe Street via a dedicated and protected bike path or lanes that are separated from vehicular traffic.

Goals

Primary goals for the proposed projects include:

- Increase recreational and commuting options to local destinations from residential neighborhoods.
- Reduce vehicle miles traveled in the Town Center.
- Connect existing biking infrastructure to provide Complete Streets throughout Rockville Town Center.
- Provide proof of concept design (e.g., no fatal flaws, minimized traffic impacts, constructable, etc.).

PROJECT INFLUENCES AND PRIOR PLANNING EFFORTS

The desired alignment for dedicated bike facilities builds upon prior work by the City along East Middle Lane and along Washington Street. These plans are complete and were provided by the City as part of the prior planning efforts. For the purpose of developing conceptual alignments, these plans were incorporated into base mapping efforts as *existing conditions*.

To assist with the feasibility analysis, the City of Rockville provided signal timing for all locally-owned traffic signals as well as available traffic count data. Remaining signal timing was obtained from Montgomery County and additional traffic counts were collected in the Winter of 2022. Additional City directives that drove the conceptual designs include:



- If proposing a road diet, keep general travel lanes at 11 feet width.
- Turn lanes can be 10 feet wide.
- Curbside *unprotected* bike lanes are undesirable.
- Mixing of pedestrians and cyclists on a shared use path is allowable, but separate pedestrian and bike facilities are desirable.
- City has previously been against 2-way cycletracks in the past.

Stakeholders

While the City of Rockville is the project originator, other government representatives that are stakeholders include:

- City of Rockville Department of Public Works
- Rockville Bicycle Advisory Committee (RBAC) / Rockville Pedestrian Advocacy Committee (RPAC)
- Montgomery County Government offices
- Maryland Department of Transportation State Highway Administration (MDOT SHA)
 - Owner of MD 28 / Monroe Street intersection
- RideOn bus service

CONCEPT DEVELOPMENT

Opportunities and Constraints

Fleet Street and Monroe Street are both fully developed with office, commercial, and residential properties. Additionally, there is limited public right of way for constructing bike facilities behind existing curb and adjacent to existing sidewalk. Also, existing travel lanes are narrow (11 to 12 feet), limiting the ability to use extra space from wide travel lanes to construct on-street bike facilities. Finally, there is on-street curb side parking along Fleet Street and Monroe Street, the latter of which is often fully-occupied.

Despite, these constraints, there are opportunities to construct dedicated bike facilities, adjacent to existing sidewalks, within the public right-of-way. Primarily, both Fleet Street and Monroe Street have ample traffic capacity, such that there is a possibility to reduce the number of general travel lanes and repurposing them for other modes. Additionally, because the Rockville Town Center area is a grid-based network of roads, there is potential to shift turn movements – and therefore dedicated turn lanes – to other intersections where capacity allows it, which also can free of pavement for repurposing. Finally, by providing safe and convenient biking options, short term vehicle trips can now be made by biking, reducing vehicle traffic.

Design Process & Study Methodology

Developing alternative concepts began with an extensive field review and CAD base mapping effort for the Fleet Street and Middle Lane corridors. County-level GIS data was supplemented with in-the-field data collection. The field survey allowed for verification of existing mapping libraries and to note any recent construction projects. It also allowed for determining potential construction impacts that can be significant cost drivers – such as utility pole relocation, inlet relocation, need for retaining structure, etc. The base mapping included all existing sidewalk, curb and gutter, utility poles, driveways, large trees, and two-foot contour lines. To this, all public right of way information and lot lines were added, in



addition to pavement markings, street signs and dimensions. Concept designs were developed using the following design standards and guidelines:

- AASHTO
- NACTO
- PROWAG
- MUTCD
- ADAAG
- MDOT SHA
- Montgomery County DOT Standards

Field Observations:

Field observations were conducted in early December 2022. The following observations were made:

AM Peak Hour Observations:

- Monroe St is generally low volume with moderate to high bus traffic.
- Several school age pedestrians and cyclists observed crossing Jefferson Street to Richard Montgomery High School.
- Monroe St at Jefferson St approximate average queue lengths noted were:
 - Eastbound left lane: 2 cars
 - o Eastbound through lanes: 7 cars
 - Westbound lanes: 9 cars
 - Northbound lane: 2 cars
 - Southbound lane: 2 cars
- Monroe St at Middle Ln
 - o Northbound queues are typically less than 2 vehicles.
 - o A school bus was observed making an eastbound right onto Monroe St southbound.
- Monroe St at Montgomery Ave
 - o Minimal queues observed on all approaches.
- Monroe Pl at Monroe St
 - o Minimal queues observed on all approaches.
 - Monroe Pl is the nearest available EBL turn to MD 355 NB
- Monroe St at Fleet St
 - Queues on all approaches are less than 5 vehicles.

PM Peak Period Observations:

- Monroe St is generally low volume with moderate to high bus traffic.
- Many peds were observed crossing mid-block west of Monroe St from courthouse to parking garage.
- Monroe St at Jefferson St:
 - o Inside north-south through lanes act as de facto left turn lanes.
 - 90% of eastbound left-turning traffic turn makes a northbound right turn at Monroe PI toward MD 355



- Buses observed making eastbound left and encroaching on through lane due to narrow lane width.
- Average queue lengths are:
 - Eastbound left lane: 1 car
 - Eastbound through lanes: 7 cars
 - Westbound lanes: 7 carsNorthbound lanes: 3 cars
 - Southbound lanes: 1 car
- Northbound queues increased to about 10 vehicles around 5:30PM when the Jury parking lot dismissed; however, queues were primarily in the outer northbound travel lane
- Jury parking lot queue was extensive (over 30 vehicle long) when drivers were leaving at once.
- No cycle failure observed at intersection.
- Monroe St at Middle Ln
 - EB queues occasionally spill beyond Monroe St intersection from downstream signal at MD 355
 - NB queues less than 3 vehicles
 - Observed several mid-block U-turns from northbound.
- Monroe St at Montgomery Ave
 - Minimal queues less than 3 vehicles on any approach
- Monroe Pl at Monroe St
 - o Minimal queues less than 3 vehicles on any approach
 - Monroe Pl is the nearest available eastbound left turn to MD 355 northbound.
- Monroe St at Fleet St
 - o Southbound queues less than 5 vehicles maximum

Initial opportunities based on traffic observations include:

Alternative design ideas based on field observations.

- Consider one-way operations on Monroe St from Middle Ln to Monroe Pl
 - Alternatively, remove parking and curb extensions on west side.
- Consider a road diet on Monroe St from Monroe Pl to Fleet St
 - o Reduce four lane section to a three-lane section with a two-way center turn lane.
- Fleet St from Monroe St to MD Ave
 - o Reduce four lane section to a three lane section with a two-way center turn lane.

Traffic Impacts of a 4-lane to 3 Lane Road Diet

Based on the observations of peak period traffic and the potential for a road diet, a traffic analysis was performed to determine if, in fact, a conversion of Fleet and Monroe Streets from four lanes to three lanes was feasible and what the overall impacts were.

The City of Rockville provided counts at: Fleet St at Monroe St and Fleet St at Maryland Ave. These were supplemented by new counts conducted in late Fall of 2022 at: MD 355 at MD 28; MD 28 (Jefferson St) at Monroe St; and Monroe St at East Middle Lane. Traffic signal timing were obtained from the City and



Montgomery County for all relevant signals. Both the signal timing and traffic volumes were used to develop a traffic model of the *existing conditions* traffic network in Synchro™ modeling software – an industry standard software used by local jurisdictions to time traffic signals and analyze traffic impacts. Standard measures of effectiveness of traffic modeling include: average vehicle delay, volume-to-capacity ratio (V/C), level of service (LOS), and vehicle queue lengths, and are generally developed for both an AM and a PM peak commuting hour. The existing conditions traffic model was validated based on field observations, allowing it to be modified to reflect real-world impacts of geometric changes, such as replacing a travel lane. Traffic counts can be found in Appendix A. The high-level results of the road diet analysis are summarized in Table 1.

Table 1: Intersection capacity analysis results between existing conditions and proposed concepts

ID		Intersection	Approach	Existing			Build - Shared Use Path			Build - Exclusive Phase Opt 1			Build - Exclusive Phase Opt 2		
		Intersection	дриоден	Delay	LOS	V/C	Delay	LOS	V/C	Delay	LOS	V/C	Delay	LOS	V/C
1	.	Monroe St & E	Control Type	Stop (2 - Way)			Stop (2 - Way)		Stop (2 - Way)			Stop (2 - Way)			
	_	Middle Ln	Overall	0.0 (0.0)	A (A)	0.10 (0.20)	0.0 (0.0)	A (A)	0.10 (0.20)	0.0 (0.0)	A (A)	0.10 (0.20)	0.0 (0.0)	A (A)	0.10 (0.20)
_	, [Monroe St & E	Control Type	Stop (All-Way)			Stop (All-Way)		Stop (All-Way)			Stop (All-Way)			
4	۷	Montgomery Ave	Overall	0.0 (0.0)	A (A)	0.00 (0.00)	0.0 (0.0)	A (A)	0.00 (0.00)	0.0 (0.0)	A (A)	0.00 (0.00)	0.0 (0.0)	A (A)	0.00 (0.00)
_	\Box	Monroe St &	Control Type	Stop (All-Way)			Stop (All-Way)		Stop (All-Way)			Stop (All-Way)			
3	١ '	Monroe Pl	Overall	0.0 (0.0)	A (A)	0.00 (0.00)	0.0 (0.0)	A (A)	0.00 (0.00)	0.0 (0.0)	A (A)	0.00 (0.00)	0.0 (0.0)	A (A)	0.00 (0.00)
	,	Monroe St & E	Control Type	Signal		Signal		Signal			Signal				
-	4	Jefferson St	Overall	17.9 (23.9)	B (C)	0.48 (0.55)	18.1 (24.9)	B (C)	0.50 (0.61)	29.3 (52.2)	C (D)	0.52 (0.64)	24.3 (33.2)	C (C)	0.51 (0.64)
5	_	Monroe St & Fleet	Control Type	Signal			Signal		Signal			Signal			
-	٦	St	Overall	13.1 (10.1)	B (B)	0.59 (0.48)	17.2 (16.1)	B (B)	0.59 (0.54)	17.2 (16.1)	B (B)	0.59 (0.54)	14.6 (17.6)	B (B)	0.56 (0.56)
6		Maryland Ave &	Control Type	Signal			Signal		Signal			Signal			
	1	Fleet St	Overall	29.3 (79.8)	C (E)	0.67 (0.88)	29.3 (81.2)	C (F)	0.67 (0.88)	29.3 (81.2)	C (F)	0.67 (0.88)	31.2 (82.1)	C (F)	0.67 (0.88)
7	,	MD 355 & E	Control Type	Signal			Signal			Signal			Signal		
	'	Jefferson St	Overall	46.2 (69.0)	D (E)	0.67 (0.78)	46.2 (68.6)	D (E)	0.67 (0.78)	46.2 (68.6)	D (E)	0.67 (0.78)	46.2 (68.6)	D (E)	0.67 (0.78)

Several assumptions were made in this initial traffic analysis, because there are additional signal modifications needed, depending on the type of facility created for cyclists. Specifically, in addition the existing conditions model, a shared-use path for cyclists and scooters (adjacent to sidewalk) could have different signal phasing requirements than an *on-street* two-way cycletrack. Accordingly, the 4 scenarios in Table 1 reflect the following assumptions:

- 1. Existing conditions
- 2. Side Path behind a new curb line, adjacent to sidewalk
- 3. On-street cycletrack that would require exclusive WALK phasing for cyclists crossing Jefferson St.
- 4. On-street cycletrack that would require a protected WALK phase for cyclists crossing Jefferson St. while prohibiting northbound left turn across the cycletrack but permitting all other northbound vehicle movements simultaneously with the WALK phase. Additionally, this option also assumes a short turn pocket for NBL on Monroe St at Fleet St.

These options will be discussed in further detail in the *Impacts* section.

HCM and queuing reports for each option can be found in Appendix B.

Initial Concept Development and Stakeholder Discussion

The following concepts present alignment options discussed with City Staff and stakeholders:

- Bike/scooter raised path (behind a curb) along the south side of Fleet Street and the west side of Monroe Street.
- In-road two-way cycletrack along the south side of Fleet Street and the west side of Monroe Street.



Figure 1 and Figure 2 show the existing and proposed typical sections for each concept.




Figure 1: Existing and proposed typical cross section for raised bike path option.




Figure 2: Existing and proposed typical section for on-street two-way cycle track option.

Fleet and Monroe Streets, Complete Streets Study



Both of these typical sections represent generally the same idea of removing a general purpose travel lane and dedicating it for bike infrastructure, leaving existing sidewalk in place. Additionally, both options propose reducing Monroe Street to one-way northbound only from Montgomery Ave to East Middle Lane. However, each option has different impacts with regard to intersection treatments. Both the raised bike path and the two-way cycletrack were conceptually drawn in plan-view for a preliminary discussion with the City of Rockville and MDOT SHA. Additionally, these concepts were discussed with MC-DOT, particularly with regard to bus stop treatments for the County's RideOn bus service, which has multiple stops along the Fleet Street and Monroe Street. An example of the preliminary conceptual layouts discussed with City, County, and State stakeholders is shown below:

- Example of raised path on Fleet Street (Figure 3)
- Example of two-way cycle track on Fleet Street (Figure 4)
- Example of one-way traffic operations on Monroe Street from Montgomery Ave to East Middle Lane (Figure 5)



Figure 3: Example of a raised path concept on Fleet Street






Figure 4: Example of a two-way cycletrack concept on Fleet Street




Figure 5: Example of a one way operations on Monroe Street, south of East Middle Lane



Initial Stakeholder Comments

The following is a summary of all concept comments and how they are addressed – either in this current preliminary design phase or the next design phase (30% Design). Solutions/next steps related to the refinements of the concepts *are in italics*.

- Maintain consistency with crosswalks bikewalks. Provide continental-style crosswalks only (global comment). MDOT SHA prefers green ladder style for bike crosswalks.
 - o All crosswalks will be shown as continental style.
- Add transit crossings at all bus stops.
 - Per discussions with MCDOT, all transit crossings will have wide crosswalks to accommodate both doors of a bus, and the crossings will be at grade with the bus stop.
- If the bike path option is selected, then existing APS/CPS needs to be relocated. Also, crossing any ADA ramps should get you immediately to pedestrian facility not into the path of a cyclist.
 - If bike path option is selected, design will reflect ADA detectable warning surface between path and existing sidewalk.
- May need to evaluate impacts of local apartments that have driveways onto Monroe Steet, if the latter is turned into one-way northbound.
 - Traffic along southbound Monroe Street is low, ~100 cars per day. Additionally adjacent apartments have garages with exits onto parallel roads (e.g., Helen Heneghan Way)
- Ensure that northbound Monroe street at Middle Lane only allows right turns only.
 - Northbound left turns and through movements are proposed to be eliminated by continuing the median along Middle Lane through the intersection, such that only right turns are feasible.
- Consider how to terminate facilities, so that they integrate into future bike lanes on Middle Lane.
 - Bike path or lane will have separate green bike crosswalk. Additionally, median break at Middle Lane is proposed to be closed.
- Ensure no ADA warning surfaces on the bike path only for shared-use bike/pedestrian paths.
 - o ADA warning surfaces along bike path are removed from concepts.
- If the cycletrack option is selected, refer to Montgomery County's draft guidelines for floating bus stops.
 - Concepts will reflect these guidelines.
- Include a conceptual option for parking removal along Monroe Street between Middle Lane and Montgomery Ave – to retain two-way traffic.
 - Optional concept is included.
- General question regarding how to tell cyclists when it is okay to cross signalized intersections.
 When should cyclist movements be protected from all/some vehicle turn movements? MDOT SHA has guidance for protection of cycletracks across State-owned intersections.
 - o For both options, the intersection of Fleet St at Monroe is designed as a protected intersection, with cyclists crossing with the WALK indication. The facility type selected will determine the type of crossing protection given to cyclists for crossing the MD 28 intersection. For a bike only path adjacent to the sidewalk and behind a curb, MDOT SHA may allow a similar crossing indication, where cyclists cross with the WALK phase (concurrent with northbound and southbound green vehicle green phases), assuming




that cyclist speed can be reduced at the intersection. For the cycletrack option, MDOT SHA only allows a dedicated WALK phase, meaning that while pedestrians can cross concurrently with cyclists, northbound and southbound vehicle traffic must be prohibited from crossing the cycletrack, i.e., only northbound through movements or right turns are allowed and southbound through movements and left turns are allowed.

- Street lighting along both Monroe Street and Fleet Street needs to be improved. It is too dark for pedestrians during the nighttime.
 - o Comment noted. Additional lighting will be evaluated during future design phases.

Finalized Concepts

The following section describes each of the two potential concepts and provides an analysis of impacts and overall construction feasibility. Impact analysis generally relates to cost, permitting needs, right of way acquisition, utility relocations, as well as any parking loss. A conceptual design plan for each project is presented in <u>Appendix C.</u> As shown in Figure 6, the limits of the proposed bike facilities are:

- West Side of Monroe Street, joining proposed bike lanes on Middle Lane in the north to Fleet Street in the South.
- South side of Fleet Street, joining Maryland Ave to the existing shared use path at Richard Montgomery High School







Concept 1: Bike Path behind curb

As shown in Figure 7, the bike path begins in the west at the southeast quadrant of Maryland Ave at Fleet Street, where the current sidewalk landing will be widened to a shared bike/pedestrian landing, before the sidewalk and bike path split.




Figure 7: West terminus of bike path option

The path, along with a buffer from the roadway, replaces the outside eastbound travel lane of Fleet Street. The path crosses three existing residential driveways, whose aprons will have to be reconstructed. Additionally, the path crosses a transit stop; as shown in Figure 7, a wide crosswalk is provided across the path, to which cyclists must yield when bus riders board or alight. Additionally, the bike path and sidewalk utilize the same crosswalks at the intersection of Fleet St at Monroe St, both modes crossing with the WALK signal. Of note, the southbound bike path bends toward the west, as it approaches Fleet Street, which forces cyclists to slow down at the crossing and also places their more into drivers' cones of vision, as they turn into the crosswalk from the north or south. Finally, the westbound left turn lane (at Maryland Ave) is shown as substantially longer than the eastbound turn lane at Monroe Street; this is due to the much larger left turn volume onto southbound Maryland Ave, when compared to the left turn volume onto northbound Monroe Street.

Figure 8 shows the eastern terminus of the separated bike path. The path meanders south, just prior to the midblock crossing at the RMHS entrance, where it ties into the existing sidewalk and ultimately the existing side use path in front of the school. Of note, existing curbside inlets will have to be relocated to the new curb line.





Figure 8: Eastern terminus of proposed bike path at RMHS

Additionally, this segment of Fleet Street has 7 metered curbside spaces along the south side of the road that will be eliminated with this design.

Figure 9 shows the bike path option crossing Jefferson street (MD 28). At this intersection, Monroe Street has somewhat wider lanes that allow the bike path to have ample buffer from the roadway, which pushes the shared use crosswalk (both for pedestrians and cyclists) back from the road edge. This allows for turning vehicles to have more opportunity to see fast moving cyclists through the crosswalk, who use the WALK phase, like pedestrians. In addition to the curb being relocated, this concept reconfigures the driveway apron for the County parking garage and the pedestrian ramps for crossing Jefferson Street.




Figure 9: Bike path option, crossing Jefferson Street



As on Fleet street, the bus stop remains at grade through the path. Northbound and southbound left turn lanes on Monroe Street remain in this option.

As the bike path terminates in the north at East Middle Lane, there is limited opportunity to install a bike path, while also retaining curbside parking on both sides of Monroe Street and two travel lanes. Accordingly, the proposed concept eliminates the southbound travel lane, turning Monroe Street into one-way northbound from Montgomery Ave to East Middle Lane, as shown in Figure 10.




Figure 10: Bike path concept, northern terminus and crossing at East Middle Lane

This design retains all existing curbside parking. This block of Monroe Street sees only about 1000 vehicles per day, with a 90%/10% northbound/southbound split. It is reasonable to expect that those 100 daily southbound trips can be absorbed into the City's grid network with minimal impacts. Additionally, the bike path terminates with a green bike crosswalk that connects it to the pending bike lanes on East Middle Lane. Finally, the existing median is proposed to be closed, since westbound lefts and northbound lefts through the median opening are already prohibited.



Concept 2: Two-way inroad cycletrack

As shown in Figure 11, the cycletrack option begins in the west, similar to the bike path option with a shared pedestrian/bike landing area off of Maryland Ave. The on-road two-way cycletrack option replaces the outside eastbound travel lane with a 9-foot two-way bike facility and 3-foot buffer shown as pre-cast concrete curbs.




Figure 11: West terminus of cycletrack option

Because the cycletrack is at the same grade as the roadway, the bus stop crossing is shown as a raised ramp through the cycletrack, and a crosswalk is shown to allow ADA-compliant crossing for transit users. A partially-protected intersection is proposed at the intersection of Fleet Street and Monroe Street, where cyclists would cross with pedestrians using the WALK phase. The bike crosswalks are situated to maximize the visibility of cyclists in the crosswalk by right- and left-turning drivers. Similar to the bike path, the southbound bike lanes along Monroe Street bend away from the intersection on the approach to Fleet Street, in order to increase the visibility of cyclists to turning motorists. Generally, the turn volumes in the peak hours are low, such that protected-only bike movements through the intersection are not necessary.

As shown in Figure 12, the cycletrack terminates at RMHS, where it merges with the existing sidewalk and connects to the existing shared use path by the midblock crossing.



Figure 12: Eastern terminus of proposed cycletrack at RMHS



Driveway crossings are marked with green bike crosswalks. Similar to the bike path option, all metered spaces are proposed to be removed.

As shown in Figure 13, the two-way cycletrack along Monroe Street crosses MD 28 (Jefferson Street) in in a separate crosswalk from pedestrians. Per MDOT SHA policy, two-way cycletracks must have dedicated (but not necessarily exclusive) phasing similar to the WALK phase for pedestrians. The WALK phase can be concurrent for both walkers and cyclists and must meet the minimum bike clearance time (similar to the flashing DON'T WALK phase for pedestrians). No other turn movements across the cycletrack are permitted during the WALK phase for the bikes. Accordingly, there are several timing options available:

- Pedestrians and cyclists receive concurrent WALK phase, and all vehicle traffic is given a red light.
- Other vehicle movements can be allowed to maximize the efficiency of the intersection, when the WALK phase is provided, and no bikes are present:
 - Optionally, the southbound left turn lane of Monroe can be provided a green arrow.
 - Optionally, the northbound left turn can be given a red arrow, while the northbound through/right lane is provided a green phase.
 - The left turns can be prohibited, and the left turn lane becomes a through lane and the
 outside northbound lane becomes a right only lane (note, this will require altering the
 lane widths to ensure that the lateral shift of northbound traffic through the
 intersection is minimized).




Figure 13: cycletrack concept crossing MD 28 (Jefferson Street)



A final option is for the WALK phase for bikers and pedestrians to be activated only, such that users need to request the WALK phase via a pedestrian push button. It should be noted that Rockville is moving away from these type of activated WALK phases – particularly in the Town Center area.

North of Monroe Place, the proposed cycletrack transitions to an off-road bike path, identical to the first option discussed – as shown previously in Figure 10. This transition from on-road to off-road occurs due to Monroe Street road width narrowing and bumpouts, north of Monroe Place.

Appendix C contains the full conceptual drawing set for the on-road cycletrack option.

IMPACTS ANALYSIS

Table 2 shows the estimated impacts as well as construction quantities for each of the two concepts. An impact analysis was also conducted on additional concept that represented a combination of the first two, where a cycletrack is proposed for Fleet Street, where bike/pedestrian activity is lower than the Town Center core, and an off-road bike path on Monroe Street, where pedestrian and bike activity is greater and off-road non-vehicle facilities are more amenable and familiar to drivers.

Table 2: Estimated Impacts and Quantities for off-road bike path and on-road cycletrack options

Metric	Cycletrack	Side Path	Combination (cycletrack only on Fleet)
LOD (sf)	7,500	34,500	22,000
Impervious area change (sf)	500 reduction	2500-3000 reduction	2000-2500 reduction
Inlets relocated	2	8	6
Utility/light poles relocated	2	2	2
Driveways reconstructed	0	9	5
	0 or 4 on Middle &	0 or 4 on Middle &	0 or 4 on Middle & 7 on
parking spaces lost	7 on Fleet	7 on Fleet	Fleet
Change in traffic LOS	LOS is unchanged	LOS is unchanged	LOS is unchanged
Bike Level of Stress	LTS 1	LTS 1	LTS 1
Estimated Cost	\$400,000	\$1,000,000	\$760,000
Other Notes	lowest cost	SUP more commonplace; highest cost	Removes need for bike phases

As shown in the table above, the Limits of Disturbance (LOD) is highest for the off-street bike path; the LOD impacts the size of the stormwater management mitigation needed to serve the project. However, both concepts, as well as the combination of the two described earlier, have a net reduction in overall impervious pavement, due largely to each concept replacing an existing asphalt travel lane.

Parking and traffic impacts

All concepts will remove 7 paid meter spaces along the south side of Fleet Street. Depending on the alternative chosen, there can as little as zero spaces lost on Monroe Street if it is converted to one-way



operations north of Monroe Place. If two-lane operations are to remain for this segment, then 4 southbound curbside spaces would be removed between Monroe Place and Montgomery Ave, and 5 southbound curbside spaces would be removed between Montgomery Ave and Middle Lane.

Traffic impacts are minimal, due to the excess roadway capacity on Fleet Street and Monroe Street. The overall LOS for each intersection would remain unchanged – even before accounting for any signal timing changes that would likely occur with a road diet. As shown in Table 3, the bike path has no impact on the intersection LOS for each study area intersection. Also, note that in the PM peak hour, the intersection of MD 28 (Jefferson St) at Monroe place degrades from a C to a D. This degradation happens under the assumption that the WALK phase for bikes is an exclusive phase, with no other vehicles permitted to enter the intersection. Since this is not a specific requirement, per MDOT SHA, a traffic analysis shows that (in the last column of Table 3) the intersection has no changes in LOS, under the assumption that all northbound Monroe Street traffic through the intersection is permitted and that left turn traffic is prohibited. Other similar traffic assumptions would yield similar results, such as permitting southbound left turns and providing northbound traffic with a green light, while providing northbound left turns with a red arrow.

Table 3: Intersection-level traffic impact summary, LOS AM (PM)

Intersection	Existing Conditions	Bike Path	2-way Cycletrack with Exclusive WALK across MD 28	2-way Cycletrack with concurrent northbound traffic at MD 28
Monroe St & E Middle Ln	A (A)	A (A)	A (A)	A (A)
Monroe St & E Montgomery Ave	A (A)	A (A)	A (A)	A (A)
Monroe St & Monroe Pl	A (A)	A (A)	A (A)	A (A)
Monroe St & E Jefferson St	B (C)	B (C)	C (D)	C (C)
Monroe St & Fleet St	B (B)	B (B)	B (B)	B (B)
Maryland Ave & Fleet St	C (E)	C (F)	C (F)	C (F)

Construction Costs

Based on the estimated quantities for each concept, the planning level construction cost is:

Concept 1, Off-road bike path: \$1,000,000Concept 2, On-road cycletrack: \$400,000

Concept 3, Combination of off-road path and on-road lanes: \$760,000

These estimates include a cost for relocating overhead utilities, relocating drainage inlets, driveway apron reconstruction, new curb and gutter, new asphalt path, new traffic signals, signing and pavement markings. The cost estimate breakdown is shown in <u>Appendix D</u>.

Public Meeting

On May 4, 2023, a virtual public meeting was held with City residents. The meeting was advertised by the City's Department of Public Works, and it coincided with the publishing of a presentation and conceptual drawings set on the City's website. The public meeting consisted of a presentation, review of the concept plans and discussion of the different options. The presentation can be found in Appendix

¹ While the LOS in the PM peak hour at the intersection of Maryland Ave at Fleet Street degrades from an E to F, in reality the average vehicle delay only degrades from 80 seconds to 81 seconds, which happens to be the numerical threshold between the assigned letter grades for LOS.



E and generally covered the project's purpose and need; concept overview; impacts; design assumptions, and next steps in project process. A question and answer session with residents followed the presentation, with a summary of the comments/questions below:

- Proposed parking removal (7 spaces) on Fleet Street, east of Monroe Street, is acceptable, since there is rarely any vehicle parked there.
- Given the added activity expected on Fleet Street, provide better pedestrian/bike lighting.
- Preference for scooter drop off areas and public bike racks along Fleet and Monroe Streets
- Pedestrian waiting areas at intersections are crowded; during the next design stage of the project, incorporate large pedestrian landing areas at all quadrants of Fleet/Monroe.
- The current configuration of Fleet Street has two off-set eastbound/westbound shared-left lanes at the east and west approaches to Monroe Street. When there is a left-turning vehicle in each of the lanes at the same time, they obscure each other from seeing upstream traffic, making left turn maneuvers difficult. Request for a left arrow was made.
 - Note: Both proposed options reduce Fleet Street to 3 lanes with opposing (i.e., not offset) left turn only lanes. This configuration will substantially reduce vehicle obstruction of upstream through traffic for both eastbound and westbound drivers.

DESIGN CONSIDERATIONS AND NEXT STEPS

Design Summary and Future Considerations

Generally speaking, design considerations for each concept include:

- Complete Streets can be accommodated on both Monroe Streets and Fleets by incorporating
 dedicated bike (and micromobility) only facilities, because sidewalk exists on both sides of both
 roads. Additionally, these bike facilities can provide a buffer between pedestrians and vehicle
 traffic and maintain vertical and horizontal separation of the SUP from vehicle traffic. By providing
 a wide-enough SUP, cyclists and pedestrians could mix with obstructing each other.
- The on-road option is shown having a horizontal and vertical buffer from the vehicle travel lanes, consisting of a three foot wide precast concrete curb. There are other less expensive buffers such as a painted hatched buffer with alternating flex posts and wheel stops. A key design requirement is ample horizontal buffer (minimum 3 feet) and a vertical buffer. The raised bike-only side path generally has a 3-foot buffer between it and the curb. This buffer is shown as grass to accommodate roadside signage, where needed.
- Bike facility width is between 9 and 10 feet. Because the path or cycletrack is not a shared use, eight-foot wide pinch points can be allowed to avoid utility pole or light post relocation. If the bike path is immediately adjacent to the sidewalk, a different material than concrete should be used. Additionally, bike markings should be applied along the path.



- Design should incorporate ADA compliance through bus stops, per Montgomery County's bus stop design guidelines.
- If a cycle track is chosen for Fleet Street, the buffers between the bike lanes and travel lanes need to have ample openings to allow a vehicle to safely back out of the residential driveways (see Figure 14).
- Design should minimize mature tree removal.
- Design should minimize expensive utility relocations, such as above ground utility poles, by meandering a bike path or narrowing at spot locations.




Figure 14: Vehicles backing up onto Fleet Street

- Design should consider ease of long-term maintenance.
- To minimize costs for the raised bike path option, consider channel drain can be utilized in lieu of relocating inlets, where the curb line is moved. See Figure 15.
- Because each option has over 5,000 square feet of disturbance, stormwater management mitigation is required.
- A protected intersection is recommended at the intersection of Fleet Street and Monroe Street, as shown in the concepts, however, protected only phasing for cyclists is likely not needed as turn volumes are generally low.



Figure 15: example of channel drain under sidewalk

- Coordination with MDOT SHA during the design phase of the
 project is required to address crossing MD 28. A on-road cycletrack will require protected, but
 not exclusive WALK phase (coincident with the pedestrian WALK phase), but an offroad bike path
 adjacent to the sidewalk may not require a distinct phase for crossing MD 28, depending on the
 design of the crosswalk. A shared bike and pedestrian crossing, for example, may eliminate the
 need for a dedicated WALK phase for cyclists. Irrespective of the selected concept, modification
 of the northbound and southbound lane usage, as well as minor signal timing adjustments, will
 maintain the intersection with an LOS D or better.
- Bike wayfinding signage and destination markers are recommended during the next design phase.

Preferred Option and Next Steps in the Design Process

The next step in the design process is to select a concept for advancement into 30% design and then secure funding for 30% design. Based on follow-up discussions, City Staff is recommending the grade-separated bike path option for advancement into 30% design. This design stage will include topographic survey and a boundary survey to locate exact lot lines and public right of way limits, as well as any existing easements. This stage will also evaluate options for stormwater mitigation and identify any additional permits required for construction. 30% design also entails a more accurate construction cost estimate. Additionally, all public and private stakeholders should be identified and notified of the next design stage, even if all construction occurs in public right of way. An additional public meeting should be held during the 30% design phase to ensure that all public comments from this current stage were addressed.

During the 30% design phase, the process should begin to secure funding for 65% Design and Final Design. During the 65% design phase, all necessary permits are obtained including SWM approval by Montgomery



County DPS. The final step is to secure funding for, and begin, construction. Note, that construction (and even design) can occur in phases, as this project has the potential to be both costly and could require a significant amount of time if utility relocation is needed.

FUNDING OPPORTUNITIES

Funding for projects can often be an obstacle to implementation. In addition to using local funds, there are several state/federal grant programs that offer monetary support for implementing the recommended bicycle facilities in this study. Some of the following funding sources identified as applicable include:

Transportation Alternatives Program (TAP). This program is administered and supported by the Maryland State Highway Administration, with reimbursement from the Federal Highway Administration, for the purpose of funding projects that enhance the cultural, aesthetic, historic, and environmental aspects of the State's intermodal transportation system. The program is set up to sub-allocate fifty percent of the funding directly to local Metropolitan Planning Organizations who are the responsible reviewers of proposed projects within their jurisdiction. Recommendations under this study would be eligible as they meet the requirements of 1) related to surface transportation; and 2) meet at least one of the ten qualifying TAP categories – such as New Walking and Biking Connections and Facilities; or Safe Routes to School (SRTS); or related environmental mitigation. Project sponsors are responsible for design, management, construction, implementation, and permits as well as a minimum of 20% of all project costs. MDOT recently updated their tap manual at: https://roads.maryland.gov/OPPEN/TAP_Manual_2022.pdf.

Maryland Bikeways Program. Supported and administered by the Maryland Department of Transportation, the goal of the program is to fill in the gaps in Maryland's bike network to support biking and bikeshare programs. An eligible project meets one of the following criteria: 1) located substantially within the Priority Funding Area (PFA) and/or located within three miles of a rail transit station or major bus transit hub, 2) provide or enhance bicycle access along any gap identified in the Statewide Trails Plan "A Greener Way to Go", and/or 3) identified as a transportation priority in a County's most recent annual priority letter submitted to MDOT. Note that all projects in this report are within a PFA (either State or Municipal PFA) and all projects are withing the three miles of rail transit. The local match requirements are a) zero percent for priority minor retrofit, b) twenty percent for other priority projects, and c) fifty percent for non-priority projects. The match may include cash or in-kind services contributing to the project such as expenditures up to twenty-four months prior to a Bikeways project award.

Safe Routes to Schools. Administered by the State Highway Administration and supported by an 80/20 federal to local match, this program funds infrastructure and non-infrastructure projects that support safe and sustainable routes for K-8 aged children to walk, roll, or bicycle to school. Projects categorized as safe routes to school must be requested through the larger Transportation Alternatives Program. Eligible project types that overlap with the recommendations under this study include traffic calming and speed reduction improvements, bike/pedestrian crossing improvements, and bicycle parking. This program would be applicable, as Richard Montgomery High School is located within the project area – allowing the City or County to qualify for Safe Routes to School funding.

MWCOG Transportation Land Use Connections (TLC) Grants. As members of MWCOG, Rockville and Montgomery County can apply for Planning and Design grants to fund studies or designs for planned projects. The TLC Program will provide consultant assistance, valued between \$30,000 - \$60,000 for

Fleet and Monroe Streets, Complete Streets Study



planning projects and up to \$80,000 for design or preliminary engineering projects, for projects that promote mixed-use, walkable communities and support a variety of transportation alternatives. These are annual grants and are competitive among the jurisdictional members.

MWCOG Transit Within Reach Program (TWR) Grants. The Transit Within Reach Program provides funding for design and preliminary engineering (up to 30% design) for projects that improve biking and walking connections to existing high-capacity transit stations, including include Metrorail, commuter rail, light rail, streetcar, bus rapid transit, and multimodal stations. Project categories may include (but are not limited to): Cost estimates of improvements; engineering systems description and analysis; preliminary or schematic drawings with site plans and elevations; renderings of site massing, elevation, or facility interior/exterior spaces; Site surveys. Grants are currently offered on a biennial cycle between FY 2021 and FY 2026. Approximately \$80,000 will be available per grant.

Fleet and Monroe Streets, Complete Streets Study APPENDICES



Appendix A: Traffic counts

City of Rockville Traffic & Transportation Division

File Name: MDAve@FleetSt

Site Code : 00000028 Start Date : 10/6/2022


							Groups	Printed	I- Unshif	fted							
	N	B Maryl	and Ave	Э		WB FI	eet St		S	B Maryl	and Ave	Э	City H	all Lowe	er Parki	ng Lot	
		From	North			From	East			From	South			From	West		
Start Time	Right	Thru	Left	Peds	Right	Thru	Left	Peds	Right	Thru	Left	Peds	Right	Thru	Left	Peds	Int. Total
07:00 AM	1	45	8	2	3	0	34	2	54	30	0	0	0	0	0	0	179
07:15 AM	0	80	13	1	5	0	35	0	85	29	0	0	0	0	0	3	251
07:30 AM	1	49	31	1	27	1	87	0	174	50	0	0	0	0	0	1	422
07:45 AM	0	82	30	1	54	0	116	1	105	83	0	1	0	0	0	1	474
Total	2	256	82	5	89	1	272	3	418	192	0	1	0	0	0	5	1326
08:00 AM	2	57	13	1	8	0	82	1	90	58	0	1	0	1	1	4	319
08:15 AM	3	57	13	0	12	1	30	0	82	85	0	1	0	0	1	1	286
08:30 AM	2	53	12	0	7	1	40	0	88	80	0	1	0	1	3	0	288
08:45 AM	4	43	6	1	8	1	29	0	102	80	0	0	0	1	3	1	279
Total	11	210	44	2	35	3	181	1	362	303	0	3	0	3	8	6	1172
09:00 AM *** BREAK ***	3	48	8	0	6	1	28	1	88	68	0	0	0	0	1	2	254
Total	3	48	8	0	6	1	28	1	88	68	0	0	0	0	1	2	254
*** BREAK ***																	
04:00 PM	0	65	5	0	19	0	74	2	77	77	0	0	0	2	2	2	325
04:15 PM	0	79	6	0	12	0	86	3	92	91	0	3	1	1	0	0	374
04:30 PM	1	71	5	0	18	0	75	4	116	76	0	2	0	0	1	0	369
04:45 PM	1	61	4	2	28	0	89	1	111	102	0	1	0	1_	5	3	409
Total	2	276	20	2	77	0	324	10	396	346	0	6	1	4	8	5	1477
05:00 PM	0	71	8	0	21	1	73	2	100	69	0	1	0	1	2	2	351
05:15 PM	1	105	4	3	13	0	65	1	88	85	0	1	2	2	4	0	374
05:30 PM	0	86	9	2	16	0	43	3	109	104	0	1	0	0	2	3	378
05:45 PM	0	69	6	0	16	0	57	2	118	94	0	0	0	0	2	0	364
Total	1	331	27	5	66	1	238	8	415	352	0	3	2	3	10	5	1467
06:00 PM	0	61	5	0	10	0	50	0	102	98	0	0	0	0	0	1	327
Grand Total	19	1182	186	14	283	6	1093	23	1781	1359	0	13	3	10	27	24	6023
Apprch %	1.4	84.4	13.3	1	20.1	0.4	77.8	1.6	56.5	43.1	0	0.4	4.7	15.6	42.2	37.5	
⊤otal %	0.3	19.6	3.1	0.2	4.7	0.1	18.1	0.4	29.6	22.6	0	0.2	0	0.2	0.4	0.4	

City of Rockville Traffic & Transportation Division

File Name: MDAve@FleetSt

Site Code : 00000028 Start Date : 10/6/2022

		NB N	/larylar	nd Ave	!		W	B Flee	t St			SB N	/laryla	nd Ave	;	City	y Hall I	Lower	Parkir	ng Lot]
		F	rom No	orth			F	rom E	ast			Fr	om So	outh			F	rom W	/est		
Start Time	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Int. Total
Peak Hour A	Analys	is Fro	m 07:0	00 AM	to 11:4	5 AM -	Peak	1 of 1													
Peak Hour f	or Ent	ire Inte	ersecti	on Beg	gins at (07:30	AM														
07:30 AM	1	49	31	1	82	27	1	87	0	115	174	50	0	0	224	0	0	0	1	1	422
07:45 AM	0	82	30	1	113	54	0	116	1	171	105	83	0	1	189	0	0	0	1	1	474
08:00 AM	2	57	13	1	73	8	0	82	1	91	90	58	0	1	149	0	1	1	4	6	319
08:15 AM	3	57	13	0	73	12	1	30	0	43	82	85	0	1	168	0	0	1	1	2	286
Total Volume	6	245	87	3	341	101	2	315	2	420	451	276	0	3	730	0	1	2	7	10	1501
% App. Total	1.8	71.8	25.5	0.9		24	0.5	75	0.5		61.8	37.8	0	0.4		0	10	20	70		
PHF	500	747	702	750	754	468	500	679	500	614	648	812	000	750	815	000	250	500	438	417	792




Page 54 of 210

City of Rockville Traffic & Transportation Division

File Name: MDAve@FleetSt

Site Code : 00000028 Start Date : 10/6/2022

			larylar	nd Ave				B Flee					Marylar	nd Ave		City	•	Lower		ng Lot	
Start Time	Right		Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru			App. Total	Right	Thru	_	Peds	App. Total	Int. Total
Peak Hour A	Analys	is Fror	n 12:0	0 PM	to 06:00	0 PM -	Peak	1 of 1													
Peak Hour f	or Enti	ire Inte	rsecti	on Beg	gins at (04:45	PM														
04:45 PM	1	61	4	2	68	28	0	89	1	118	111	102	0	1	214	0	1	5	3	9	409
05:00 PM	0	71	8	0	79	21	1	73	2	97	100	69	0	1	170	0	1	2	2	5	351
05:15 PM	1	105	4	3	113	13	0	65	1	79	88	85	0	1	174	2	2	4	0	8	374
05:30 PM	0	86	9	2	97	16	0	43	3	62	109	104	0	1	214	0	0	2	3	5	378
Total Volume	2	323	25	7	357	78	1	270	7	356	408	360	0	4	772	2	4	13	8	27	1512
% App. Total	0.6	90.5	7	2		21.9	0.3	75.8	2		52.8	46.6	0	0.5		7.4	14.8	48.1	29.6		
PHF	.500	.769	.694	.583	.790	.696	.250	.758	.583	.754	.919	.865	.000	1.0	.902	.250	.500	.650	.667	.750	.924



Page 55 of 210

City of Rockville Traffic & Transportation Division

File Name: Monroe St@Fleet St

Site Code : 00000036 Start Date : 10/11/2022


							Groups	Printed	- Unshif	ted							
		SB Mor	roe St			WB Fl	eet St			NB Mor	nroe St			EB FI	eet St		
		From	North			From	East			From	South			From	West		
Start Time	Right	Thru	Left	Peds	Right	Thru	Left	Peds	Right	Thru	Left	Peds	Right	Thru	Left	Peds	Int. Total
07:00 AM	10	10	5	1	4	13	1	0	3	13	1	4	6	37	16	6	130
07:15 AM	13	3	11	2	6	26	1	2	1	3	4	1	6	49	25	10	163
07:30 AM	13	6	18	12	22	59	2	1	5	9	8	4	10	134	26	21	350
07:45 AM	22	12	16	6	41	145	4	0	8	23	15	5	15	110	38_	15	475
Total	58	31	50	21	73	243	8	3	17	48	28	14	37	330	105	52	1118
08:00 AM	24	13	5	2	9	50	0	0	3	22	11	7	19	40	40	3	248
08:15 AM	24	12	4	0	9	21	4	4	5	15	9	3	18	30	44	1	203
08:30 AM	20	13	8	0	4	25	2	3	5	27	10	5	9	27	45	3	206
08:45 AM	19	12	4	0	4	20	3	0	3	8	7	1	19	39	39	2	180
Total	87	50	21	2	26	116	9	7	16	72	37	16	65	136	168	9	837
09:00 AM *** BREAK ***	13	10	2	1	5	21	3	1	3	20	6	4	15	39	41	1	185
Total	13	10	2	1	5	21	3	1	3	20	6	4	15	39	41	1	185
*** BREAK ***																	
04:00 PM	23	21	2	1	15	46	1	6	0	23	5	3	20	41	32	0	239
04:15 PM	20	18	2	1	14	42	2	3	5	14	2	3	17	28	35	4	210
04:30 PM	40	10	2	0	9	42	4	1	3	19	5	7	16	51	30	3	242
04:45 PM	33	16	3	2	13	31	6	4	1_	19	3	8	24	44	37	3	247
Total	116	65	9	4	51	161	13	14	9	75	15	21	77	164	134	10	938
05:00 PM	31	19	1	6	9	64	2	9	2	11	2	0	17	56	36	0	265
05:15 PM	30	28	3	1	13	43	1	5	1	17	1	8	26	38	54	1	270
05:30 PM	27	27	3	6	4	37	1	3	2	13	3	5	30	33	43	3	240
05:45 PM	16	24	2	1	7	31	3	2	2	22	1	5	16	27	29	0	188
Total	104	98	9	14	33	175	7	19	7	63	7	18	89	154	162	4	963
06:00 PM	16	14	1	3	11	30	4	0	3	16	7	4	16	46	33	0	204
Grand Total	394	268	92	45	199	746	44	44	55	294	100	77	299	869	643	76	4245
Apprch %	49.3	33.5	11.5	5.6	19.3	72.2	4.3	4.3	10.5	55.9	19	14.6	15.8	46.1	34.1	4	
Total %	9.3	6.3	2.2	1.1	4.7	17.6	1	1	1.3	6.9	2.4	1.8	7	20.5	15.1	1.8	

City of Rockville Traffic & Transportation Division

File Name: Monroe St@Fleet St

Site Code : 00000036 Start Date : 10/11/2022

		SB	Monro	ne St			W	B Flee	t St			NR	Monr	ne St			F	B Flee	t St]
		_	om N					rom E					om S					rom W			
Start Time	Right	Thru	Left	Peds	App. Total	Right		Left	Peds	App. Total	Right	Thru	_	Peds	App. Total	Right	Thru		Peds	App. Total	Int. Total
Peak Hour A	Analys	is Fror	n 07:0	00 AM				1 of 1													
Peak Hour f	•																				
07:30 AM	13	6	18	12	49	22	59	2	1	84	5	9	8	4	26	10	134	26	21	191	350
07:45 AM	22	12	16	6	56	41	145	4	0	190	8	23	15	5	51	15	110	38	15	178	475
08:00 AM	24	13	5	2	44	9	50	0	0	59	3	22	11	7	43	19	40	40	3	102	248
08:15 AM	24	12	4	0	40	9	21	4	4	38	5	15	9	3	32	18	30	44	1	93	203
Total Volume	83	43	43	20	189	81	275	10	5	371	21	69	43	19	152	62	314	148	40	564	1276
% App. Total	43.9	22.8	22.8	10.6		21.8	74.1	2.7	1.3		13.8	45.4	28.3	12.5		11	55.7	26.2	7.1		
PHF	865	827	597	417	.844	494	474	625	.313	.488	656	750	717	679	.745	.816	586	841	476	.738	.672




Page 57 of 210

City of Rockville Traffic & Transportation Division

File Name: Monroe St@Fleet St

Site Code : 00000036 Start Date : 10/11/2022

		SB	Monro	oe St			W	B Flee	et St			NB	Monr	oe St			Е	B Flee	t St]
		Fr	om No	orth			F	rom E	ast			Fr	om So	outh			F	rom W	/est		
Start Time	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Int. Total
Peak Hour A	Analys	is Fron	n 12:0	0 PM	to 06:0) PM -	Peak	1 of 1													
Peak Hour f	or Enti	ire Inte	rsecti	on Beg	gins at	04:30	PM														
04:30 PM	40	10	2	0	52	9	42	4	1	56	3	19	5	7	34	16	51	30	3	100	242
04:45 PM	33	16	3	2	54	13	31	6	4	54	1	19	3	8	31	24	44	37	3	108	247
05:00 PM	31	19	1	6	57	9	64	2	9	84	2	11	2	0	15	17	56	36	0	109	265
05:15 PM	30	28	3	1	62	13	43	1	5	62	1	17	1	8	27	26	38	54	1	119	270
Total Volume	134	73	9	9	225	44	180	13	19	256	7	66	11	23	107	83	189	157	7	436	1024
% App. Total	59.6	32.4	4	4		17.2	70.3	5.1	7.4		6.5	61.7	10.3	21.5		19	43.3	36	1.6		
PHF	838	652	750	375	907	846	703	542	528	762	583	868	550	719	787	798	844	727	583	916	948



Page 58 of 210

7055 Samuel Morse Dr. Ste. 100 Columbia, Maryland 21045 443-741-3500

Weather: File Name: MD 355 AT MD 28-MD 586

 Counted By:
 Site Code : 00000000

 Town:
 Start Date : 9/20/2022

Country Page No : 1

Crounc	Drintod	VFHS&PFDS

Γ				MD 35	55				MD 58		mileu-	VENS		MD 35	55				MD 2	<u>α</u>		
				om No					rom E					om So				F	rom W	-		
ŀ	Start Time	Left	Thru	Right		App. Total	Left	Thru	Right	Peds	App. Total	Left	Thru	Right		App. Total	Left	Thru	Right	Peds	App. Total	Int. Total
L	06:00 AM	14	70	1	0	85	0	55	21	1	77	8	27	0	0	35	0	19	23	0	42	239
	06:15 AM	16	114	3	0	133	0	81	32	0	113	10	38	0	0	48	0	13	32	0	45	339
	06:30 AM	41	106	4	Ő	151	Ö	118	46	1	165	15	35	0	0	50	0	38	28	1	67	433
	06:45 AM	34	174	5	Ő	213	Ö	129	59	0	188	18	58	0	Ö	76	0	38	48	1	87	564
-	Total	105	464	13	0	582	0	383	158	2	543	51	158	0	0	209	0	108	131	2	241	1575
	i otai į				Ū	002	, ,	000	100	_	0.10	0.	.00	Ŭ	Ŭ	200	·		101	_		1070
	07:00 AM	39	184	6	0	229	0	120	60	1	181	15	58	0	0	73	0	42	50	3	95	578
	07:15 AM	62	276	13	Ö	351	ő	149	62	0	211	23	75	0	Ö	98	0	55	53	7	115	775
	07:30 AM	66	351	12	Ö	429	0	162	87	0	249	43	130	0	Ö	173	0	65	64	5	134	985
	07:45 AM	78	298	9	Ö	385	ő	173	122	0	295	41	131	0	Ö	172	Ö	75	83	2	160	1012
-	Total	245	1109	40	0	1394	0	604	331	1	936	122	394	0	0	516	0	237	250	<u>_</u> _	504	3350
					-					-					-							
	08:00 AM	93	296	10	0	399	0	169	81	2	252	44	128	0	0	172	0	80	80	0	160	983
	08:15 AM	88	263	18	0	369	Ō	179	97	0	276	42	136	0	0	178	0	87	78	3	168	991
	08:30 AM	74	293	8	1	376	0	158	110	3	271	38	127	0	0	165	0	60	92	0	152	964
	08:45 AM	81	290	15	0	386	Ō	149	122	3	274	52	131	0	0	183	0	64	89	1	154	997
-	Total	336	1142	51	1	1530	0	655	410	8	1073	176	522	0	0	698	0	291	339	4	634	3935
																•						
	09:00 AM	74	262	8	0	344	0	112	134	0	246	40	152	0	0	192	0	69	105	0	174	956
	09:15 AM	63	200	10	0	273	0	124	142	3	269	35	168	0	0	203	0	72	82	1	155	900
	09:30 AM	81	231	12	0	324	0	105	109	0	214	34	127	0	0	161	0	66	56	3	125	824
	09:45 AM	79	182	17	0	278	0	108	107	0	215	31	124	0	0	155	0	68	77	5	150	798
	Total	297	875	47	0	1219	0	449	492	3	944	140	571	0	0	711	0	275	320	9	604	3478
	,															1						II
	10:00 AM	79	170	12	0	261	0	72	91	0	163	52	161	0	0	213	0	56	75	2	133	770
	10:15 AM	65	179	24	0	268	0	83	94	2	179	44	164	0	0	208	0	62	52	0	114	769
	10:30 AM	82	163	9	0	254	0	67	109	0	176	36	147	0	0	183	0	53	67	2	122	735
-	10:45 AM	87_	198	10	0	295	0	<u>76</u>	117	3_	196	42	159	0	0	201	0	68	78_	0_	146	838
	Total	313	710	55	0	1078	0	298	411	5	714	174	631	0	0	805	0	239	272	4	515	3112
	11:00 AM	99	199	11	0	309	۱ ۵	72	95	0	167	49	169	0	0	218	0	55	54	4	110	804
	11:00 AM		208	7	0	313	0	87	93 88	2	177	49	186	0	0	232	0	55 57	75	1 3	135	857
	11:30 AM	98 94	204	15	0	313	0	64	80	0	144	55	204	0	0	252	0	66	60	2	128	844
	11:45 AM	70	204	13	0	287	0	67	113	1	181	61	190	0	0	259	0	62	77	4	143	862
-	Total	361	815	46	0	1222	0	290	376	3	669	211	749	0	0	960	0	240	266	10	516	3367
	Total	301	013	40	U	1222	0	290	3/0	3	009	211	149	U	U	900	0	240	200	10	310	3307
	12:00 PM	7	22	1	0	30	0	18	17	0	35	12	31	0	0	43	0	17	4	0	21	129
	12:15 PM	76	143	9	0	228	0	49	85	0	134	49	169	0	0	218	0	44	42	3	89	669
	12:30 PM	101	232	15	0	348	0	98	101	0	199	54	213	0	0	267	0	89	58	3	150	964
	12:45 PM	97	243	13	0	353	0	71	92	0	163	66	228	1	0	295	0	80	58	2	140	951
-	Total	281	640	38	0	959	0	236	295	0	531	181	641	1	0	823	0	230	162	<u></u>	400	2713
					_					_		-	-		_							-
	01:00 PM	111	209	15	0	335	0	94	84	1	179	54	213	3	0	270	0	74	50	4	128	912
	01:15 PM	89	198	18	0	305	0	99	75	0	174	59	205	1	0	265	0	79	70	0	149	893
	01:30 PM	100	187	11	0	298	0	84	84	3	171	63	179	0	1	243	0	55	61	0	116	828
	01:45 PM	91	198	13	0	302	0	82	107	3	192	62	230	0	0	292	0	69	47	2	118	904
-	Total	391	792	57	0	1240	0	359	350	7	716	238	827	4	1	1070	0	277	228	6	511	3537
																						ı.
	02:00 PM	109	220	19	0	348	0	72	88	2	162	70	204	0	0	274	0	58	62	0	120	904
	02:15 PM	111	223	12	0	346	0	94	71	0	165	64	222	1	0	287	0	104	65	3	172	970
	02:30 PM	113	188	14	0	315	0	87	83	3	173	69	260	0	0	329	0	92	60	9	161	978
										_			_									

MEAD & HUNT

7055 Samuel Morse Dr. Ste. 100 Columbia, Maryland 21045 443-741-3500

File Name: MD 355 AT MD 28-MD 586

Site Code : 00000000 Start Date : 9/20/2022

Page No : 2

Groups Printed- VFHS&PFDS


								Gro	oups F	<u>rintea-</u>	VEHS	&PEL	15								
			MD 35	55				MD 58	36				MD 35	55				MD 2	8		
		Fı	rom N	orth			F	rom E	ast			Fr	om Sc	outh			F	rom W	est_		
Start Time	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Int. Total
02:45 PM	105	171	17	0	293	0	91	121	3	215	69	202	0	0	271	0	102	63	2	167	946
Total	438	802	62	0	1302	0	344	363	8	715	272	888	1	0	1161	0	356	250	14	620	3798
	ı					ı															
03:00 PM	108	173	10	0	291	0	84	134	3	221	56	150	1	0	207	0	85	56	4	145	864
03:15 PM	114	149	10	0	273	0	92	125	4	221	54	176	0	0	230	0	138	70	1	209	933
03:30 PM	124	148	6	0	278	0	131	121	2	254	67	235	1	0	303	0	102	47	4	153	988
03:45 PM	83	148	10_	0_	241	0	126	117	3_	246	64	256	1_	0_	321	0	117	66	2_	185	993
Total	429	618	36	0	1083	0	433	497	12	942	241	817	3	0	1061	0	442	239	11	692	3778
				_					_				_	_					_		
04:00 PM	135	218	17	0	370	0	141	116	0	257	63	257	0	0	320	0	104	72	2	178	1125
04:15 PM	137	207	11	0	355	0	120	105	2	227	82	256	1	0	339	0	154	58	3	215	1136
04:30 PM	120	216	13	0	349	0	110	98	1	209	62	261	1	0	324	0	153	58	0	211	1093
04:45 PM	135	206	13_	0	354	0	109	89_	4_	202	67	256	0	0_	323	0	132	57	3_	192	1071
Total	527	847	54	0	1428	0	480	408	7	895	274	1030	2	0	1306	0	543	245	8	796	4425
05:00 DM	400	045	47	0	200		440	400	0	000	74	050	0	0	220		450	- 7	4	040	4400
05:00 PM 05:15 PM	136 144	215 210	17 18	0	368 372	0	118 106	100 91	2	220 197	71 67	259 227	0	0	330 294	0	152 154	57	1	210	1128 1084
	139	-	_	0	-	0		-	0		85		0	0	-	0	132	66	1	221	
05:30 PM		201	20	0	360	0	99	99	2	200		228	1	0	314	1	-	85	4	222	1096
05:45 PM	116	<u>193</u> 819	<u>12</u> 67	<u>0</u>	321	0	82 405	88	4 8	174	305	270 984	<u>0</u> 1	0	352	0 1	138	58	<u>3</u> 9	199	1046
Total	535	019	07	U	1421	U	405	378	0	791	305	904	- 1	U	1290	ı	576	266	9	852	4354
Grand Total	4258	9633	566	1	14458	0	4936	4469	64	9469	2385	8212	12	1	10610	1	3814	2968	102	6885	41422
Apprch %	29.5	66.6	3.9	0		0	52.1	47.2	0.7	0 100	22.5	77.4	0.1	0	10010		55.4	43.1	1.5	5500	,22
Total %	10.3	23.3	1.4	0	34.9	0	11.9	10.8	0.2	22.9	5.8	19.8	0.1	0	25.6	0	9.2	7.2	0.2	16.6	
1 Otal 70	10.0	20.0		Ü	54.5		11.5	10.0	5.2	0	5.0	13.0	Ü	Ü	20.0		5.2		5.2	. 0.0	1

MEAD & HUNT

7055 Samuel Morse Dr. Ste. 100 Columbia, Maryland 21045 443-741-3500

File Name: MD 355 AT MD 28-MD 586

Site Code : 00000000 Start Date : 9/20/2022




7055 Samuel Morse Dr. Ste. 100 Columbia, Maryland 21045 443-741-3500

File Name: MD 355 AT MD 28-MD 586

Site Code : 00000000 Start Date : 9/20/2022

			MD 35	55				MD 58	36				MD 35	55				MD 2	8]
		Fr	om No	orth			F	rom E	ast			Fr	om Sc	outh			Fı	rom W	est		
Start Time	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Int. Tota
Peak Hour A	nalysi	s From	n 06:00	O AM to	o 11:45	AM - F	Peak 1	of 1													
Peak Hour fo	or Enti	re Inte	rsectio	n Beg	ins at 07	7:30 A	M														
07:30 AM	66	351	12	0	429	0	162	87	0	249	43	130	0	0	173	0	65	64	5	134	985
07:45 AM	78	298	9	0	385	0	173	122	0	295	41	131	0	0	172	0	75	83	2	160	1012
08:00 AM	93	296	10	0	399	0	169	81	2	252	44	128	0	0	172	0	80	80	0	160	983
08:15 AM	88	263	18	0	369	0	179	97	0	276	42	136	0	0	178	0	87	78	3	168	991
Total Volume	325	1208	49	0	1582	0	683	387	2	1072	170	525	0	0	695	0	307	305	10	622	3971
% App. Total	20.5	76.4	3.1	0		0	63.7	36.1	0.2		24.5	75.5	0	0		0	49.4	49	1.6		
PHF	.874	.860	.681	.000	.922	.000	.954	.793	.250	.908	.966	.965	.000	.000	.976	.000	.882	.919	.500	.926	.981




Page 62 of 210

7055 Samuel Morse Dr. Ste. 100 Columbia, Maryland 21045 443-741-3500

File Name: MD 355 AT MD 28-MD 586

Site Code : 00000000 Start Date : 9/20/2022

			MD 35	55				MD 58	36				MD 35	55				MD 2	8		[
		Fr	om No	orth			F	rom E	ast			Fr	om Sc	outh			F	rom W	est		
Start Time	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Int. Tot
Peak Hour A Peak Hour fo								of 1													
04:15 PM	137	207	11	0	355	0	120	105	2	227	82	256	1	0	339	0	154	58	3	215	113
04:30 PM	120	216	13	0	349	0	110	98	1	209	62	261	1	0	324	0	153	58	0	211	109
04:45 PM	135	206	13	0	354	0	109	89	4	202	67	256	0	0	323	0	132	57	3	192	107
05:00 PM	136	215	17	0	368	0	118	100	2	220	71	259	0	0	330	0	152	57	1	210	112
Total Volume	528	844	54	0	1426	0	457	392	9	858	282	1032	2	0	1316	0	591	230	7	828	442
% App. Total	37	59.2	3.8	0		0	53.3	45.7	1		21.4	78.4	0.2	0		0	71.4	27.8	0.8		
PHF	964	977	794	000	969	000	952	933	563	945	860	989	500	000	971	000	959	991	583	963	97



Page 63 of 210

7055 Samuel Morse Dr. Ste. 100 Columbia, Maryland 21045 443-741-3500

Weather: File Name: MD 355 AT MD 28-MD 586

 Counted By:
 Site Code : 00000000

 Town:
 Start Date : 9/20/2022

Country Page No : 1

Groups Pr	inted- U	TURNS
-----------	----------	-------


			MD 35	55				MD 58		Printed	I- U I		MD 35	55				MD 28	3		
		Fr	rom N					rom E					rom Sc				F	rom W			
Start Time	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Int. Total
*** BREAK **	**																				
07:15 AM *** BREAK **	0	0	0	0	0	0	0	0	0	0	1	0	0	0	1	1	0	0	0	1	2
Total	0	0	0	0	0	0	0	0	0	0	1	0	0	0	1	1	0	0	0	1	2
08:00 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	2	0	0	0	2	2
*** BREAK ** Total	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	2	0	0	0	2	2
*** BREAK **	**																				
09:30 AM *** BREAK **	0	0	0	0	0	0	0	0	0	0	1	0	0	0	1	0	0	0	0	0	1
Total	0	0	0	0	0	0	0	0	0	0	1	0	0	0	1	0	0	0	0	0	1
10:00 AM	0	0	0	0	0	0	0	0	0	0	1	0	0	0	1	0	0	0	0	0	1
10:15 AM	0	0	0	Ö	ő	0	0	0	Ö	o l	1	0	Ö	0	1	0	0	0	0	ő	1
10:30 AM *** BREAK **	0	0	0	0	0	0	0	0	0	0	2	0	0	0	2	0	0	0	0	0	2
Total	0	0	0	0	0	0	0	0	0	0	4	0	0	0	4	0	0	0	0	0	4
11:00 AM *** BREAK **	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1	0	0	0	1	1
11:30 AM *** BREAK **	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1	0	0	0	1	1
Total	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	2	0	0	0	2	2
*** BREAK ** 12:30 PM	**	0	0	0	0	0	0	0	0	0	1	0	0	0	1	0	0	0	0	0	1
*** BREAK **																					
Total	0	0	0	0	0	0	0	0	0	0	1	0	0	0	1	0	0	0	0	0	1
01:00 PM *** BREAK **	0	0	0	0	0	0	0	0	0	0	2	0	0	0	2	0	0	0	0	0	2
01:45 PM	0	0	0	0	0	0	0	0	0	0	1_	0	0	0	1	0	0	0	0	0	1_
Total	0	0	0	0	0	0	0	0	0	0	3	0	0	0	3	0	0	0	0	0	3
02:00 PM	0	0	0	0	0	0	0	0	0	0	2	0	0	0	2	0	0	0	0	0	2
02:15 PM 02:30 PM	0	0	0	0	0	0	0	0	0	0	1 2	0	0	0	1 2	0	0	0	0	0	1 2
*** BREAK *	•	U	U	U	0	U	U	U	U	0	2	U	U	U	2	U	U	U	U	0	2
Total	0	0	0	0	0	0	0	0	0	0	5	0	0	0	5	0	0	0	0	0	5
03:00 PM	0	0	0	0	0	0	0	0	0	0	1	0	0	0	1	0	0	0	0	0	1
03:15 PM *** BREAK **	0	0	0	0	0	0	0	0	0	0	1	0	0	0	1	0	0	0	0	0	1
Total	0	0	0	0	0	0	0	0	0	0	2	0	0	0	2	0	0	0	0	0	2
*** BREAK **	**																				
Grand Total	0	0	0	0	0	0	0	0	0	0	17	0	0	0	17	5	0	0	0	5	22
Apprch %	0	0	0	0		0	0	0	0	-	100	0	0	0		100	0	0	0		
Total %	0	0	0	0	0	0	0	0	0	0	77.3	0	0	0	77.3	22.7	0	0	0	22.7	

MEAD & HUNT

7055 Samuel Morse Dr. Ste. 100 Columbia, Maryland 21045 443-741-3500

File Name: MD 355 AT MD 28-MD 586

Site Code : 00000000 Start Date : 9/20/2022



7055 Samuel Morse Dr. Ste. 100 Columbia, Maryland 21045 443-741-3500

Weather: File Name: MD 355 AT MD 28-MD 586

 Counted By:
 Site Code : 00000000

 Town:
 Start Date : 9/20/2022

Country Page No : 1

										Printed-	BIC)										1
			MD 35	-				MD 58					MD 3				_	MD 2	-		
Start Time	Loft	Thru	Right	ortn Peds		Left	⊢ Thru	rom E	Peds		Left		om So		App. Total	Left	Thru	rom W Right	Peds	App. Total	Int. Total
06:00 AM	0	0	Right 1	Peus I	App. Total	0	0	0	1	App. Total	0	0	Right 0	Peus 0	App. Total	0	0	0) Peus	App. Total	Int. Total
06:15 AM	0	0	0	0	0	0	0	0	1	1	0	0	0	Ö	Ö	0	1	0	0	1	2
06:30 AM	0	1	0	0	1	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1
06:45 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1	1	1
Total	0	1	0	0	1	0	0	0	2	2	0	0	0	0	0	0	1	0	1	2	5
07:00 AM *** BREAK *	**	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1	1	1
07:30 AM *** BREAK *	**	1	0	0	1	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1
Total	0	1	0	0	1	0	0	0	0	0	0	0	0	0	0	0	0	0	1	1	2
*** BREAK *															ı						1
08:15 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	2	2	2
08:30 AM	0	1	0	0	1	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1
08:45 AM Total	0	0 1	<u>0</u>	0	0 1	0	0	0 0	<u>1</u> 1	1	0	0 0	0 0	<u>0</u> 0	0	0	0 0	0 0	0 2	0 2	4
09:00 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	2	0	0	2	2
09:15 AM	0	0	0	0	0	0	0	0	1	1	0	0	0	0	0	0	0	0	1	1	2
*** BREAK ** Total	0	0	0	0	0	0	0	0	1	1	0	0	0	0	0	0	2	0	1	3	4
*** BREAK *	**																				
10:30 AM	0	1	0	0	1	0	0	0	1	1	0	0	0	0	0	0	0	0	1	1	3
10:45 AM Total	0	0 1	0	0	<u> </u>	0	0	0	1 2	1 2	0	0	0	0	0	0	0	0	<u>0</u>	0 1	1 4
,	•	·	Ü	Ü	•	, ,	Ū	Ů	_	- 1	Ü	Ū	Ū	Ü	o ,		Ū	Ū		•	
*** BREAK ** 11:15 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1	1	1
11:30 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1	1	1
*** BREAK *	_	Ū	U	Ū	O	, 0	O	O	Ū	0	O	Ū	Ū	Ü	0		Ū	O	'	•	
Total	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	2	2	2
*** BREAK *																					II.
12:45 PM Total	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0 0	0	<u>1</u> 1	1 1	1
·	-	U	U	U	U	0	U	U	U	0	U	U	U	U	U	0	U	U	'	!	!
*** BREAK * 01:15 PM	** 1	0	0	0	1	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1
*** BREAK *										. 1	_		_		_ 1						1 .
01:45 PM Total	0 1	0	0	<u> </u>	<u> </u>	0	0	0	<u>1</u> 1	1	0	0	0 0	0	0	0	0 0	0	0	0	1
	-	0	3	3	•	, 0	3	J	'	' '	0	3	J	3	5		3	J	3	O	
*** BREAK * 02:15 PM	0	1	0	0	1	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1
*** BREAK *	**																				
Total	0	1	0	0	1	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
03:00 PM 03:15 PM	0	0	1 0	0	1 0	0	0	0	0	0	0	0	0	0	0 0	0	0	0	1	1 3	2


Page 66 of 210

7055 Samuel Morse Dr. Ste. 100 Columbia, Maryland 21045 443-741-3500

File Name: MD 355 AT MD 28-MD 586

Site Code : 00000000 Start Date : 9/20/2022

								G	roups	Printed	- BIC\	CLES	3								
			MD 35	55			1	MD 58	36				MD 35	55				MD 2	8		
		Fı	om N	orth			F	rom E	ast			Fr	om Sc	outh			Fı	rom W	est		
Start Time	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Int. Total
03:30 PM	0	0	0	0	0	0	0	0	2	2	0	0	0	0	0	0	0	0	1	1	3
03:45 PM	0	0	0	0	0	0	0	0	1_	1	0	0	0	0	0	0	0	0	2	2	3
Total	0	0	1	0	1	0	0	0	3	3	0	0	0	0	0	0	0	0	7	7	11
*** BREAK *	**																				
04:15 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1	1	1
04:30 PM	0	0	0	0	0	0	0	0	1	1	0	0	0	0	0	0	0	0	3	3	4
04:45 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1_	1	1_
Total	0	0	0	0	0	0	0	0	1	1	0	0	0	0	0	0	0	0	5	5	6
·																					
05:00 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1	1	1
05:15 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1	1	1
05:30 PM	0	0	0	0	0	0	0	1	0	1	0	0	1	0	1	0	0	0	0	0	2
05:45 PM	0	1	0	0	1	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1_
Total	0	1	0	0	1	0	0	1	0	1	0	0	1	0	1	0	0	0	2	2	5
Grand Total	1	6	1	0	8	0	0	1	11	12	0	0	1	0	1	0	3	0	23	26	47
Apprch %	12.5	75	12.5	0		0	0	8.3	91.7		0	0	100	0		0	11.5	0	88.5		
Total %	2.1	12.8	2.1	0	17	0	0	2.1	23.4	25.5	0	0	2.1	0	2.1	0	6.4	0	48.9	55.3	



Page 67 of 210

MEAD & HUNT

7055 Samuel Morse Dr. Ste. 100 Columbia, Maryland 21045 443-741-3500

Mead & Hunt

7055 Samuel Morse Drive Suite 100 Columbia, MD 21046 1 443 741 3500

Weather: File Name: MONROE ST AT JEFFERSON ST

Counted By: Site Code : 00000000
Town: Start Date : 10/26/2022

Country Page No : 1

Craina	Drintod	VFHS&PFDS	
CHOUDS	Printed-	VED9@FED9	

		MC	NRO	F ST			JEEF		ON ST	IIIIleu-	VLIIC		ONRO	= ST			JEFF	FRS	ON ST	-	
			om No					rom E					rom Sc					rom W			
Start Time	Left	Thru	Right		App. Total	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Left	Thru	Right		App. Total	Int. Total
06:00 AM	2	3	4	0	ярр. Total	2	74	2	2	80	0	7	4	1	12	1	25	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	1	28	129
06:15 AM	2	5	7	1	15	9	84	1	2	96	4	11	8	0	23	5	30	2	1	38	172
	4		2	0	14		_		4			10		0		5		1		48	
06:30 AM		8		-		6	102	3		115	0		6	-	16		37	-	5		193
06:45_AM_	3	8	3	0_	14	9	102	12	10	133	2	13	15	0_	30	9	65	6	2	82	259
Total	11	24	16	1	52	26	362	18	18	424	6	41	33	1	81	20	157	10	9	196	753
				_	1	٠		_	_					_		_		_	_		
07:00 AM	2	10	10	2	24	11	113	6	6	136	4	20	13	0	37	7	91	5	3	106	303
07:15 AM	3	17	13	2	35	22	161	7	13	203	4	21	12	2	39	13	137	9	5	164	441
07:30 AM	3	26	12	1	42	23	174	6	30	233	29	28	18	3	78	18	155	25	7	205	558
07:45 AM	4	15	13	2	34	24	171	18	9	222	30	42	13	4	89	22	136	17	19	194	539
Total	12	68	48	7	135	80	619	37	58	794	67	111	56	9	243	60	519	56	34	669	1841
08:00 AM	2	23	8	4	37	23	161	14	11	209	6	25	15	4	50	22	138	15	21	196	492
08:15 AM	6	14	8	1	29	26	168	18	9	221	5	40	25	5	75	7	139	7	19	172	497
08:30 AM	5	16	19	2	42	33	151	10	10	204	6	33	11	17	67	14	115	17	35	181	494
08:45 AM	8	12	15	5	40	30	158	13	12	213	9	29	24	7	69	16	146	12	26	200	522
Total	21	65	50	12	148	112	638	55	42	847	26	127	75	33	261	59	538	51	101	749	2005
					- '	•					_										
09:00 AM	5	17	12	0	34	33	138	16	1	188	12	35	18	28	93	23	142	19	24	208	523
09:15 AM	7	14	8	4	33	26	145	11	9	191	14	44	19	9	86	18	135	14	27	194	504
09:30 AM	4	16	10	2	32	13	146	13	4	176	5	19	23	7	54	14	115	11	11	151	413
09:45 AM	10	12	10	1	33	15	157	5	5	182	11	17	17	8	53	16	120	12	11	159	427
Total	26	59	40	7	132	87	586	45	19	737	42	115	77	52	286	71	512	56	73	712	1867
Total	20	33	40	'	102	07	300	70	13	131	72	110	,,	32	200	, , ,	312	50	75	112	1001
10:00 AM	4	9	14	5	32	12	107	13	9	141	4	18	23	9	54	9	87	15	8	119	346
10:15 AM	3	8	11	3	25	12	107	10	11	141	8	15	13	6	42	12	109	7	12	140	348
10:30 AM	6	11	18	0	35	5	99	9	6	119	5	21	7	7	40	8	109	2	9	128	322
	5			1			122	7	5	149	5	23		9	52	9	122	15		157	384
10:45 AM		6_	14		26	15							<u>15</u>						11		
Total	18	34	57	9	118	44	436	39	31	550	22	77	58	31	188	38	427	39	40	544	1400
44.00.414		•	40	•	00	1 4-	404		40	405	_	00	45		40		0.4	_	0	444	004
11:00 AM	4	6	13	3	26	15	104	4	12	135	7	20	15	4	46	8	94	6	6	114	321
11:15 AM	16	12	8	3	39	10	106	6	31	153	7	15	11	11	44	9	89	8	16	122	358
11:30 AM	9	17	14	2	42	8	108	10	53	179	6	18	15	21	60	13	103	11	15	142	423
11:45 AM	8	16	17_	9	50	12	121	7	46	186	6	21	17_	11_	55	10	102	9	11_	132	423
Total	37	51	52	17	157	45	439	27	142	653	26	74	58	47	205	40	388	34	48	510	1525
											ı										
12:00 PM	4	17	8	6	35	16	131	8	55	210	10	25	14	11	60	13	116	5	10	144	449
12:15 PM	10	10	23	11	54	15	115	7	27	164	8	24	19	10	61	13	125	6	21	165	444
12:30 PM	10	11	21	4	46	16	139	9	18	182	17	24	22	9	72	8	100	10	14	132	432
12:45 PM	1	13	12	5	31	15	137	12	22	186	12	17	17	15	61	14	111	7	25	157	435
Total	25	51	64	26	166	62	522	36	122	742	47	90	72	45	254	48	452	28	70	598	1760
01:00 PM	8	23	18	0	49	15	130	8	7	160	13	30	17	8	68	7	108	8	12	135	412
01:15 PM	5	15	19	3	42	21	116	5	5	147	7	19	19	12	57	9	122	6	9	146	392
01:30 PM	9	19	21	1	50	18	129	4	5	156	13	20	22	6	61	14	102	10	11	137	404
01:45 PM	6	12	19	6	43	10	122	10	13	155	14	18	29	6	67	10	100	7	11	128	393
Total	28	69	77	10	184	64	497	27	30	618	47	87	87	32	253	40	432	31	43	546	1601
. 5.31		-								5.5		٠.	٠.	-				٠.		٥.٠	
02:00 PM	7	10	13	4	34	9	126	7	8	150	5	14	16	7	42	5	115	13	12	145	371
02:15 PM	4	16	16	1	37	11	134	2	4	151	11	16	17	4	48	18	119	11	10	158	394
02:30 PM	4	15	16	7	42	12	144	7	73	236	36	22	13	43	114	11	170	14	17	212	604
02:45 PM	6	18	20	1	45	14	167	10	37	228	19	28	26	7	80	11	135	12	14	172	525
Total	21	59	65	13	158	46	571	26	122	765	71	80	72	61	284	45	539	50	53	687	1894
Total	21	39	00	13	100	40	5/ 1	20	122	700	/ /	οU	12	01	204	40	559	50	33	001	1094

Mead & Hunt

7055 Samuel Morse Drive Suite 100 Columbia, MD 21046 1 443 741 3500

File Name: MONROE ST AT JEFFERSON ST

Site Code : 00000000 Start Date : 10/26/2022

Page No : 2
Groups Printed- VEHS&PEDS


								Gro	oups P	rinted-	<u>VEHS</u>	&PEC	<u>s</u>								
		MC	NRO	E ST			JEFF	ERSO	ON ST			MC	NRO	E ST			JEFF	ERS	ON ST		
		Fi	rom No	orth			F	rom E	ast			Fr	om So	outh			Fi	rom W	/est		
Start Time	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Int. Total
03:00 PM	10	15	15	6	46	12	134	9	15	170	9	24	29	6	68	11	170	5	8	194	478
03:15 PM	8	12	10	1	31	11	149	11	17	188	10	20	27	3	60	7	178	9	13	207	486
03:30 PM	9	15	20	8	52	12	153	11	14	190	5	22	17	5	49	10	143	6	10	169	460
03:45 PM	6	14	29	10_	59	7	162	13	17	199	15	25	36	8	84	13	139	5	13_	170	512
Total	33	56	74	25	188	42	598	44	63	747	39	91	109	22	261	41	630	25	44	740	1936
											ı										
04:00 PM	13	25	13	4	55	14	154	6	10	184	15	25	32	7	79	13	143	12	12	180	498
04:15 PM	8	25	21	7	61	14	191	10	14	229	11	27	32	13	83	8	176	10	18	212	585
04:30 PM	24	26	27	4	81	10	173	6	10	199	14	38	40	9	101	12	209	10	26	257	638
04:45 PM	14	25	18	2	59	16	153	10_	13_	192	17	30	45_	5_	97	10	161	8_	7_	186	534
Total	59	101	79	17	256	54	671	32	47	804	57	120	149	34	360	43	689	40	63	835	2255
05 00 D14		-00	0.4	_	00	•	450			400	۱	4.0	40		0.5		400	40		000	
05:00 PM	11	22	31	2	66	9	152	8	11	180	19	19	46	1	85	11	186	12	30	239	570
05:15 PM	13	24	20	0	57	18	174	6	15	213	15	19	52	4	90	14	188	7	14	223	583
05:30 PM	14	21	20	5	60	14	190	14	12	230	13	30	42	2	87	8	197	7	10	222	599
05:45 PM	8	18	21	3_	50	12	156	10	16	194	14	32	39	4	89	11	155	8	11_	185	518
Total	46	85	92	10	233	53	672	38	54	817	61	100	179	11	351	44	726	34	65	869	2270
06:00 PM	6	28	14	4	52	11	141	10	10	172	13	17	27	4	61	9	157	4	9	179	464
06:15 PM	13	22	15	1	51	16	156	10	18	200	13	29	23	1	66	6	142	4	12	164	481
06:30 PM	6	17	17	4	44	9	145	15	16	185	10	17	15	1	43	12	140	10	7	169	441
06:45 PM	5	11	11	2	29	6	153	12	5	176	14	23	30	0	67	4	138	7	2	151	423
Total	30	78	57	11	176	42	595	47	49	733	50	86	95	<u>_</u> 6	237	31	577	25	30	663	1809
10141	1 00		O,				000	• • • • • • • • • • • • • • • • • • • •	.0	, 00	, 00	00	00	Ŭ	201	٠.	011		00	000	1000
Grand Total	367	800	771	165	2103	757	7206	471	797	9231	561	1199	1120	384	3264	580	6586	479	673	8318	22916
Apprch %	17.5	38	36.7	7.8		8.2	78.1	5.1	8.6		17.2	36.7	34.3	11.8		7	79.2	5.8	8.1		
Total %	1.6	3.5	3.4	0.7	9.2	3.3	31.4	2.1	3.5	40.3	2.4	5.2	4.9	1.7	14.2	2.5	28.7	2.1	2.9	36.3	

Mead & Hunt

7055 Samuel Morse Drive Suite 100 Columbia, MD 21046 1 443 741 3500

File Name: MONROE ST AT JEFFERSON ST

Site Code : 00000000 Start Date : 10/26/2022



Mead & Hunt

7055 Samuel Morse Drive Suite 100 Columbia, MD 21046 1 443 741 3500

File Name: MONROE ST AT JEFFERSON ST

Site Code : 00000000 Start Date : 10/26/2022

		MC	NRO	E ST			JEFF	ERSO	ON ST	-		MC	NRO	E ST			JEFF	ERSO	ON ST		
		Fr	om No	orth			F	rom E	ast			Fr	om So	outh			F	rom W	'est		
Start Time	Left Thru Right Peds App. 1					Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Int. Total

Mead & Hunt

7055 Samuel Morse Drive Suite 100 Columbia, MD 21046 1 443 741 3500

Weather: File Name: MONROE ST AT JEFFERSON ST

 Counted By:
 Site Code : 00000000

 Town:
 Start Date : 10/26/2022

Country Page No : 1

Groups Printed- U TURNS

		MC	NRO	E OT			ICCC		roups ON ST	Printed	- U II		NRO	ECT			ICC	EDC	ON ST		
			rom N				-	rom E				_	om Sc	_			-	rom W			
Start Time	Left				App. Total	Left	Thru			App. Total	Left	Thru	Right	Peds	App. Total	Left	Thru			App. Total	Int. Total
*** BREAK **		Tillu	rugiit	1 000	Арр. Тота	Loit	Tillu	rugiit	1 000	Арр. Тотаг	Lon	Tillu	rugiii	1 000	Арр. Тотаг	Loit	mu	rugiit	1 000	Арр. Тотаг	III. Total
09:15 AM *** BREAK **	1	0	0	0	1	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1
Total	1	0	0	0	1	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1
*** BREAK **																					
10:30 AM *** BREAK **	0	0	0	0	0	0	0	0	0	0	1	0	0	0	1	0	0	0	0	0	1
Total	0	0	0	0	0	0	0	0	0	0	1	0	0	0	1	0	0	0	0	0	1
*** BREAK ** 11:30 AM	0	0	0	0	0	1	0	0	0	1	0	0	0	0	0	0	0	0	0	0	1
*** BREAK ** Total	0	0	0	0	0	1	0	0	0	1	0	0	0	0	0	0	0	0	0	0	1
*** BREAK **	**																				
02:00 PM *** BREAK **	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1	0	0	0	1	1
02:45 PM	0	0	0	0	0	0	0	0	0	0	1	0	0	0	1	0	0	0	0	0	1
Total	0	0	0	0	0	0	0	0	0	0	1	0	0	0	1	1	0	0	0	1	2
03:00 PM	0	0	0	0	0	0	0	0	0	0	1	0	0	0	1	0	0	0	0	0	1
03:15 PM *** BREAK **	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1	0	0	0	1	1
Total	0	0	0	0	0	0	0	0	0	0	1	0	0	0	1	1	0	0	0	1	2
*** BREAK **	**																				
05:15 PM *** BREAK **	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1	0	0	0	1	1
Total	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1	0	0	0	1	1
*** BREAK ** 06:15 PM	**	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1	0	0	0	1	1
*** BREAK **	**																				
Total	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1	0	0	0	1	1
Grand Total	1	0	0	0	1	1	0	0	0	1	3	0	0	0	3	4	0	0	0	4	9
Apprch %	100	0	0	0	44.4	100	0	0	0	44.4	100	0	0	0	22.0	100	0	0	0	44.4	
Total %	11.1	0	0	0	11.1	11.1	0	0	0	11.1	33.3	0	0	0	33.3	44.4	0	0	0	44.4	

Mead & Hunt

7055 Samuel Morse Drive Suite 100 Columbia, MD 21046 1 443 741 3500

Weather: File Name: MONROE ST AT JEFFERSON ST

Counted By: Site Code : 00000000
Town: Start Date : 10/26/2022

Country Page No : 1

								Gr	oune	Printed-	BICVO	N ES									
			NROE om No					ERSO om Ea	N ST	i iiiieu-	DICTO	MO	NROE				JEFF	ERSO om We			
Start Time	Left	Thru		Peds	App. Total	Left			Peds	App. Total	Left -			Peds	App. Total	Left	Thru		Peds	App. Total	Int. Total
*** BREAK **	*						•				'		·	•			'				
06:45 AM	0	1_	0	0	1	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1_
Total	0	1	0	0	1	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1
*** BREAK **	*																				
07:15 AM	0	0	0	0	0	0	0	0	1	1	0	0	0	0	0	0	0	0	1	1	2
07:30 AM	0	1	0	0	1	0	0	0	1	1	0	0	0	0	0	0	0	0	0	0	2
07:45 AM	0	0	0	0	0	0	0	0	1_	1	0	1_	0	0	1	0	0	0	0	0	2
Total	0	1	0	0	1	0	0	0	3	3	0	1	0	0	1	0	0	0	1	1	6
*** BREAK **	*																				
09:15 AM *** BREAK **	* 0	0	0	0	0	0	0	0	0	0	0	2	0	0	2	0	0	0	0	0	2
Total	0	0	0	0	0	0	0	0	0	0	0	2	0	0	2	0	0	0	0	0	2
*** BREAK **	*																				
11:15 AM	0	0	0	0	0	0	1	0	0	1	0	0	0	0	0	0	0	0	0	0	1
11:30 AM	0	0	0	0	0	0	0	0	1	1	0	0	0	0	0	0	0	0	0	0	1
11:45 AM	0	0	0	0	0	0	0_	0	1_	1	0	0_	0	0	0	0	0_	0_	0	0	1
Total	0	0	0	0	0	0	1	0	2	3	0	0	0	0	0	0	0	0	0	0	3
*** BREAK ** 12:15 PM	* 0	0	1	0	1	0	0	0	0	0	0	0	0	0	0	0	0	0	1	1	2
*** BREAK **	-	U		U	'	U	U	U	U	0	U	U	U	U	0	U	U	U		• '	2
Total	0	0	1	0	1	0	0	0	0	0	0	0	0	0	0	0	0	0	1	1	2
01:00 PM *** BREAK **	. 0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1	0	0	1	1
01:30 PM	0	0	0	0	0	0	0	0	1	1	0	0	0	0	0	0	0	0	0	0	1
*** BREAK ** Total	0	0	0	0	0	0	0	0	1	1	0	0	0	0	0	0	1	0	0	1	2
*** BREAK **	*																				
02:30 PM	0	0	0	0	0	0	0	0	1	1	0	3	0	1	4	0	0	0	0	0	5
02:45 PM	0	0	0	0	0	0	0	0	0	0	0	1	0	0	1	0	0	0	0	0	1_
Total	0	0	0	0	0	0	0	0	1	1	0	4	0	1	5	0	0	0	0	0	6
03:00 PM	0	1	0	0	1	0	0	0	0	0	0	0	0	1	1	0	0	0	0	0	2
03:15 PM	0	0	0	0	0	0	0	0	0	0	0	1	0	0	1	0	0	0	0	0	1
03:30 PM 03:45 PM	0	0	0	0 0	0	0	0	0	1 0	1 0	0 0	0 1	0 0	0	0	0	0	0	0	0	1 1
Total	0	1	0	0	1	0	0	0	1	1	0	2	0	1	3	0	0	0	0	0	5
*** BREAK **	*																				
04:30 PM *** BREAK **		1	0	0	1	0	0	0	1	1	0	0	0	0	0	0	0	0	0	0	2
Total	0	1	0	0	1	0	0	0	1	1	0	0	0	0	0	0	0	0	0	0	2
05:00 PM *** BREAK **	0	0	0	0	0	0	0	0	0	0	0	0	0	1	1	0	0	0	0	0	1
Total	0	0	0	0	0	0	0	0	0	0	0	0	0	1	1	0	0	0	0	0	1

Page 74 of 210

Mead & Hunt

7055 Samuel Morse Drive Suite 100 Columbia, MD 21046 1 443 741 3500

File Name: MONROE ST AT JEFFERSON ST

Site Code : 00000000 Start Date : 10/26/2022

Page No : 2

Groups Printed- BICYCLES

								G	roups	Printed	<u>- BIC\</u>	CLES	3								
		MC	NRO	E ST			JEFF	ERS	ON ST			MC	NRO	E ST			JEFF	ERS	ON ST	•	
		Fı	rom N	orth			F	rom E	ast			Fr	om So	outh			Fr	om W	/est		
Start Time	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Int. Total
06:00 PM	0	2	0	0	2	0	0	0	1	1	0	0	0	0	0	0	0	0	0	0	3
06:15 PM	0	0	0	0	0	0	0	0	1	1	0	0	1	0	1	0	1	0	0	1	3
06:30 PM	0	1	0	0	1	0	0	0	0	0	0	1	0	0	1	0	0	0	0	0	2
06:45 PM	0	0	0	0	0	0	0	0	0	0	0	1	0	0	1	0	0	0	0	0	1_
Total	0	3	0	0	3	0	0	0	2	2	0	2	1	0	3	0	1	0	0	1	9
Grand Total	0	7	1	0	8	0	1	0	11	12	0	11	1	3	15	0	2	0	2	4	39
Apprch %	0	87.5	12.5	0		0	8.3	0	91.7		0	73.3	6.7	20		0	50	0	50		
Total %	0	17.9	2.6	0	20.5	0	2.6	0	28.2	30.8	0	28.2	2.6	7.7	38.5	0	5.1	0	5.1	10.3	

Mead & Hunt

7055 Samuel Morse Drive Suite 100 Columbia, MD 21046 1 443 741 3500

Weather: File Name: MONROE ST AT MIDDLE LN

 Counted By:
 Site Code : 00000000

 Town:
 Start Date : 10/26/2022

Country Page No : 1

Note						Groups F	Printed- V		EDS					
Start Time Left Thru Peds App. Total Left Right Peds App. Total Thru Right App. Total Th														
06:00 AM	O	1 6												= 1
06:15 AM														
06:30 AM													1	
06.45 AM				_										
Total 0 129													I	
07:00 AM														
07-15 AM 0 0 70 0 70 0 6 5 111 49 0 4 53 134 0730 AM 0 66 6 7 2 9 6 17 47 7 1 1 55 139 07-45 AM 0 105 0 105 1 133 5 19 65 3 2 70 194 Total 2 287 1 290 3 36 21 60 201 11 8 220 570 194 66 3 3 2 70 194 66 3 3 2 70 194 66 3 3 2 70 194 67 195 195 195 195 195 195 195 195 195 195	Total	U	129	U	129	3	17	17	31	122	1	4	127	293
07:15 AM	07:00 AM	2	45	1	48	0	8	5	13	40	1	1	42	103
07:30 AM	07:15 AM		70	0	70	0			11	49	0	4	53	134
Total 2	07:30 AM	0	67	0	67	2	9	6	17	47	7	1		139
08:00 AM	 07:45 AM	0	105	0	105				19	65		2	70	194
08:15 AM	Total	2	287	1	290	3	36	21	60	201	11	8	220	570
08:15 AM	08:00 AM	0	99	1	100	0	11	7	18	63	3	2	68	186
08:30 AM													1	
OB-45 AM							-				1		1	
Total											3			
09:15 AM						6								
09:15 AM	MA 00:00	0	100	0	100	2	12	0	24	60	2	5	76	200
09:30 AM 0 72 0 72 1 12 6 19 65 3 3 71 162 09:45 AM 0 57 0 57 2 8 8 18 57 2 0 59 134 Total 0 306 0 306 7 46 28 81 253 11 11 275 662 10:00 AM 0 62 0 62 3 14 5 22 49 1 1 51 135 10:15 AM 1 62 0 63 1 8 9 18 48 1 2 51 132 10:30 AM 1 54 0 55 0 14 8 22 56 3 7 66 143 10:45 AM 1 72 1 7 50 24 81 215 8 12 <													1	
O9:45 AM													1	
Total 0 306 0 306 7 46 28 81 253 11 11 275 662														
10:15 AM														
10:15 AM	10:00 AM	0	62	0	62	2	1.1	5	22	40	1	1	51	135
10:30 AM													ı	
10:45 AM													I	
Total 3 250 1 254 7 50 24 81 215 8 12 235 570 11:00 AM 0 72 0 72 1 16 3 20 43 2 0 45 137 11:15 AM 0 65 0 65 2 11 6 19 48 0 7 55 139 11:30 AM 1 68 0 69 2 19 2 23 58 3 3 64 156 11:45 AM 0 64 0 64 2 14 8 24 61 2 7 70 158 Total 1 269 0 270 7 10 5 22 68 2 10 80 181 12:00 PM 0 79 0 79 7 10 5 22 68 2 <td< td=""><td>i</td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td>1</td><td></td></td<>	i												1	
11:15 AM														
11:15 AM	44.00 414	0	70	0	70	4	40	•	00	40	0	0	45	407
11:30 AM													1	
11:45 AM		_									-		i	
Total 1 269 0 270 7 60 19 86 210 7 17 234 590 12:00 PM 0 79 0 79 7 10 5 22 68 2 10 80 181 12:15 PM 0 84 2 86 2 24 5 31 69 2 10 81 198 12:30 PM 2 78 0 80 2 22 10 34 72 1 6 79 193 12:45 PM 1 78 0 79 5 10 4 19 64 1 4 69 167 Total 3 319 2 324 16 66 24 106 273 6 30 309 739 01:00 PM 0 74 0 74 3 16 8 27 62 3														
12:15 PM 0 84 2 86 2 24 5 31 69 2 10 81 198 12:30 PM 2 78 0 80 2 22 10 34 72 1 6 79 193 12:45 PM 1 78 0 79 5 10 4 19 64 1 4 69 167 Total 3 319 2 324 16 66 24 106 273 6 30 309 739 01:00 PM 0 74 0 74 3 16 8 27 62 3 4 69 170 01:15 PM 0 76 0 76 4 10 5 19 61 4 1 66 161 01:30 PM 0 66 2 68 3 16 11 30 61 3														
12:15 PM 0 84 2 86 2 24 5 31 69 2 10 81 198 12:30 PM 2 78 0 80 2 22 10 34 72 1 6 79 193 12:45 PM 1 78 0 79 5 10 4 19 64 1 4 69 167 Total 3 319 2 324 16 66 24 106 273 6 30 309 739 01:00 PM 0 74 0 74 3 16 8 27 62 3 4 69 170 01:15 PM 0 76 0 76 4 10 5 19 61 4 1 66 161 01:30 PM 0 66 2 68 3 16 11 30 61 3	40.00 514	•			70 l	_	4.0	_	00			4.0	00	404
12:30 PM					i								i	
12:45 PM													i	
Total 3 319 2 324 16 66 24 106 273 6 30 309 739 01:00 PM 0 74 0 74 3 16 8 27 62 3 4 69 170 01:15 PM 0 76 0 76 4 10 5 19 61 4 1 66 161 01:30 PM 0 66 2 68 3 16 11 30 61 3 5 69 167 01:45 PM 0 58 0 58 1 14 4 19 58 0 1 59 136 Total 0 274 2 276 11 56 28 95 242 10 11 263 634 02:00 PM 0 74 0 74 3 17 12 32 45 2														
01:00 PM 0 74 0 74 3 16 8 27 62 3 4 69 170 01:15 PM 0 76 0 76 4 10 5 19 61 4 1 66 161 01:30 PM 0 66 2 68 3 16 11 30 61 3 5 69 167 01:45 PM 0 58 0 58 1 14 4 19 58 0 1 59 136 Total 0 274 2 276 11 56 28 95 242 10 11 263 634 02:00 PM 0 74 0 74 3 17 12 32 45 2 6 53 159 02:15 PM 0 72 0 72 4 15 7 26 66 2											-			
01:15 PM 0 76 0 76 4 10 5 19 61 4 1 66 161 01:30 PM 0 66 2 68 3 16 11 30 61 3 5 69 167 01:45 PM 0 58 0 58 1 14 4 19 58 0 1 59 136 Total 0 274 2 276 11 56 28 95 242 10 11 263 634 02:00 PM 0 74 0 74 3 17 12 32 45 2 6 53 159 02:15 PM 0 72 0 72 4 15 7 26 66 2 3 71 169 02:30 PM 1 71 0 72 1 15 4 20 64 1	Total	3	313		324	10	00	24	100	213	Ü	30	303	755
01:30 PM 0 66 2 68 3 16 11 30 61 3 5 69 167 01:45 PM 0 58 0 58 1 14 4 19 58 0 1 59 136 Total 0 274 2 276 11 56 28 95 242 10 11 263 634 02:00 PM 0 74 0 74 3 17 12 32 45 2 6 53 159 02:15 PM 0 72 0 72 4 15 7 26 66 2 3 71 169 02:30 PM 1 71 0 72 1 15 4 20 64 1 3 68 160 02:45 PM 1 68 0 69 1 16 11 28 63 2	01:00 PM	0	74	0	74	3	16	8	27	62	3	4	69	170
01:45 PM 0 58 0 58 1 14 4 19 58 0 1 59 136 Total 0 274 2 276 11 56 28 95 242 10 11 263 634 02:00 PM 0 74 0 74 3 17 12 32 45 2 6 53 159 02:15 PM 0 72 0 72 4 15 7 26 66 2 3 71 169 02:30 PM 1 71 0 72 1 15 4 20 64 1 3 68 160 02:45 PM 1 68 0 69 1 16 11 28 63 2 10 75 172	01:15 PM	0	76	0	76	4	10	5	19	61	4	1	66	161
Total 0 274 2 276 11 56 28 95 242 10 11 263 634 02:00 PM 0 74 0 74 3 17 12 32 45 2 6 53 159 02:15 PM 0 72 0 72 4 15 7 26 66 2 3 71 169 02:30 PM 1 71 0 72 1 15 4 20 64 1 3 68 160 02:45 PM 1 68 0 69 1 16 11 28 63 2 10 75 172		-				3	_			-	-	_		
02:00 PM 0 74 0 74 3 17 12 32 45 2 6 53 159 02:15 PM 0 72 0 72 4 15 7 26 66 2 3 71 169 02:30 PM 1 71 0 72 1 15 4 20 64 1 3 68 160 02:45 PM 1 68 0 69 1 16 11 28 63 2 10 75 172														
02:15 PM 0 72 0 72 4 15 7 26 66 2 3 71 169 02:30 PM 1 71 0 72 1 15 4 20 64 1 3 68 160 02:45 PM 1 68 0 69 1 16 11 28 63 2 10 75 172	Total	0	274	2	276	11	56	28	95	242	10	11	263	634
02:15 PM 0 72 0 72 4 15 7 26 66 2 3 71 169 02:30 PM 1 71 0 72 1 15 4 20 64 1 3 68 160 02:45 PM 1 68 0 69 1 16 11 28 63 2 10 75 172	02:00 PM	0	74	0	74	3	17	12	32	45	2	6	53	159
02:30 PM 1 71 0 72 1 15 4 20 64 1 3 68 160 02:45 PM 1 68 0 69 1 16 11 28 63 2 10 75 172		0	72		72		15			66				169
	02:30 PM	1		0	72	1	15	4	20	64	1	3	68	160
Total 2 285 0 287 9 63 34 106 238 7 22 267 660														
	Total	2	285	0	287	9	63	34	106	238	7	22	267	660

Mead & Hunt

7055 Samuel Morse Drive Suite 100 Columbia, MD 21046 1 443 741 3500

File Name: MONROE ST AT MIDDLE LN

Site Code : 00000000 Start Date : 10/26/2022

Page No : 2
Groups Printed- VEHS&PEDS

					Groups F	Printed- V	EHS&PI	EDS					
		MIDD	LE LN		-	MONR	OE ST			MIDD	LE LN		
		From	n East			From	South			From	West		
Start Time	Left	Thru	Peds	App. Total	Left	Right	Peds	App. Total	Thru	Right	Peds	App. Total	Int. Total
03:00 PM	2	73	1	76	0	16	5	21	74	1	6	81	178
03:15 PM	0	71	1	72	1	5	11	17	86	1	4	91	180
03:30 PM	0	68	0	68	4	12	7	23	81	3	8	92	183
03:45 PM	0	68	0	68	2	11	5	18	83	2	4	89	175
Total	2	280	2	284	7	44	28	79	324	7	22	353	716
04:00 PM	0	83	0	83	3	20	11	34	78	2	2	82	199
04:15 PM	0	79	0	79	4	19	11	34	111	1	6	118	231
04:30 PM	0	68	0	68	3	19	7	29	119	1	2	122	219
04:45 PM	0	70	2	72	2	8	14	24	94	0	2	96	192
Total	0	300	2	302	12	66	43	121	402	4	12	418	841
	ı												
05:00 PM	0	88	0	88	2	16	8	26	108	2	5	115	229
05:15 PM	0	96	0	96	2	8	9	19	114	1	3	118	233
05:30 PM	0	89	0	89	3	18	6	27	124	3	2	129	245
05:45 PM	0	81	0	81	0	14	10	24	114	5	9	128	233
Total	0	354	0	354	7	56	33	96	460	11	19	490	940
	i												
06:00 PM	0	101	0	101	1	16	9	26	89	4	4	97	224
06:15 PM	1	98	0	99	1	8	3	12	73	1	11	85	196
06:30 PM	0	96	0	96	2	16	5	23	73	2	2	77	196
06:45 PM	0	83	0	83	2	12	7_	21	84	3	1_	88	192
Total	1	378	0	379	6	52	24	82	319	10	18	347	808
				1				1				1	
Grand Total	15	3805	11	3831	101	649	362	1112	3491	101	207	3799	8742
Apprch %	0.4	99.3	0.3		9.1	58.4	32.6		91.9	2.7	5.4		
Total %	0.2	43.5	0.1	43.8	1.2	7.4	4.1	12.7	39.9	1.2	2.4	43.5	


Mead & Hunt

7055 Samuel Morse Drive Suite 100 Columbia, MD 21046 1 443 741 3500

File Name: MONROE ST AT MIDDLE LN

Site Code : 00000000 Start Date : 10/26/2022

Page No : 3



Mead & Hunt

7055 Samuel Morse Drive Suite 100 Columbia, MD 21046 1 443 741 3500

File Name: MONROE ST AT MIDDLE LN

Site Code : 00000000 Start Date : 10/26/2022

Page No : 4

		MID	DLE LN			MON	ROE ST			MIDE	DLE LN		
		Fro	m East			From	South			From	n West		
Start Ti	ne Le	ft Thru	Peds	App. Total	Left	Right	Peds	App. Total	Thru	Right	Peds	App. Total	Int. Total

Peak Hour Analysis From 06:00 AM to 06:00 AM - Peak 1 of 1

Mead & Hunt

7055 Samuel Morse Drive Suite 100 Columbia, MD 21046 1 443 741 3500

Weather: File Name: MONROE ST AT MIDDLE LN

Counted By: Site Code : 00000000
Town: Start Date : 10/26/2022

Country Page No : 1

Groups Printed- U TURNS MIDDLE LN MONROE ST MIDDLE LN From East From South From West Start Time Left Peds App. Total Int. Total Peds App. Total Left Peds App. Total Thru Right Thru Right *** BREAK *** 07:15 AM *** BREAK *** Total *** BREAK *** 01:00 PM 01:15 PM *** BREAK *** 01:45 PM Total *** BREAK *** 02:30 PM 1 | *** BREAK *** Total 1 | 03:00 PM *** BREAK *** 03:30 PM 03:45 PM Total *** BREAK *** 04:30 PM *** BREAK *** Total *** BREAK *** 05:15 PM 05:30 PM 05:45 PM Total *** BREAK *** **Grand Total** Apprch % Total % 23.5 11.8 23.5 11.8 64.7 64.7

Mead & Hunt

7055 Samuel Morse Drive Suite 100 Columbia, MD 21046 1 443 741 3500

Weather: File Name: MONROE ST AT MIDDLE LN

 Counted By:
 Site Code : 00000000

 Town:
 Start Date : 10/26/2022

Country Page No : 1

					Groups		BICYCLE	S					
		MIDDI					OE ST			MIDDI			
Start Time	Left	From Thru		App. Total	Left	From Right		App. Total	Thru	From Right		pp. Total	Int. Total
*** BREAK ***	Len	IIIIu	i eus	App. Total	Len	Right	i eus i	App. Total	IIIIu	Right	i eus A	pp. rotar [IIII. TOtal
06:15 AM	0	0	0	0	0	0	0	0	2	0	1	3	3
06:30 AM	0	0	0	0	0	0	0	0	1	0	0	1	1
06:45 AM	2	0	0	2	0	0	0	0	0	0	0	0	2
Total	2	0	0	2	0	0	0	0	3	0	1	4	6
*** BREAK ***													
07:15 AM	0	0	0	0	0	0	0	0	0	0	1	1	1
07:30 AM	0	0	0	0	0	0	0	0	1	1	0	2	2
07:45 AM	0	0	0	0	0	1	0	1	0	0	0	0	1_
Total	0	0	0	0	0	1	0	1	1	1	1	3	4
*** BREAK ***													
08:30 AM	0	0	0	0	0	0	0	0	1	0	0	1	1
08:45 AM	0	2	0	2	0	0	0	0	0	0	0	0	2
Total	0	2	0	2	0	0	0	0	1	0	0	1	3
09:00 AM	0	0	0	0	0	0	1	1	1	0	0	1	2
09:15 AM	0	0	0	0	0	1	0	1	0	0	0	0	1
09:30 AM	0	0	0	0	0	0	0	0	1	0	0	1	1
*** BREAK ***		0		0	0	1	1	2	2	0	0	2	4
Total	0	U	0	U	U	ı	ı	2	2	U	U	۷	4
*** BREAK ***													
10:30 AM	0	0	0	0	0	0	0	0	1	0	0	1	1
*** BREAK ***													
Total	0	0	0	0	0	0	0	0	1	0	0	1	1
11:00 AM	0	0	0	0	0	0	1	1	0	0	0	0	1
11:15 AM	0	0	0	0	0	0	1	1	1	0	0	1	2
*** BREAK ***													
Total	0	0	0	0	0	0	2	2	1	0	0	1	3
*** BREAK ***													
12:15 PM	0	1	0	1	0	0	0	0	0	0	0	0	1
12:30 PM	0	0	0	0	0	0	1	1	0	0	0	0	1
*** BREAK ***				4		0	4	4		0		0	2
Total	0	1	0	1	0	0	1	1	0	0	0	0	2
*** BREAK ***													
00:20 DM	0	0	0	0	0	0	0	0	0	0	2	3	2
02:30 PM *** BREAK ***	0	0	0	U	U	0	0	0	0	U	3	3	3
Total	0	0	0	0	0	0	0	0	0	0	3	3	3
*** BREAK ***													
03:15 PM	0	1	0	1	0	1	0	1	0	0	0	0	2
03:30 PM	0	0	0	0	0	0	1	1	1	0	1	2	3
03:45 PM	0	1	0	1	0	1	Ö	1	0	0	3	3	5
Total	0	2	0	2	0	2	1	3	1	0	4	5	10
04:00 PM	0	2	0	2	0	0	0	0	0	0	0	0	2
04:00 PM 04:15 PM	0 0	0	0	2 0	0 0	0 1	1	2	0	0 0	0	0	2 2

Page 81 of 210

Mead & Hunt

7055 Samuel Morse Drive Suite 100 Columbia, MD 21046 1 443 741 3500

File Name: MONROE ST AT MIDDLE LN

Site Code : 00000000 Start Date : 10/26/2022

Page No : 2

					Groups	Printed-	BICYCL	ES					
		MIDD	LE LN			MONF	OE ST			MIDD	LE LN		
		From	East			From	South			From	West		
Start Time	Left	Thru	Peds	App. Total	Left	Right	Peds	App. Total	Thru	Right	Peds	App. Total	Int. Total
04:30 PM	0	1	0	1	0	0	0	0	1	0	0	1	2
04:45 PM	0	2	0	2	0	0	1	1	1	0	0	1	4_
Total	0	5	0	5	0	1	2	3	2	0	0	2	10
05:00 PM *** BREAK ***	0	0	0	0	0	0	1	1	0	0	1	1	2
05:30 PM *** BREAK ***	0	0	0	0	0	0	0	0	1	0	0	1	1
Total	0	0	0	0	0	0	1	1	1	0	1	2	3
06:00 PM *** BREAK ***	0	0	0	0	0	0	2	2	0	0	0	0	2
06:30 PM	0	1	0	1	0	0	0	0	0	0	0	0	1
06:45 PM	1	0	0	1	0	0	0	0	0	0	0	0	1
Total	1	1	0	2	0	0	2	2	0	0	0	0	4
Grand Total Apprch % Total %	3 21.4 5.7	11 78.6 20.8	0 0 0	14 26.4	0 0 0	5 33.3 9.4	10 66.7 18.9	15 28.3	13 54.2 24.5	1 4.2 1.9	10 41.7 18.9	24 45.3	53

Fleet and Monroe Streets, Complete Streets Study APPENDICES



Appendix B: HCM Reports

Existing Conditions, Bike Path, Cycletrack Opt 1, Cycletrack Opt 2

HCM Unsignalized Intersection Capacity Analysis 1: Monroe St & E Middle Ln

	→	\rightarrow	•	←	•	~
Movement	EBT	EBR	WBL	WBT	NBL	NBR
Lane Configurations	∱ Ъ			^		7
Traffic Volume (veh/h)	229	14	0	350	0	42
Future Volume (Veh/h)	229	14	0	350	0	42
Sign Control	Free			Free	Stop	
Grade	0%			0%	0%	
Peak Hour Factor	0.86	0.86	0.86	0.86	0.86	0.86
Hourly flow rate (vph)	266	16	0	407	0	49
Pedestrians	11			1	29	
Lane Width (ft)	12.0			12.0	12.0	
Walking Speed (ft/s)	3.5			3.5	3.5	
Percent Blockage	1			0	3	
Right turn flare (veh)						
Median type	None			None		
Median storage veh)						
Upstream signal (ft)						
pX, platoon unblocked						
vC, conflicting volume			311		518	171
vC1, stage 1 conf vol						
vC2, stage 2 conf vol						
vCu, unblocked vol			311		518	171
tC, single (s)			4.1		6.8	6.9
tC, 2 stage (s)						
tF (s)			2.2		3.5	3.3
p0 queue free %			100		100	94
cM capacity (veh/h)			1212		469	819
Direction, Lane #	EB 1	EB 2	WB 1	WB 2	NB 1	
Volume Total	177	105	204	204	49	
Volume Left	0	0	0	0	0	
Volume Right	0	16	0	0	49	
cSH	1700	1700	1700	1700	819	
Volume to Capacity	0.10	0.06	0.12	0.12	0.06	
Queue Length 95th (ft)	0	0	0	0	5	
Control Delay (s)	0.0	0.0	0.0	0.0	9.7	
Lane LOS		7.2		,,,	A	
Approach Delay (s)	0.0		0.0		9.7	
Approach LOS					Α	
Intersection Summary						
Average Delay			0.6			
Intersection Capacity Utilizat	tion		21.5%	IC	U Level o	f Service
Analysis Period (min)			15			

HCM Unsignalized Intersection Capacity Analysis

2: Monroe St & E Montgomery Ave

	•	•	•	†	Ţ	4
Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations	W			+	*	
Sign Control	Stop			Stop	Stop	
Traffic Volume (vph)	0	0	0	0	0	0
Future Volume (vph)	0	0	0	0	0	0
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Hourly flow rate (vph)	0	0	0	0	0	0
Direction, Lane #	EB 1	NB 1	SB 1			
Volume Total (vph)	0	0	0			
Volume Left (vph)	0	0	0			
Volume Right (vph)	0	0	0			
Hadj (s)	0.00	0.00	0.00			
Departure Headway (s)	3.9	3.9	3.9			
Degree Utilization, x	0.00	0.00	0.00			
Capacity (veh/h)	917	917	917			
Control Delay (s)	6.9	6.9	6.9			
Approach Delay (s)	0.0	0.0	0.0			
Approach LOS	Α	Α	Α			
Intersection Summary						
Delay			0.0			
Level of Service			Α			
Intersection Capacity Utiliz	zation		0.0%	IC	U Level o	of Service
Analysis Period (min)			15			

HCM Unsignalized Intersection Capacity Analysis 3: Monroe St & Monroe PI

	۶	→	•	√	←	4	4	†	<i>></i>	/	+	✓
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		4			4			ર્ન	7		4	
Sign Control		Stop			Stop			Stop			Stop	
Traffic Volume (vph)	0	0	0	0	0	0	0	0	0	0	0	0
Future Volume (vph)	0	0	0	0	0	0	0	0	0	0	0	0
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Hourly flow rate (vph)	0	0	0	0	0	0	0	0	0	0	0	0
Direction, Lane #	EB 1	WB 1	NB 1	NB 2	SB 1							
Volume Total (vph)	0	0	0	0	0							
Volume Left (vph)	0	0	0	0	0							
Volume Right (vph)	0	0	0	0	0							
Hadj (s)	0.00	0.00	0.00	0.00	0.00							
Departure Headway (s)	3.9	3.9	4.5	4.5	4.0							
Degree Utilization, x	0.00	0.00	0.00	0.00	0.00							
Capacity (veh/h)	917	917	806	806	900							
Control Delay (s)	6.9	6.9	6.3	6.3	7.0							
Approach Delay (s)	0.0	0.0	0.0		0.0							
Approach LOS	Α	Α	Α		Α							
Intersection Summary												
Delay			0.0									
Level of Service			Α									
Intersection Capacity Utiliza	ition		0.0%	IC	U Level	of Service			Α			
Analysis Period (min)			15									

HCM Signalized Intersection Capacity Analysis

4: Monroe St & E Jefferson St

	۶	→	*	•	+	4	1	<u>†</u>	/	\	+	4
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	, N	↑ ↑		ň	∱ }			€ 1₽			सींक	
Traffic Volume (vph)	69	568	64	96	674	56	70	135	71	15	78	41
Future Volume (vph)	69	568	64	96	674	56	70	135	71	15	78	41
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	5.5	5.5		5.5	5.5			6.0			6.0	
Lane Util. Factor	1.00	0.95		1.00	0.95			0.95			0.95	
Frpb, ped/bikes	1.00	1.00		1.00	1.00			0.98			0.97	
Flpb, ped/bikes	1.00	1.00		1.00	1.00			0.98			0.99	
Frt	1.00	0.98		1.00	0.99			0.96			0.95	
Flt Protected	0.95	1.00		0.95	1.00			0.99			0.99	
Satd. Flow (prot)	1592	3129		1590	3144			2909			2918	
Flt Permitted	0.30	1.00		0.34	1.00			0.83			0.90	
Satd. Flow (perm)	497	3129		563	3144			2435			2640	
Peak-hour factor, PHF	0.94	0.94	0.94	0.94	0.94	0.94	0.94	0.94	0.94	0.94	0.94	0.94
Adj. Flow (vph)	73	604	68	102	717	60	74	144	76	16	83	44
RTOR Reduction (vph)	0	0	0	0	0	0	0	0	0	0	0	0
Lane Group Flow (vph)	73	672	0	102	777	0	0	294	0	0	143	0
Confl. Peds. (#/hr)	8		16	16		8	66		59	59		66
Turn Type	pm+pt	NA		pm+pt	NA		Perm	NA		Perm	NA	
Protected Phases	1	6		5	2			8			4	
Permitted Phases	6			2			8			4		
Actuated Green, G (s)	49.3	43.3		50.7	44.0			23.0			23.0	
Effective Green, g (s)	49.3	43.3		50.7	44.0			23.0			23.0	
Actuated g/C Ratio	0.55	0.48		0.56	0.49			0.26			0.26	
Clearance Time (s)	5.5	5.5		5.5	5.5			6.0			6.0	
Vehicle Extension (s)	3.0	3.0		3.0	3.0			3.0			3.0	
Lane Grp Cap (vph)	345	1505		393	1537			622			674	
v/s Ratio Prot	0.01	0.21		c0.02	c0.25							
v/s Ratio Perm	0.10			0.13				c0.12			0.05	
v/c Ratio	0.21	0.45		0.26	0.51			0.47			0.21	
Uniform Delay, d1	10.0	15.4		9.5	15.6			28.4			26.4	
Progression Factor	1.00	1.00		1.00	1.00			0.85			1.00	
Incremental Delay, d2	0.3	1.0		0.4	1.2			0.5			0.2	
Delay (s)	10.3	16.4		9.8	16.8			24.7			26.5	
Level of Service	В	В		Α	В			С			С	
Approach Delay (s)		15.8			16.0			24.7			26.5	
Approach LOS		В			В			С			С	
Intersection Summary												
HCM 2000 Control Delay			17.9	Н	CM 2000	Level of S	Service		В			
HCM 2000 Volume to Capa	city ratio		0.48									
Actuated Cycle Length (s)			90.0		um of lost				17.0			
Intersection Capacity Utiliza	ation		64.2%	IC	CU Level o	of Service			С			
Analysis Period (min)			15									
c Critical Lane Group												

HCM Signalized Intersection Capacity Analysis 5: Monroe St & Fleet St

3. Monioe St & Fleet	Οl										0-1/	14/2020
	ၨ	→	•	•	+	•	4	†	/	\	ļ	1
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		414			सीक			4			र्स	7
Traffic Volume (vph)	148	314	62	10	275	81	43	69	21	43	43	83
Future Volume (vph)	148	314	62	10	275	81	43	69	21	43	43	83
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)		5.0			5.0			5.0			5.0	5.0
Lane Util. Factor		0.95			0.95			1.00			1.00	1.00
Frpb, ped/bikes		0.99			0.99			1.00			1.00	0.93
Flpb, ped/bikes		1.00			1.00			0.99			1.00	1.00
Frt		0.98			0.97			0.98			1.00	0.85
Flt Protected		0.99			1.00			0.98			0.98	1.00
Satd. Flow (prot)		3052			3050			1588			1632	1329
Flt Permitted		0.67			0.93			0.84			0.68	1.00
Satd. Flow (perm)		2069			2837			1358			1131	1329
Peak-hour factor, PHF	0.66	0.66	0.66	0.66	0.66	0.66	0.66	0.66	0.66	0.66	0.66	0.66
Adj. Flow (vph)	224	476	94	15	417	123	65	105	32	65	65	126
RTOR Reduction (vph)	0	8	0	0	21	0	0	9	0	0	0	39
Lane Group Flow (vph)	0	786	0	0	534	0	0	193	0	0	130	87
Confl. Peds. (#/hr)	20		19	19		20	40		5	5		40
Turn Type	Perm	NA		Perm	NA		Perm	NA		Perm	NA	custom
Protected Phases	T CITI	6		1 01111	2		1 Cilli	8		1 01111	4	odotom
Permitted Phases	6	•		2	_		8	•		4	•	6
Actuated Green, G (s)		62.3			62.3			17.7		'	17.7	62.3
Effective Green, g (s)		62.3			62.3			17.7			17.7	62.3
Actuated g/C Ratio		0.69			0.69			0.20			0.20	0.69
Clearance Time (s)		5.0			5.0			5.0			5.0	5.0
Vehicle Extension (s)		3.0			3.0			3.0			3.0	3.0
Lane Grp Cap (vph)		1432			1963			267			222	919
v/s Ratio Prot		1432			1303			201			222	313
v/s Ratio Perm		c0.38			0.19			c0.14			0.11	0.07
v/c Ratio		0.55			0.19			0.72			0.11	0.07
Uniform Delay, d1		6.9			5.3			33.9			32.8	4.6
Progression Factor		0.85			1.00			1.00			0.98	2.62
Incremental Delay, d2		1.3			0.3			9.3			3.8	0.2
		7.2			5.6			43.2			35.9	12.2
Delay (s) Level of Service		7.2 A			3.0 A			43.2 D			33.9 D	12.2 B
Approach Delay (s)		7.2			5.6			43.2			24.2	Б
Approach LOS		7.2 A			3.0 A			43.2 D			24.2 C	
Intersection Summary												
HCM 2000 Control Delay			13.1	H	CM 2000	Level of	Service		В			
HCM 2000 Volume to Capacity	ratio		0.59	1.		. ,, ,,						
Actuated Cycle Length (s)			90.0	Sı	um of lost	t time (s)			10.0			
Intersection Capacity Utilization)		69.4%			of Service			С			
Analysis Period (min)			15									
c Critical Lane Group												

HCM Signalized Intersection Capacity Analysis 6: Maryland Ave & Fleet St

o. Mai yianu Ave & i											•	
	•	-	•	•	←	•	1	†	~	-	ţ	4
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		4		ሻ		7			7	ሻ	•	
Traffic Volume (vph)	2	1	1	315	0	101	0	276	451	87	245	0
Future Volume (vph)	2	1	1	315	0	101	0	276	451	87	245	0
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)		4.5		4.5		4.5		4.5	4.5	4.5	4.5	
Lane Util. Factor		1.00		1.00		1.00		1.00	1.00	1.00	1.00	
Frpb, ped/bikes		0.98		1.00		0.97		1.00	0.98	1.00	1.00	
Flpb, ped/bikes		1.00		1.00		1.00		1.00	1.00	1.00	1.00	
Frt		0.97		1.00		0.85		1.00	0.85	1.00	1.00	
Flt Protected		0.97		0.95		1.00		1.00	1.00	0.95	1.00	
Satd. Flow (prot)		1545		1593		1384		1676	1403	1593	1676	
Flt Permitted		0.97		0.95		1.00		1.00	1.00	0.27	1.00	
Satd. Flow (perm)		1545		1593		1384		1676	1403	456	1676	
Peak-hour factor, PHF	0.79	0.79	0.79	0.79	0.79	0.79	0.79	0.79	0.79	0.79	0.79	0.79
Adj. Flow (vph)	3	1	1	399	0	128	0	349	571	110	310	0
RTOR Reduction (vph)	0	1	0	0	0	88	0	0	407	0	0	0
Lane Group Flow (vph)	0	4	0	399	0	40	0	349	164	110	310	0
Confl. Peds. (#/hr)	3		3	3		3	7		2	2		7
Turn Type	Split	NA		Prot		Perm		NA	Perm	pm+pt	NA	
Protected Phases	3	3		4				2		1	6	
Permitted Phases						4			2	6		
Actuated Green, G (s)		1.3		28.0		28.0		25.9	25.9	47.2	47.2	
Effective Green, g (s)		1.3		28.0		28.0		25.9	25.9	47.2	47.2	
Actuated g/C Ratio		0.01		0.31		0.31		0.29	0.29	0.52	0.52	
Clearance Time (s)		4.5		4.5		4.5		4.5	4.5	4.5	4.5	
Vehicle Extension (s)		4.0		2.0		2.0		5.0	5.0	3.0	5.0	
Lane Grp Cap (vph)		22		495		430		482	403	451	878	
v/s Ratio Prot		c0.00		c0.25				c0.21		0.05	c0.18	
v/s Ratio Perm		00.00		00.20		0.03			0.12	0.08	00.10	
v/c Ratio		0.18		0.81		0.09		0.72	0.41	0.24	0.35	
Uniform Delay, d1		43.8		28.5		22.0		28.8	25.9	12.4	12.5	
Progression Factor		1.00		1.01		1.45		1.00	1.00	1.00	1.00	
Incremental Delay, d2		5.4		8.6		0.0		9.1	3.0	1.3	1.1	
Delay (s)		49.2		37.4		32.0		38.0	28.9	13.7	13.6	
Level of Service		D		D		С		D	С	В	В	
Approach Delay (s)		49.2			36.1			32.3			13.6	
Approach LOS		D			D			С			В	
Intersection Summary												
HCM 2000 Control Delay			29.3	H	CM 2000	Level of	Service		С			
HCM 2000 Volume to Capaci	ty ratio		0.67									
Actuated Cycle Length (s)			90.0	Sı	um of lost	time (s)			18.0			
Intersection Capacity Utilization	on		58.4%			of Service			В			
Analysis Period (min)			15									
c Critical Lane Group												

HCM Signalized Intersection Capacity Analysis 7: MD 355 & E Jefferson St

	۶	→	\rightarrow	•	←	•	4	†	/	\	ļ	1
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		∱ î≽			^	7	14.54	ተተተ		44	↑ ↑	
Traffic Volume (vph)	0	307	305	0	683	387	170	525	0	325	1208	49
Future Volume (vph)	0	307	305	0	683	387	170	525	0	325	1208	49
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)		9.0			9.0	9.0	8.0	8.0		9.0	9.0	
Lane Util. Factor		0.95			0.95	1.00	0.97	0.91		0.97	0.91	
Frpb, ped/bikes		1.00			1.00	1.00	1.00	1.00		1.00	1.00	
Flpb, ped/bikes		1.00			1.00	1.00	1.00	1.00		1.00	1.00	
Frt		0.93			1.00	0.85	1.00	1.00		1.00	0.99	
Flt Protected		1.00			1.00	1.00	0.95	1.00		0.95	1.00	
Satd. Flow (prot)		2947			3185	1425	3090	4577		3090	4544	
Flt Permitted		1.00			1.00	1.00	0.95	1.00		0.95	1.00	
Satd. Flow (perm)		2947			3185	1425	3090	4577		3090	4544	
Peak-hour factor, PHF	0.98	0.98	0.98	0.98	0.98	0.98	0.98	0.98	0.98	0.98	0.98	0.98
Adj. Flow (vph)	0	313	311	0	697	395	173	536	0	332	1233	50
RTOR Reduction (vph)	0	120	0	0	0	284	0	0	0	0	3	0
Lane Group Flow (vph)	0	504	0	0	697	111	173	536	0	332	1280	0
Confl. Peds. (#/hr)												10
Turn Type		NA			NA	Perm	Prot	NA		Prot	NA	
Protected Phases		4			8		1	5		6	2	
Permitted Phases						8						
Actuated Green, G (s)		38.0			38.0	38.0	13.0	45.0		41.0	73.0	
Effective Green, g (s)		38.0			38.0	38.0	13.0	45.0		41.0	73.0	
Actuated g/C Ratio		0.25			0.25	0.25	0.09	0.30		0.27	0.49	
Clearance Time (s)		9.0			9.0	9.0	8.0	8.0		9.0	9.0	
Vehicle Extension (s)		5.0			5.0	5.0	7.0	0.2		5.0	0.2	
Lane Grp Cap (vph)		746			806	361	267	1373		844	2211	
v/s Ratio Prot		0.17			c0.22		c0.06	0.12		0.11	c0.28	
v/s Ratio Perm						0.08						
v/c Ratio		0.68			0.86	0.31	0.65	0.39		0.39	0.58	
Uniform Delay, d1		50.4			53.5	45.3	66.3	41.6		44.4	27.5	
Progression Factor		1.00			1.00	1.00	1.00	1.00		1.00	1.00	
Incremental Delay, d2		4.9			11.9	2.2	9.9	0.8		1.4	1.1	
Delay (s)		55.3			65.5	47.5	76.2	42.5		45.8	28.6	
Level of Service		Е			Е	D	Е	D		D	С	
Approach Delay (s)		55.3			59.0			50.7			32.1	
Approach LOS		Е			Е			D			С	
Intersection Summary												
HCM 2000 Control Delay			46.2	H	CM 2000	Level of	Service		D			
HCM 2000 Volume to Capacity	ratio		0.67									
Actuated Cycle Length (s)			150.0		um of lost				26.0			
Intersection Capacity Utilization			75.2%	IC	U Level	of Service			D			
Analysis Period (min)			15									
c Critical Lane Group												

HCM Unsignalized Intersection Capacity Analysis 1: Monroe St & E Middle Ln

	→	\rightarrow	•	←	4	~
Movement	EBT	EBR	WBL	WBT	NBL	NBR
Lane Configurations	∱ }			^		7
Traffic Volume (veh/h)	435	4	0	322	0	51
Future Volume (Veh/h)	435	4	0	322	0	51
Sign Control	Free			Free	Stop	
Grade	0%			0%	0%	
Peak Hour Factor	0.87	0.87	0.87	0.87	0.87	0.87
Hourly flow rate (vph)	500	5	0	370	0	59
Pedestrians	12			2	38	
Lane Width (ft)	12.0			12.0	12.0	
Walking Speed (ft/s)	3.5			3.5	3.5	
Percent Blockage	1			0	4	
Right turn flare (veh)						
Median type	None			None		
Median storage veh)						
Upstream signal (ft)						
pX, platoon unblocked						
vC, conflicting volume			543		738	292
vC1, stage 1 conf vol						
vC2, stage 2 conf vol						
vCu, unblocked vol			543		738	292
tC, single (s)			4.1		6.8	6.9
tC, 2 stage (s)						
tF (s)			2.2		3.5	3.3
p0 queue free %			100		100	91
cM capacity (veh/h)			985		337	677
Direction, Lane #	EB 1	EB 2	WB 1	WB 2	NB 1	
Volume Total	333	172	185	185	59	
Volume Left	0	0	0	0	0	
Volume Right	0	5	0	0	59	
cSH	1700	1700	1700	1700	677	
Volume to Capacity	0.20	0.10	0.11	0.11	0.09	
Queue Length 95th (ft)	0	0	0	0	7	
Control Delay (s)	0.0	0.0	0.0	0.0	10.8	
Lane LOS					В	
Approach Delay (s)	0.0		0.0		10.8	
Approach LOS					В	
Intersection Summary						
Average Delay			0.7			
Intersection Capacity Utiliz	ation		24.5%	IC	U Level o	f Service
Analysis Period (min)			15			

HCM Unsignalized Intersection Capacity Analysis

2: Monroe St & E Montgomery Ave

	•	•	•	†	↓	4
Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations	W			†	†	
Sign Control	Stop			Stop	Stop	
Traffic Volume (vph)	0	0	0	0	0	0
Future Volume (vph)	0	0	0	0	0	0
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Hourly flow rate (vph)	0	0	0	0	0	0
Direction, Lane #	EB 1	NB 1	SB 1			
Volume Total (vph)	0	0	0			
Volume Left (vph)	0	0	0			
Volume Right (vph)	0	0	0			
Hadj (s)	0.00	0.00	0.00			
Departure Headway (s)	3.9	3.9	3.9			
Degree Utilization, x	0.00	0.00	0.00			
Capacity (veh/h)	917	917	917			
Control Delay (s)	6.9	6.9	6.9			
Approach Delay (s)	0.0	0.0	0.0			
Approach LOS	Α	Α	Α			
Intersection Summary						
Delay			0.0			
Level of Service			Α			
Intersection Capacity Utiliz	zation		0.0%	IC	U Level o	f Service
Analysis Period (min)			15			

HCM Unsignalized Intersection Capacity Analysis 3: Monroe St & Monroe PI

o. Monioc of a Mo	1110011										• ., .	.,
	•	→	•	•	+	•	•	†	<i>></i>	/	Ţ	4
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		4			4			4	7		4	
Sign Control		Stop			Stop			Stop			Stop	
Traffic Volume (vph)	0	0	0	0	0	0	0	0	0	0	0	0
Future Volume (vph)	0	0	0	0	0	0	0	0	0	0	0	0
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Hourly flow rate (vph)	0	0	0	0	0	0	0	0	0	0	0	0
Direction, Lane #	EB 1	WB 1	NB 1	NB 2	SB 1							
Volume Total (vph)	0	0	0	0	0							
Volume Left (vph)	0	0	0	0	0							
Volume Right (vph)	0	0	0	0	0							
Hadj (s)	0.00	0.00	0.00	0.00	0.00							
Departure Headway (s)	3.9	3.9	4.5	4.5	4.0							
Degree Utilization, x	0.00	0.00	0.00	0.00	0.00							
Capacity (veh/h)	917	917	806	806	900							
Control Delay (s)	6.9	6.9	6.3	6.3	7.0							
Approach Delay (s)	0.0	0.0	0.0		0.0							
Approach LOS	Α	Α	Α		Α							
Intersection Summary												
Delay			0.0									
Level of Service			Α									
Intersection Capacity Utiliza	ition		0.0%	IC	U Level	of Service			Α			
Analysis Period (min)			15									

HCM Signalized Intersection Capacity Analysis

4: Monroe St & E Jefferson St

	۶	→	•	•	—	•	•	†	~	/	↓	-√
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	Ŋ	↑ ↑		, J	∱ }			414			414	
Traffic Volume (vph)	47	744	37	53	652	30	65	106	183	62	97	96
Future Volume (vph)	47	744	37	53	652	30	65	106	183	62	97	96
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	5.5	5.5		5.5	5.5			6.0			6.0	
Lane Util. Factor	1.00	0.95		1.00	0.95			0.95			0.95	
Frpb, ped/bikes	1.00	1.00		1.00	1.00			0.96			0.96	
Flpb, ped/bikes	1.00	1.00		1.00	1.00			0.99			0.99	
Frt	1.00	0.99		1.00	0.99			0.92			0.94	
Flt Protected	0.95	1.00		0.95	1.00			0.99			0.99	
Satd. Flow (prot)	1592	3158		1591	3161			2774			2825	
Flt Permitted	0.32	1.00		0.25	1.00			0.82			0.74	
Satd. Flow (perm)	539	3158		419	3161			2292			2103	
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	51	809	40	58	709	33	71	115	199	67	105	104
RTOR Reduction (vph)	0	0	0	0	0	0	0	0	0	0	0	0
Lane Group Flow (vph)	51	849	0	58	742	0	0	385	0	0	276	0
Confl. Peds. (#/hr)	8		19	19		8	77		49	49		77
Turn Type	pm+pt	NA		pm+pt	NA		Perm	NA		Perm	NA	
Protected Phases	1	6		5	2			8			4	
Permitted Phases	6			2			8			4		
Actuated Green, G (s)	47.9	43.6		50.5	44.9			23.8			23.8	
Effective Green, g (s)	47.9	43.6		50.5	44.9			23.8			23.8	
Actuated g/C Ratio	0.53	0.48		0.56	0.50			0.26			0.26	
Clearance Time (s)	5.5	5.5		5.5	5.5			6.0			6.0	
Vehicle Extension (s)	3.0	3.0		3.0	3.0			3.0			3.0	
Lane Grp Cap (vph)	337	1529		308	1576			606			556	
v/s Ratio Prot	0.01	c0.27		c0.01	0.23							
v/s Ratio Perm	0.07			0.09				c0.17			0.13	
v/c Ratio	0.15	0.56		0.19	0.47			0.64			0.50	
Uniform Delay, d1	10.4	16.4		9.8	14.8			29.3			28.0	
Progression Factor	1.00	1.00		1.45	1.76			1.00			1.00	
Incremental Delay, d2	0.2	1.5		0.3	0.9			2.1			0.7	
Delay (s)	10.6	17.8		14.4	26.9			31.3			28.7	
Level of Service	В	В		В	С			С			С	
Approach Delay (s)		17.4			26.0			31.3			28.7	
Approach LOS		В			С			С			С	
Intersection Summary												
HCM 2000 Control Delay			23.9	Н	CM 2000	Level of S	Service		С			
HCM 2000 Volume to Capa	acity ratio		0.55									
Actuated Cycle Length (s)			90.0	S	um of lost	time (s)			17.0			
Intersection Capacity Utiliz	ation		85.0%		CU Level				Е			
Analysis Period (min)			15									
c Critical Lane Group												

HCM Signalized Intersection Capacity Analysis 5: Monroe St & Fleet St

Movement EBL EBT EBR WBL WBT WBR NBL NBT NBR SBL SBT SBF Traffic Volume (yph) 157 189 83 13 180 44 11 66 7 9 73 134 14 14 16 16 7 9 73 134 14 14 16 16 7 9 73 134 14 14 16 16 7 9 73 134 14 14 16 16 7 9 73 134 14 14 16 16 7 9 73 134 14 14 16 16 7 9 73 134 14 14 16 16 7 9 73 134 14 14 16 16 7 9 73 134 14 14 16 16 7 9 73 134 14 14 16 16 7 9 73 134 14 14 16 16 7 9 73 134 14 14 16 16 7 9 73 134 14 14 16 16 7 9 73 134 14 14 14 16 16 7 9 73 134 14 14 16 17 14 14 14 16 17 14 14 14 16 17 14 14 14 16 17 14 14 14 16 17 14 14 14 16 17 14 14 14 16 17 14 14 14 16 17 14 14 14 16 17 14 14 14 16 17 14 14 14 16 17 14 14 14 16 17 14 16 17 14 14 16 17 14 14 16 17 14 14 16 14 14 16 17 14 14 16 17 14 14 16 17 14 14 16 17 14 14 16 17 14 14 16 17 14 14 16 17 14 14 16 17 14 14 16 17 14 14 16 14 14 16 14 14	J. MOINGE St & Flee			_		_	_		_			I	,	
Lane Configurations 1		•	→	•	•	•	•	1	T		-	¥	*	
Traffic Volume (vph) 157 189 83 13 180 44 111 66 7 9 73 134 lideal Flow (vph) 157 189 83 13 180 44 111 66 7 9 73 134 lideal Flow (vph) 150 1900 1900 1900 1900 1900 1900 1900	Movement	EBL		EBR	WBL	WBT	WBR	NBL		NBR	SBL	SBT	SBR	
Future Volume (vph)													7	
Ideal Flow (vphph)										7	9			
Total Lost time (s)										-			134	
Lane Util. Factor		1900		1900	1900		1900	1900		1900	1900			
Frpb, ped/bikes													5.0	
Fipb, pedrbikes														
Fit 0.97 0.97 0.99 1.00 0.85 Fit Protected 0.98 1.00 0.99 0.99 1.00 Satd. Flow (prot) 2987 3072 1640 1664 1394 Fit Permitted 0.69 0.90 0.94 0.96 1.00 Satd. Flow (perm) 2085 2781 1559 1606 1394 Peak-hour factor, PHF 0.60 0.60 0.60 0.60 0.60 0.60 0.60 0.60 0.60 Adj. Flow (pph) 262 315 138 22 300 73 18 110 12 15 122 223 RTOR Reduction (vph) 0 12 0 0 11 0 0 5 0 0 0 0 Lane Group Flow (vph) 0 703 0 0 384 0 0 135 0 0 137 136 Confl. Peds. (#/hr) 9 23 23 9 7 19 19 7 Turn Type Perm NA Perm NA Perm NA Perm NA Perm NA Permitted Phases 6 2 8 4 6 Actuated Green, G (s) 66.9 66.9 13.1 13.1 66.9 Actuated Green, G (s) 66.9 66.9 13.1 13.1 66.9 Actuated grow (ph) 1549 2067 226 233 1036 Vis Ratio Prot Vyth 1549 2067 226 233 1036 Vis Ratio Prot Vyth 1549 2067 226 233 1036 Vis Ratio Prot Vyth 1549 2067 226 233 1036 Vis Ratio Prot Vyth 1549 2067 226 233 1036 Vis Ratio Prot Vyth 1549 2067 226 233 1036 Vis Ratio Prot Vyth 1549 2067 226 233 1036 Vis Ratio Prot Vyth 1549 2067 226 233 1036 Vis Ratio Prot Vyth 1549 2067 226 233 1036 Vis Ratio Prot Vyth 1549 2067 226 233 1036 Vis Ratio Prot Vyth 1549 2067 226 233 1036 Vis Ratio Prot Vyth 1549 2067 226 233 1036 Vis Ratio Prot Vyth 1549 2067 226 233 1036 Vis Ratio Prot Vyth 1549 2067 226 233 1036 Vis Ratio Prot Vyth 1549 2067 226 233 1036 Vis Ratio Prot Vyth 2067 226 233 1036 Vis Ratio Prot 2067 2067 2067 2067 2067 Vis Ratio Prot 2067 2067 2067 2067 2067 2067 Vis Ratio Pr														
Fit Protected 0,98 1.00 0.99 0.99 1.00 Satd. Flow (prot) 2987 3072 1640 1664 1394 Fit Permitted 0,69 0.99 0.99 0.94 0.96 1394 0.96 1.394 0.96 1.00 Satd. Flow (perm) 2085 2781 1559 1606 1394 0.96 1.394 0.96 1.00 Satd. Flow (perm) 2085 2781 1559 1606 1394 0.96 1.00 Satd. Flow (perm) 2085 2781 1559 1606 1394 0.96 1.00 Satd. Flow (perm) 2085 2781 1559 1606 1394 0.96 1.00 Satd. Flow (perm) 2085 2781 1559 1606 1394 0.96 1.00 Satd. Flow (perm) 2085 2781 1559 1606 1394 0.96 1.00 Satd. Flow (perm) 2082 315 138 22 300 73 18 110 12 15 122 223 RTOR Reduction (protected (perm) 0 12 0 0 11 0 0 5 0 0 0 57 1.00 Satd. Flow (protected (perm) 0 703 0 0 384 0 0 135 0 0 137 166 0.00 Confl. Peds. (#hr) 9 23 23 9 7 19 19 7 7 19 19 7 7 10 Turn Type Perm NA														
Satd. Flow (prot)													0.85	
Fit Permitted	Flt Protected											0.99	1.00	
Satd. Flow (perm) 2085 2781 1559 1606 1394 Peak-hour factor, PHF 0.60 0.70 13.1	Satd. Flow (prot)												1394	
Peak-hour factor, PHF 0.60	Flt Permitted											0.96	1.00	
Adj. Flow (vph)	Satd. Flow (perm)		2085			2781			1559			1606	1394	
RTOR Reduction (vph) 0 12 0 0 11 0 5 0 0 0 57 Lane Group Flow (vph) 0 703 0 0 384 0 0 135 0 0 137 166 Confl. Peds. (#/hr) 9 23 23 9 7 19 19 9 7 166 0 0 137 166 0 0 137 166 0 0 137 166 0 0 137 166 0 0 137 166 0	Peak-hour factor, PHF	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	
RTOR Reduction (vph) 0 12 0 0 11 0 0 5 0 0 0 5 5 1 1 1 1 1 1 1 1	Adj. Flow (vph)	262	315	138	22	300	73	18	110	12	15	122	223	
Confil. Peds. (#/hr) 9 23 23 9 7 19 19 7 Turn Type Perm NA NB A D 66.9 66.9 66.9 66.9 13.1 13.1 13.1 16.0 10.15 10.15 10.15 10.15 10.15 10.15<	RTOR Reduction (vph)	0	12	0	0	11	0	0	5	0	0	0	57	
Confi. Peds. (#/hr) 9 23 23 9 7 19 19 7 Turn Type Perm NA Perm NA Perm NA Perm NA Perm NA Perm NA custom Protected Phases 6 2 8 4 6 6 2 8 4 6 6 6 9 66.9 13.1 13.1 66.9 66.9 13.1 13.1 66.9 66.9 13.1 13.1 66.9 66.9 13.1 13.1 13.1 66.9 66.9 13.1 13.1 13.1 66.9 66.9 13.1 13.1 13.1 66.9 66.9 13.1 13.1 66.9 66.9 13.1 13.1 66.9 66.9 13.1 13.1 13.1 66.9 66.9 13.1 13.1 13.1 13.1 66.9 66.9 13.1 13.1 13.1 13.1 13.1 13.1 13.1 13.1 <t< td=""><td>Lane Group Flow (vph)</td><td>0</td><td>703</td><td>0</td><td>0</td><td>384</td><td>0</td><td>0</td><td>135</td><td>0</td><td>0</td><td>137</td><td>166</td></t<>	Lane Group Flow (vph)	0	703	0	0	384	0	0	135	0	0	137	166	
Turn Type		9		23	23		9	7		19	19		7	
Protected Phases 6		Perm	NA		Perm	NA		Perm	NA		Perm	NA	custom	
Permitted Phases 6													-	
Actuated Green, G (s) 66.9 66.9 13.1 13.1 66.9 Effective Green, g (s) 66.9 66.9 13.1 13.1 66.9 Actuated g/C Ratio 0.74 0.74 0.15 0.15 0.74 Clearance Time (s) 5.0 5.0 5.0 5.0 5.0 5.0 Vehicle Extension (s) 3.0 3.0 3.0 3.0 3.0 3.0 Lane Grp Cap (vph) 1549 2067 226 233 1036 V/s Ratio Prot V/s Ratio Prot V/s Ratio Perm		6	-		2			8	-		4		6	
Effective Green, g (s) 66.9 66.9 13.1 13.1 66.9 Actuated g/C Ratio 0.74 0.74 0.15 0.15 0.74 Clearance Time (s) 5.0 5.0 5.0 5.0 5.0 5.0 Vehicle Extension (s) 3.0 3.0 3.0 3.0 3.0 3.0 3.0 Lane Grp Cap (vph) 1549 2067 226 233 1036 V/S Ratio Prot v/S Ratio Perm c0.34 0.14 c0.09 0.09 0.12 V/S Ratio Perm c0.34 0.14 c0.09 0.09 0.12 V/S Ratio Perm c0.34 0.19 0.60 0.59 0.16 Uniform Delay, d1 4.5 3.4 36.0 35.9 3.4 Progression Factor 0.82 1.00 1.00 0.92 1.23 Incremental Delay, d2 0.8 0.2 4.2 3.7 0.3 Delay (s) 4.4 3.6 40.2 36.7 4.5 Level of Service A A D B <td col<="" td=""><td></td><td></td><td>66.9</td><td></td><td></td><td>66.9</td><td></td><td></td><td>13.1</td><td></td><td></td><td>13.1</td><td>66.9</td></td>	<td></td> <td></td> <td>66.9</td> <td></td> <td></td> <td>66.9</td> <td></td> <td></td> <td>13.1</td> <td></td> <td></td> <td>13.1</td> <td>66.9</td>			66.9			66.9			13.1			13.1	66.9
Actuated g/C Ratio 0.74 0.74 0.15 0.75 0.75 Clearance Time (s) 5.0 5.0 5.0 5.0 5.0 Vehicle Extension (s) 3.0 3.0 3.0 3.0 3.0 3.0 Lane Grp Cap (vph) 1549 2067 226 233 1036 v/s Ratio Prot 2067 226 233 1036 v/s Ratio Perm c0.34 0.14 c0.09 0.09 0.12 v/s Ratio Perm c0.34 0.14 c0.09 0.09 0.10 Uniform Delay, d1 4.5 3.4 36.0 35.9 3.4 Progression Factor 0.82 1.00 1.00 0.92 1.23 Incremental Delay, d2 0.8 0.2 4.2 3.7 0.3 Approach Delay (s) 4.4 3.6 </td <td> ,</td> <td></td> <td>66.9</td>	,												66.9	
Clearance Time (s) 5.0 3.0														
Vehicle Extension (s) 3.0 0.1 0.0 0.1 0.0 0.1 0.0 0.1 0.0 0.1 0.0 0.1 0.0 0.1 0.0 0.1 0.0 0.0 0.0 0.1 0.0 0.0 0.0 0.0 1.0 0.0 0.0 0.0 1.0 0.0 0.0 0.0 1.0 0.0 0.0 0.0 3.0 3.0 3.0 3.0 0.2 4.2 3.7 0.3 3.0 0.2 4.2 3.0														
Lane Grp Cap (vph) 1549 2067 226 233 1036 v/s Ratio Prot v/s Ratio Perm c0.34 0.14 c0.09 0.09 0.12 v/c Ratio 0.45 0.19 0.60 0.59 0.16 Uniform Delay, d1 4.5 3.4 36.0 35.9 3.4 Progression Factor 0.82 1.00 1.00 0.92 1.23 Incremental Delay, d2 0.8 0.2 4.2 3.7 0.3 Delay (s) 4.4 3.6 40.2 36.7 4.5 Level of Service A A D D A Approach Delay (s) 4.4 3.6 40.2 16.7 Approach LOS A A A D B Intersection Summary B HCM 2000 Centrol Delay 10.1 HCM 2000 Level of Service B HCM 2000 Volume to Capacity ratio 0.48 A 0.5 10.0 Intersection Capacity Utilization 68.7% ICU Level of Service C Analysis Period (min) 15 <td></td>														
v/s Ratio Prot v/s Ratio Perm c0.34 0.14 c0.09 0.09 0.12 v/c Ratio 0.45 0.19 0.60 0.59 0.16 Uniform Delay, d1 4.5 3.4 36.0 35.9 3.4 Progression Factor 0.82 1.00 1.00 0.92 1.23 Incremental Delay, d2 0.8 0.2 4.2 3.7 0.3 Delay (s) 4.4 3.6 40.2 36.7 4.5 Level of Service A A D D A Approach Delay (s) 4.4 3.6 40.2 16.7 A Approach LOS A A D B B Intersection Summary B HCM 2000 Level of Service B B HCM 2000 Volume to Capacity ratio 0.48 A D B Actuated Cycle Length (s) 90.0 Sum of lost time (s) 10.0 Intersection Capacity Utilization 68.7% ICU Level of Service C Analysis Period (min) 15														
v/s Ratio Perm c0.34 0.14 c0.09 0.09 0.12 v/c Ratio 0.45 0.19 0.60 0.59 0.16 Uniform Delay, d1 4.5 3.4 36.0 35.9 3.4 Progression Factor 0.82 1.00 1.00 0.92 1.23 Incremental Delay, d2 0.8 0.2 4.2 3.7 0.3 Delay (s) 4.4 3.6 40.2 36.7 4.5 Level of Service A A D D D Approach Delay (s) 4.4 3.6 40.2 16.7 Approach LOS A A D B Intersection Summary HCM 2000 Control Delay 10.1 HCM 2000 Level of Service B HCM 2000 Volume to Capacity ratio 0.48 Actuated Cycle Length (s) 90.0 Sum of lost time (s) 10.0 Intersection Capacity Utilization 68.7% ICU Level of Service C Analysis Period (min) 15			1010			2007			LLO			200	1000	
v/c Ratio 0.45 0.19 0.60 0.59 0.16 Uniform Delay, d1 4.5 3.4 36.0 35.9 3.4 Progression Factor 0.82 1.00 1.00 0.92 1.23 Incremental Delay, d2 0.8 0.2 4.2 3.7 0.3 Delay (s) 4.4 3.6 40.2 36.7 4.5 Level of Service A A A D D A Approach Delay (s) 4.4 3.6 40.2 16.7 A Approach LOS A A A D B Intersection Summary B HCM 2000 Level of Service B B HCM 2000 Volume to Capacity ratio 0.48 A A D B Actuated Cycle Length (s) 90.0 Sum of lost time (s) 10.0 Intersection Capacity Utilization 68.7% ICU Level of Service C Analysis Period (min) 15			c0 34			0 14			c0 09			0.09	0.12	
Uniform Delay, d1 4.5 3.4 36.0 35.9 3.4 Progression Factor 0.82 1.00 1.00 0.92 1.23 Incremental Delay, d2 0.8 0.2 4.2 3.7 0.3 Delay (s) 4.4 3.6 40.2 36.7 4.5 Level of Service A A A D D A Approach Delay (s) 4.4 3.6 40.2 16.7 Approach LOS A A A D B Intersection Summary HCM 2000 Level of Service B HCM 2000 Volume to Capacity ratio 0.48 Actuated Cycle Length (s) 90.0 Sum of lost time (s) 10.0 Intersection Capacity Utilization 68.7% ICU Level of Service C Analysis Period (min) 15														
Progression Factor 0.82 1.00 1.00 0.92 1.23 Incremental Delay, d2 0.8 0.2 4.2 3.7 0.3 Delay (s) 4.4 3.6 40.2 36.7 4.5 Level of Service A A A D D A Approach Delay (s) 4.4 3.6 40.2 16.7 A Approach LOS A A A D B Intersection Summary B HCM 2000 Control Delay 10.1 HCM 2000 Level of Service B HCM 2000 Volume to Capacity ratio 0.48 A A D 10.0 Actuated Cycle Length (s) 90.0 Sum of lost time (s) 10.0 10.0 Intersection Capacity Utilization 68.7% ICU Level of Service C Analysis Period (min) 15														
Incremental Delay, d2														
Delay (s) 4.4 3.6 40.2 36.7 4.5 Level of Service A A D D A Approach Delay (s) 4.4 3.6 40.2 16.7 Approach LOS A A D B Intersection Summary HCM 2000 Control Delay 10.1 HCM 2000 Level of Service B HCM 2000 Volume to Capacity ratio 0.48 Actuated Cycle Length (s) 90.0 Sum of lost time (s) 10.0 Intersection Capacity Utilization 68.7% ICU Level of Service C Analysis Period (min) 15														
Level of Service A A D D A Approach Delay (s) 4.4 3.6 40.2 16.7 Approach LOS A A D B Intersection Summary HCM 2000 Control Delay 10.1 HCM 2000 Level of Service B HCM 2000 Volume to Capacity ratio 0.48 Actuated Cycle Length (s) 90.0 Sum of lost time (s) 10.0 Intersection Capacity Utilization 68.7% ICU Level of Service C Analysis Period (min) 15														
Approach Delay (s) 4.4 3.6 40.2 16.7 Approach LOS A A A D B Intersection Summary HCM 2000 Control Delay 10.1 HCM 2000 Level of Service B HCM 2000 Volume to Capacity ratio 0.48 Actuated Cycle Length (s) 90.0 Sum of lost time (s) 10.0 Intersection Capacity Utilization 68.7% ICU Level of Service C Analysis Period (min) 15														
Approach LOS A A A D B Intersection Summary HCM 2000 Control Delay 10.1 HCM 2000 Level of Service B HCM 2000 Volume to Capacity ratio 0.48 Actuated Cycle Length (s) 90.0 Sum of lost time (s) 10.0 Intersection Capacity Utilization 68.7% ICU Level of Service C Analysis Period (min) 15													, , , , , , , , , , , , , , , , , , ,	
HCM 2000 Control Delay 10.1 HCM 2000 Level of Service B HCM 2000 Volume to Capacity ratio 0.48 Actuated Cycle Length (s) 90.0 Sum of lost time (s) 10.0 Intersection Capacity Utilization 68.7% ICU Level of Service C Analysis Period (min) 15	Approach LOS													
HCM 2000 Volume to Capacity ratio O.48 Actuated Cycle Length (s) Intersection Capacity Utilization O.48 Sum of lost time (s) OCU Level of Service C Analysis Period (min) O.48 Sum of lost time (s) ICU Level of Service C	Intersection Summary													
HCM 2000 Volume to Capacity ratio O.48 Actuated Cycle Length (s) Intersection Capacity Utilization O.48 Sum of lost time (s) OCU Level of Service C Analysis Period (min) O.48 Sum of lost time (s) ICU Level of Service C	HCM 2000 Control Delay			10.1	Н	CM 2000	Level of	Service		В				
Actuated Cycle Length (s) 90.0 Sum of lost time (s) 10.0 Intersection Capacity Utilization 68.7% ICU Level of Service C Analysis Period (min) 15		city ratio												
Intersection Capacity Utilization 68.7% ICU Level of Service C Analysis Period (min) 15		,			Sı	um of lost	time (s)			10.0				
Analysis Period (min) 15		tion												

HCM Signalized Intersection Capacity Analysis 6: Maryland Ave & Fleet St

o. Mai yianu Ave & i	1001.0											17/2020
	•	-	•	•	•	•	4	†	/	-	↓	4
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		4		7		7		†	7	7	†	
Traffic Volume (vph)	12	4	2	302	0	80	0	332	415	21	308	0
Future Volume (vph)	12	4	2	302	0	80	0	332	415	21	308	0
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)		4.5		4.5		4.5		4.5	4.5	4.5	4.5	
Lane Util. Factor		1.00		1.00		1.00		1.00	1.00	1.00	1.00	
Frpb, ped/bikes		0.99		1.00		0.97		1.00	0.97	1.00	1.00	
Flpb, ped/bikes		1.00		1.00		1.00		1.00	1.00	1.00	1.00	
Frt		0.98		1.00		0.85		1.00	0.85	1.00	1.00	
Flt Protected		0.97		0.95		1.00		1.00	1.00	0.95	1.00	
Satd. Flow (prot)		1579		1593		1376		1676	1388	1593	1676	
Flt Permitted		0.97		0.95		1.00		1.00	1.00	0.18	1.00	
Satd. Flow (perm)		1579		1593		1376		1676	1388	301	1676	
Peak-hour factor, PHF	0.71	0.71	0.71	0.71	0.71	0.71	0.71	0.71	0.71	0.71	0.71	0.71
Adj. Flow (vph)	17	6	3	425	0	113	0	468	585	30	434	0
RTOR Reduction (vph)	0	3	0	0	0	77	0	0	469	0	0	0
Lane Group Flow (vph)	0	23	0	425	0	36	0	468	116	30	434	0
Confl. Peds. (#/hr)	5		5	5		5	5		8	8		5
Turn Type	Split	NA		Prot		Perm	-	NA	Perm	pm+pt	NA	
Protected Phases	3	3		4		1 01111		2	1 01111	1	6	
Permitted Phases	J	J		•		4		_	2	6	•	
Actuated Green, G (s)		2.6		28.8		28.8		17.8	17.8	45.1	45.1	
Effective Green, g (s)		2.6		28.8		28.8		17.8	17.8	45.1	45.1	
Actuated g/C Ratio		0.03		0.32		0.32		0.20	0.20	0.50	0.50	
Clearance Time (s)		4.5		4.5		4.5		4.5	4.5	4.5	4.5	
Vehicle Extension (s)		4.0		2.0		2.0		5.0	5.0	3.0	5.0	
Lane Grp Cap (vph)		45		509		440		331	274	478	839	
v/s Ratio Prot		c0.01		c0.27		770		c0.28	217	0.02	c0.26	
v/s Ratio Perm		00.01		00.21		0.03		00.20	0.08	0.02	00.20	
v/c Ratio		0.51		0.83		0.08		1.41	0.42	0.06	0.52	
Uniform Delay, d1		43.1		28.4		21.4		36.1	31.6	13.3	15.1	
Progression Factor		1.00		1.04		2.57		1.00	1.00	1.00	1.00	
Incremental Delay, d2		12.5		10.7		0.0		203.3	4.7	0.3	2.3	
Delay (s)		55.6		40.2		55.0		239.4	36.3	13.6	17.4	
Level of Service		E		D		D		F	D	В	В	
Approach Delay (s)		55.6			43.3			126.6			17.1	
Approach LOS		E			D			F			В	
Intersection Summary												
HCM 2000 Control Delay			79.8	H	CM 2000	Level of S	Service		Е			
HCM 2000 Volume to Capaci	ty ratio		0.88									
Actuated Cycle Length (s)			90.0	Sı	um of los	time (s)			18.0			
Intersection Capacity Utilization	on		51.8%	IC	U Level	of Service			Α			
Analysis Period (min)			15									
c Critical Lane Group												

04/14/2023

HCM Signalized Intersection Capacity Analysis

7: MD 355 & E Jefferson St

	۶	→	•	•	+	4	1	†	/	/	↓	4
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		ተኈ			^	7	14.54	ተተተ		44	↑ ↑₽	
Traffic Volume (vph)	0	591	238	0	443	378	267	1003	0	535	847	61
Future Volume (vph)	0	591	238	0	443	378	267	1003	0	535	847	61
\ I I /	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)		9.0			9.0	9.0	8.0	8.0		9.0	9.0	
Lane Util. Factor		0.95			0.95	1.00	0.97	0.91		0.97	0.91	
Frpb, ped/bikes		1.00			1.00	1.00	1.00	1.00		1.00	1.00	
Flpb, ped/bikes		1.00			1.00	1.00	1.00	1.00		1.00	1.00	
Frt		0.96			1.00	0.85	1.00	1.00		1.00	0.99	
Flt Protected		1.00			1.00	1.00	0.95	1.00		0.95	1.00	
Satd. Flow (prot)		3048			3185	1425	3090	4577		3090	4523	
Flt Permitted		1.00			1.00	1.00	0.95	1.00		0.95	1.00	
Satd. Flow (perm)		3048			3185	1425	3090	4577		3090	4523	
Peak-hour factor, PHF	0.98	0.98	0.98	0.98	0.98	0.98	0.98	0.98	0.98	0.98	0.98	0.98
Adj. Flow (vph)	0	603	243	0	452	386	272	1023	0	546	864	62
RTOR Reduction (vph)	0	24	0	0	0	244	0	0	0	0	4	0
Lane Group Flow (vph)	0	822	0	0	452	142	272	1023	0	546	922	0
Confl. Peds. (#/hr)												5
Turn Type		NA			NA	Perm	Prot	NA		Prot	NA	
Protected Phases		4			8		1	5		6	2	
Permitted Phases						8						
Actuated Green, G (s)		51.0			51.0	51.0	25.0	76.0		27.0	78.0	
Effective Green, g (s)		51.0			51.0	51.0	25.0	76.0		27.0	78.0	
Actuated g/C Ratio		0.28			0.28	0.28	0.14	0.42		0.15	0.43	
Clearance Time (s)		9.0			9.0	9.0	8.0	8.0		9.0	9.0	
Vehicle Extension (s)		5.0			5.0	5.0	7.0	0.2		5.0	0.2	
Lane Grp Cap (vph)		863			902	403	429	1932		463	1959	
v/s Ratio Prot		c0.27			0.14		0.09	c0.22		c0.18	0.20	
v/s Ratio Perm						0.10						
v/c Ratio		0.95			0.50	0.35	0.63	0.53		1.18	0.47	
Uniform Delay, d1		63.3			53.9	51.4	73.2	38.7		76.5	36.3	
Progression Factor		0.96			1.00	1.00	1.00	1.00		1.00	1.00	
Incremental Delay, d2		18.9			2.0	2.4	5.9	1.0		101.1	8.0	
Delay (s)		80.0			55.9	53.8	79.0	39.7		177.6	37.1	
Level of Service		Ε			Ε	D	Ε	D		F	D	
Approach Delay (s)		80.0			54.9			48.0			89.2	
Approach LOS		Е			D			D			F	
Intersection Summary												
HCM 2000 Control Delay			69.0	Н	CM 2000	Level of S	Service		Е			
HCM 2000 Volume to Capacity r	atio		0.78									
Actuated Cycle Length (s)			180.0	S	um of lost	t time (s)			26.0			
Intersection Capacity Utilization			86.8%			of Service			Е			
Analysis Period (min)			15									
c Critical Lane Group												

04/14/2023

Intersection: 1: Monroe St & E Middle Ln

Movement	EB	EB	WB	WB	NB
Directions Served	Т	TR	Т	T	R
Maximum Queue (ft)	29	6	25	12	46
Average Queue (ft)	2	0	2	0	22
95th Queue (ft)	16	4	15	6	48
Link Distance (ft)	640	640	187	187	
Upstream Blk Time (%)					
Queuing Penalty (veh)					
Storage Bay Dist (ft)					
Storage Blk Time (%)					
Queuing Penalty (veh)					

Intersection: 2: Monroe St & E Montgomery Ave

Movement
Directions Served
Maximum Queue (ft)
Average Queue (ft)
95th Queue (ft)
Link Distance (ft)
Upstream Blk Time (%)
Queuing Penalty (veh)
Storage Bay Dist (ft)
Storage Blk Time (%)
Queuing Penalty (veh)

Intersection: 3: Monroe St & Monroe PI

ement
ctions Served
imum Queue (ft)
rage Queue (ft)
Queue (ft)
Distance (ft)
tream Blk Time (%)
uing Penalty (veh)
age Bay Dist (ft)
age Blk Time (%)
uing Penalty (veh)

04/14/2023

Intersection: 4: Monroe St & E Jefferson St

Movement	EB	EB	EB	WB	WB	WB	NB	NB	SB	SB	
Directions Served	L	Т	TR	L	T	TR	LT	TR	LT	TR	
Maximum Queue (ft)	72	208	244	150	452	362	130	138	104	100	
Average Queue (ft)	33	82	116	68	162	181	68	74	40	43	
95th Queue (ft)	63	151	204	150	355	339	116	129	85	88	
Link Distance (ft)		540	540		880	880	427	427			
Upstream Blk Time (%)											
Queuing Penalty (veh)											
Storage Bay Dist (ft)	250			125							
Storage Blk Time (%)		0		0	9						
Queuing Penalty (veh)		0		0	9						

Intersection: 5: Monroe St & Fleet St

Movement	EB	EB	WB	WB	NB	SB	SB
Directions Served	LT	TR	LT	TR	LTR	LT	R
Maximum Queue (ft)	122	120	130	93	151	128	66
Average Queue (ft)	60	55	53	34	73	52	22
95th Queue (ft)	109	106	108	75	127	101	51
Link Distance (ft)	354	354	574	574	521	427	427
Upstream Blk Time (%)							
Queuing Penalty (veh)							
Storage Bay Dist (ft)							
Storage Blk Time (%)							
Queuing Penalty (yeh)							

Intersection: 6: Maryland Ave & Fleet St

Movement	EB	WB	WB	NB	NB	SB	SB
Directions Served	LTR	L	R	Т	R	L	Т
Maximum Queue (ft)	24	312	99	220	90	80	149
Average Queue (ft)	3	165	38	118	23	28	50
95th Queue (ft)	17	262	73	195	69	63	108
Link Distance (ft)	141	354	354	650			431
Upstream Blk Time (%)		0					
Queuing Penalty (veh)		0					
Storage Bay Dist (ft)					450	125	
Storage Blk Time (%)						0	1
Queuing Penalty (veh)						0	0

04/14/2023

Intersection: 7: MD 355 & E Jefferson St

Movement	EB	EB	WB	WB	WB	NB	NB	NB	NB	NB	SB	SB
Directions Served	Т	TR	T	T	R	L	L	Т	Т	Т	L	L
Maximum Queue (ft)	191	314	390	372	43	132	162	246	230	173	239	279
Average Queue (ft)	99	114	246	221	4	39	83	154	137	72	120	164
95th Queue (ft)	164	232	358	334	25	113	145	228	211	162	217	248
Link Distance (ft)	880	880	941	941	941			760	760	760		
Upstream Blk Time (%)												
Queuing Penalty (veh)												
Storage Bay Dist (ft)						275	275				425	425
Storage Blk Time (%)								0				
Queuing Penalty (veh)								0				

Intersection: 7: MD 355 & E Jefferson St

Movement	SB	SB	SB
Directions Served	T	Т	TR
Maximum Queue (ft)	355	357	302
Average Queue (ft)	246	237	177
95th Queue (ft)	333	321	276
Link Distance (ft)	658	658	658
Upstream Blk Time (%)			
Queuing Penalty (veh)			
Storage Bay Dist (ft)			
Storage Blk Time (%)	0		
Queuing Penalty (veh)	0		

Network Summary

Network wide Queuing Penalty: 10

Queuing Penalty (veh)

04/14/2023

Intersection: 1: Monroe St & E Middle Ln

Movement	EB	EB	WB	WB	NB
Directions Served	T	TR	T	T	R
Maximum Queue (ft)	29	28	39	6	55
Average Queue (ft)	3	1	2	0	26
95th Queue (ft)	20	12	17	4	49
Link Distance (ft)	640	640	187	187	
Upstream Blk Time (%)					
Queuing Penalty (veh)					
Storage Bay Dist (ft)					
Storage Blk Time (%)					

Intersection: 2: Monroe St & E Montgomery Ave

Movement Directions Served Maximum Queue (ft) Average Queue (ft) 95th Queue (ft) Link Distance (ft) Upstream Blk Time (%) Queuing Penalty (veh) Storage Bay Dist (ft) Storage Blk Time (%) Queuing Penalty (veh)

Intersection: 3: Monroe St & Monroe PI

Movement
Directions Served
Maximum Queue (ft)
Average Queue (ft)
95th Queue (ft)
Link Distance (ft)
Upstream Blk Time (%)
Queuing Penalty (veh)
Storage Bay Dist (ft)
Storage Blk Time (%)
Queuing Penalty (veh)
account, (con)

04/14/2023

Intersection: 4: Monroe St & E Jefferson St

Movement	EB	EB	EB	WB	WB	WB	NB	NB	SB	SB	
Directions Served	L	Т	TR	L	Т	TR	LT	TR	LT	TR	
Maximum Queue (ft)	66	236	247	149	315	342	154	224	138	171	
Average Queue (ft)	26	133	129	57	203	220	78	129	62	88	
95th Queue (ft)	58	211	217	145	315	327	133	195	125	154	
Link Distance (ft)		540	540		880	880	427	427			
Upstream Blk Time (%)											
Queuing Penalty (veh)											
Storage Bay Dist (ft)	250			125							
Storage Blk Time (%)		0		0	14						
Queuing Penalty (veh)		0		0	7						

Intersection: 5: Monroe St & Fleet St

Movement	EB	EB	WB	WB	NB	SB	SB
Directions Served	LT	TR	LT	TR	LTR	LT	R
Maximum Queue (ft)	114	94	89	70	126	124	78
Average Queue (ft)	41	35	32	19	58	49	27
95th Queue (ft)	86	78	72	54	103	103	62
Link Distance (ft)	354	354	574	574	521	427	427
Upstream Blk Time (%)							
Queuing Penalty (veh)							
Storage Bay Dist (ft)							
Storage Blk Time (%)							
Queuing Penalty (veh)							

Intersection: 6: Maryland Ave & Fleet St

Movement	EB	WB	WB	NB	NB	SB	SB
Directions Served	LTR	L	R	Т	R	L	Т
Maximum Queue (ft)	50	302	90	450	226	34	155
Average Queue (ft)	12	164	38	222	33	9	62
95th Queue (ft)	38	260	70	411	208	29	131
Link Distance (ft)	141	354	354	650			431
Upstream Blk Time (%)		0		0			
Queuing Penalty (veh)		0		0			
Storage Bay Dist (ft)					450	125	
Storage Blk Time (%)				1	0		1
Queuing Penalty (veh)				5	0		0

04/14/2023

Intersection: 7: MD 355 & E Jefferson St

Movement	EB	EB	WB	WB	WB	NB	NB	NB	NB	NB	SB	SB
Directions Served	Т	TR	Т	Т	R	L	L	Т	Т	Т	L	L
Maximum Queue (ft)	462	522	251	258	102	241	300	441	394	287	437	450
Average Queue (ft)	277	320	155	134	18	90	168	270	244	186	431	447
95th Queue (ft)	423	476	233	227	67	193	302	400	357	283	464	465
Link Distance (ft)	880	880	941	941	941			760	760	760		
Upstream Blk Time (%)												
Queuing Penalty (veh)												
Storage Bay Dist (ft)						275	275				425	425
Storage Blk Time (%)						0	0	6			17	72
Queuing Penalty (veh)						0	1	17			47	202

ATTACHMENT A

Intersection: 7: MD 355 & E Jefferson St

Movement	SB	SB	SB
Directions Served	Т	Т	TR
Maximum Queue (ft)	712	648	436
Average Queue (ft)	653	420	256
95th Queue (ft)	809	688	410
Link Distance (ft)	658	658	658
Upstream Blk Time (%)	69	0	
Queuing Penalty (veh)	0	0	
Storage Bay Dist (ft)			
Storage Blk Time (%)	1		
Queuing Penalty (veh)	4		

Network Summary

Network wide Queuing Penalty: 284

HCM Unsignalized Intersection Capacity Analysis 1: Monroe St & E Middle Ln

04/14/2023

	-	\rightarrow	•	←	4	~
Movement	EBT	EBR	WBL	WBT	NBL	NBR
Lane Configurations	∱ Ъ			^		7
Traffic Volume (veh/h)	229	14	0	350	0	42
Future Volume (Veh/h)	229	14	0	350	0	42
Sign Control	Free			Free	Stop	
Grade	0%			0%	0%	
Peak Hour Factor	0.86	0.86	0.86	0.86	0.86	0.86
Hourly flow rate (vph)	266	16	0	407	0	49
Pedestrians	11			1	29	
Lane Width (ft)	12.0			12.0	12.0	
Walking Speed (ft/s)	3.5			3.5	3.5	
Percent Blockage	1			0	3	
Right turn flare (veh)						
Median type	None			None		
Median storage veh)						
Upstream signal (ft)						
pX, platoon unblocked						
vC, conflicting volume			311		518	171
vC1, stage 1 conf vol						
vC2, stage 2 conf vol						
vCu, unblocked vol			311		518	171
tC, single (s)			4.1		6.8	6.9
tC, 2 stage (s)						
tF (s)			2.2		3.5	3.3
p0 queue free %			100		100	94
cM capacity (veh/h)			1212		469	819
	ED 4	ED 0		WD 0		
Direction, Lane # Volume Total	EB 1 177	EB 2 105	WB 1 204	WB 2 204	NB 1 49	
Volume Total Volume Left					49	
	0	0 16	0	0	49	
Volume Right						
cSH	1700	1700	1700	1700	819	
Volume to Capacity	0.10	0.06	0.12	0.12	0.06	
Queue Length 95th (ft)	0	0	0	0	5	
Control Delay (s)	0.0	0.0	0.0	0.0	9.7	
Lane LOS	0.0		0.0		A	
Approach Delay (s)	0.0		0.0		9.7	
Approach LOS					Α	
Intersection Summary						
Average Delay			0.6			
Intersection Capacity Utiliza	ation		21.5%	IC	U Level o	f Service
Analysis Period (min)			15			

Build Shared Use Path AM

Synchro 11 Report

Timing Plan: AM

Page 1

HCM Unsignalized Intersection Capacity Analysis

2: Monroe St & E Montgomery Ave

04/14/2023

	•	_	•	+	ı	1
		•	7	ı	*	•
Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations	W			†	↑	
Sign Control	Stop			Stop	Stop	
Traffic Volume (vph)	0	0	0	0	0	0
Future Volume (vph)	0	0	0	0	0	0
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Hourly flow rate (vph)	0	0	0	0	0	0
Direction, Lane #	EB 1	NB 1	SB 1			
Volume Total (vph)	0	0	0			
Volume Left (vph)	0	0	0			
Volume Right (vph)	0	0	0			
Hadj (s)	0.00	0.00	0.00			
Departure Headway (s)	3.9	3.9	3.9			
Degree Utilization, x	0.00	0.00	0.00			
Capacity (veh/h)	917	917	917			
Control Delay (s)	6.9	6.9	6.9			
Approach Delay (s)	0.0	0.0	0.0			
Approach LOS	Α	Α	Α			
Intersection Summary						
Delay			0.0			
Level of Service			Α			
Intersection Capacity Utiliza	ation		0.0%	IC	U Level c	of Service
Analysis Period (min)			15			

Build Shared Use Path AM
Timing Plan: AM
Synchro 11 Report
Page 2

HCM Unsignalized Intersection Capacity Analysis 3: Monroe St & Monroe Pl

04/14/2023

5. MOTIOE SEA MO	Worlde St & Worlde 1 1										0-1/1	7/2020
	٠	→	•	•	←	•	4	†	<i>></i>	/	ļ	4
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		4			4			4	7		4	
Sign Control		Stop			Stop			Stop			Stop	
Traffic Volume (vph)	0	0	0	0	0	0	0	0	0	0	0	0
Future Volume (vph)	0	0	0	0	0	0	0	0	0	0	0	0
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Hourly flow rate (vph)	0	0	0	0	0	0	0	0	0	0	0	0
Direction, Lane #	EB 1	WB 1	NB 1	NB 2	SB 1							
Volume Total (vph)	0	0	0	0	0							
Volume Left (vph)	0	0	0	0	0							
Volume Right (vph)	0	0	0	0	0							
Hadj (s)	0.00	0.00	0.00	0.00	0.00							
Departure Headway (s)	3.9	3.9	4.5	4.5	4.0							
Degree Utilization, x	0.00	0.00	0.00	0.00	0.00							
Capacity (veh/h)	917	917	806	806	900							
Control Delay (s)	6.9	6.9	6.3	6.3	7.0							
Approach Delay (s)	0.0	0.0	0.0		0.0							
Approach LOS	Α	Α	Α		Α							
Intersection Summary												
Delay			0.0									
Level of Service			Α									
Intersection Capacity Utiliza	tion		0.0%	IC	CU Level	of Service			Α			
Analysis Period (min)			15									

Build Shared Use Path AM
Timing Plan: AM
Synchro 11 Report
Page 3

HCM Signalized Intersection Capacity Analysis

4: Monroe St & E Jefferson St

04/14/2023

	۶	→	•	•	←	4	1	†	<u> </u>	\	 	4
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	ň	∱ }		Ť	∱ }		¥	ĵ»		¥	ĵ,	
Traffic Volume (vph)	69	568	64	96	674	56	70	135	71	15	78	41
Future Volume (vph)	69	568	64	96	674	56	70	135	71	15	78	41
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	5.5	5.5		5.5	5.5		6.0	6.0		6.0	6.0	
Lane Util. Factor	1.00	0.95		1.00	0.95		1.00	1.00		1.00	1.00	
Frpb, ped/bikes	1.00	1.00		1.00	1.00		1.00	0.97		1.00	0.97	
Flpb, ped/bikes	1.00	1.00		1.00	1.00		0.93	1.00		0.95	1.00	
Frt	1.00	0.98		1.00	0.99		1.00	0.95		1.00	0.95	
Flt Protected	0.95	1.00		0.95	1.00		0.95	1.00		0.95	1.00	
Satd. Flow (prot)	1591	3123		1589	3140		1479	1546		1517	1537	
Flt Permitted	0.30	1.00		0.34	1.00		0.68	1.00		0.53	1.00	
Satd. Flow (perm)	494	3123		563	3140		1052	1546		850	1537	
Peak-hour factor, PHF	0.94	0.94	0.94	0.94	0.94	0.94	0.94	0.94	0.94	0.94	0.94	0.94
Adj. Flow (vph)	73	604	68	102	717	60	74	144	76	16	83	44
RTOR Reduction (vph)	0	0	0	0	0	0	0	0	0	0	0	0
Lane Group Flow (vph)	73	672	0	102	777	0	74	220	0	16	127	0
Confl. Peds. (#/hr)	8		16	16		8	66		59	59		66
Turn Type	pm+pt	NA		pm+pt	NA		Perm	NA		Perm	NA	
Protected Phases	1	6		5	2			8			4	
Permitted Phases	6			2			8			4		
Actuated Green, G (s)	49.2	43.1		50.4	43.7		23.2	23.2		23.2	23.2	
Effective Green, g (s)	49.2	43.1		50.4	43.7		23.2	23.2		23.2	23.2	
Actuated g/C Ratio	0.55	0.48		0.56	0.49		0.26	0.26		0.26	0.26	
Clearance Time (s)	5.5	5.5		5.5	5.5		6.0	6.0		6.0	6.0	
Vehicle Extension (s)	3.0	3.0		3.0	3.0		3.0	3.0		3.0	3.0	
Lane Grp Cap (vph)	344	1495		391	1524		271	398		219	396	
v/s Ratio Prot	0.01	0.22		c0.02	c0.25			c0.14			0.08	
v/s Ratio Perm	0.10			0.13			0.07			0.02		
v/c Ratio	0.21	0.45		0.26	0.51		0.27	0.55		0.07	0.32	
Uniform Delay, d1	10.0	15.6		9.6	15.8		26.7	28.9		25.3	27.0	
Progression Factor	1.00	1.00		1.00	1.00		0.83	0.84		1.00	1.00	
Incremental Delay, d2	0.3	1.0		0.4	1.2		0.5	1.5		0.1	0.5	
Delay (s)	10.4	16.6		10.0	17.0		22.7	25.9		25.4	27.5	
Level of Service	В	В		Α	В		С	С		С	С	
Approach Delay (s)		15.9			16.2			25.1			27.3	
Approach LOS		В			В			С			С	
Intersection Summary												
HCM 2000 Control Delay			18.1	Н	CM 2000	Level of S	Service		В			
HCM 2000 Volume to Capa	icity ratio		0.50									
Actuated Cycle Length (s)			90.0		um of lost				17.0			
Intersection Capacity Utiliza	ation		64.2%	IC	CU Level o	of Service			С			
Analysis Period (min)			15									
c Critical Lane Group												

Build Shared Use Path AM

Synchro 11 Report
Timing Plan: AM

Page 4

HCM Signalized Intersection Capacity Analysis 5: Monroe St & Fleet St

04/14/2023

J. WOITIOE St & FIE												-1/2020
	•	-	•	•	←	•	1	†	~	-	↓	4
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	ሻ	₽		Ť	₽			4		Ť	₽	
Traffic Volume (vph)	148	314	62	10	275	81	43	69	21	43	43	83
Future Volume (vph)	148	314	62	10	275	81	43	69	21	43	43	83
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	5.0	5.0		5.0	5.0			5.0		5.0	5.0	
Lane Util. Factor	1.00	1.00		1.00	1.00			1.00		1.00	1.00	
Frpb, ped/bikes	1.00	0.99		1.00	0.99			1.00		1.00	0.93	
Flpb, ped/bikes	0.98	1.00		0.98	1.00			0.98		0.99	1.00	
Frt	1.00	0.98		1.00	0.97			0.98		1.00	0.90	
Flt Protected	0.95	1.00		0.95	1.00			0.98		0.95	1.00	
Satd. Flow (prot)	1567	1618		1567	1597			1576		1582	1407	
Flt Permitted	0.41	1.00		0.39	1.00			0.69		0.52	1.00	
Satd. Flow (perm)	676	1618		646	1597			1112		873	1407	
Peak-hour factor, PHF	0.66	0.66	0.66	0.66	0.66	0.66	0.66	0.66	0.66	0.66	0.66	0.66
Adj. Flow (vph)	224	476	94	15	417	123	65	105	32	65	65	126
RTOR Reduction (vph)	0	6	0	0	8	0	0	9	0	0	91	0
Lane Group Flow (vph)	224	564	0	15	532	0	0	193	0	65	100	0
Confl. Peds. (#/hr)	20		19	19		20	40		5	5		40
Turn Type	Perm	NA		Perm	NA		Perm	NA		Perm	NA	
Protected Phases	1 01111	6		1 01111	2		1 01111	8		1 01111	4	
Permitted Phases	6			2	_		8			4	•	
Actuated Green, G (s)	61.9	61.9		61.9	61.9			18.1		18.1	18.1	
Effective Green, g (s)	61.9	61.9		61.9	61.9			18.1		18.1	18.1	
Actuated g/C Ratio	0.69	0.69		0.69	0.69			0.20		0.20	0.20	
Clearance Time (s)	5.0	5.0		5.0	5.0			5.0		5.0	5.0	
Vehicle Extension (s)	3.0	3.0		3.0	3.0			3.0		3.0	3.0	
Lane Grp Cap (vph)	464	1112		444	1098			223		175	282	
v/s Ratio Prot	707	c0.35		777	0.33			220		173	0.07	
v/s Ratio Perm	0.33	00.00		0.02	0.00			c0.17		0.07	0.07	
v/c Ratio	0.48	0.51		0.02	0.48			0.87		0.37	0.35	
Uniform Delay, d1	6.6	6.7		4.5	6.6			34.8		31.0	30.9	
Progression Factor	0.85	0.84		1.00	1.00			1.00		0.98	0.98	
Incremental Delay, d2	3.1	1.4		0.1	1.5			27.8		1.3	0.50	
Delay (s)	8.7	7.1		4.6	8.1			62.6		31.6	30.9	
Level of Service	Α	Α.		4.0 A	Α			02.0 E		C	C	
Approach Delay (s)		7.5			8.0			62.6		U	31.1	
Approach LOS		Α			Α			62.0 E			C	
Intersection Summary												
HCM 2000 Control Delay			17.2	H	CM 2000	Level of S	Service		В			
HCM 2000 Volume to Capa	city ratio		0.59									
Actuated Cycle Length (s)			90.0	Sı	um of lost	time (s)			10.0			
Intersection Capacity Utiliza	ition		85.6%		U Level o				Е			
Analysis Period (min)			15									
c Critical Lane Group												

Build Shared Use Path AM
Timing Plan: AM
Synchro 11 Report
Page 5

HCM Signalized Intersection Capacity Analysis 6: Maryland Ave & Fleet St

04/14/2023

	ၨ	→	•	•	—	4	•	†	~	\		1
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		4		*		7		1	7	ሻ	*	
Traffic Volume (vph)	2	1	1	315	0	101	0	276	451	87	245	0
Future Volume (vph)	2	1	1	315	0	101	0	276	451	87	245	0
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)		4.5		4.5		4.5		4.5	4.5	4.5	4.5	
Lane Util. Factor		1.00		1.00		1.00		1.00	1.00	1.00	1.00	
Frpb, ped/bikes		0.98		1.00		0.97		1.00	0.97	1.00	1.00	
Flpb, ped/bikes		1.00		1.00		1.00		1.00	1.00	1.00	1.00	
Frt		0.97		1.00		0.85		1.00	0.85	1.00	1.00	
Flt Protected		0.97		0.95		1.00		1.00	1.00	0.95	1.00	
Satd. Flow (prot)		1545		1593		1384		1676	1388	1593	1676	
Flt Permitted		0.97		0.95		1.00		1.00	1.00	0.27	1.00	
Satd. Flow (perm)		1545		1593		1384		1676	1388	456	1676	
Peak-hour factor, PHF	0.79	0.79	0.79	0.79	0.79	0.79	0.79	0.79	0.79	0.79	0.79	0.79
Adj. Flow (vph)	3	1	1	399	0	128	0	349	571	110	310	0
RTOR Reduction (vph)	0	1	0	0	0	88	0	0	407	0	0	0
Lane Group Flow (vph)	0	4	0	399	0	40	0	349	164	110	310	0
Confl. Peds. (#/hr)	3		3	3		3	7		2	2		7
Turn Type	Split	NA		Prot		Perm		NA	Perm	pm+pt	NA	
Protected Phases	3	3		4				2		1	6	
Permitted Phases						4			2	6		
Actuated Green, G (s)		1.3		28.0		28.0		25.9	25.9	47.2	47.2	
Effective Green, g (s)		1.3		28.0		28.0		25.9	25.9	47.2	47.2	
Actuated g/C Ratio		0.01		0.31		0.31		0.29	0.29	0.52	0.52	
Clearance Time (s)		4.5		4.5		4.5		4.5	4.5	4.5	4.5	
Vehicle Extension (s)		4.0		2.0		2.0		5.0	5.0	3.0	5.0	
Lane Grp Cap (vph)		22		495		430		482	399	451	878	
v/s Ratio Prot		c0.00		c0.25				c0.21		0.05	c0.18	
v/s Ratio Perm						0.03			0.12	0.08		
v/c Ratio		0.18		0.81		0.09		0.72	0.41	0.24	0.35	
Uniform Delay, d1		43.8		28.5		22.0		28.8	25.9	12.4	12.5	
Progression Factor		1.00		1.04		1.41		1.00	1.00	1.00	1.00	
Incremental Delay, d2		5.4		8.0		0.0		9.1	3.1	1.3	1.1	
Delay (s)		49.2		37.7		31.0		38.0	29.0	13.7	13.6	
Level of Service		D		D		С		D	С	В	В	
Approach Delay (s)		49.2			36.1			32.4			13.6	
Approach LOS		D			D			С			В	
Intersection Summary												
HCM 2000 Control Delay			29.3	H	CM 2000	Level of S	Service		С			
HCM 2000 Volume to Capacity	y ratio		0.67									
Actuated Cycle Length (s)			90.0		um of lost				18.0			
Intersection Capacity Utilizatio	n		58.4%	IC	U Level of	of Service	!		В			
Analysis Period (min)			15									
c Critical Lane Group												

Build Shared Use Path AM

Synchro 11 Report
Timing Plan: AM

Page 6

HCM Signalized Intersection Capacity Analysis 7: MD 355 & E Jefferson St

04/14/2023

	۶	→	•	•	+	•	•	†	~	/	↓	-√
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		ħβ			^	7	1,1	ተተተ		1,4	ተተ _ጉ	
Traffic Volume (vph)	0	307	305	0	683	387	170	525	0	325	1208	49
Future Volume (vph)	0	307	305	0	683	387	170	525	0	325	1208	49
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)		9.0			9.0	9.0	8.0	8.0		9.0	9.0	
Lane Util. Factor		0.95			0.95	1.00	0.97	0.91		0.97	0.91	
Frpb, ped/bikes		1.00			1.00	1.00	1.00	1.00		1.00	1.00	
Flpb, ped/bikes		1.00			1.00	1.00	1.00	1.00		1.00	1.00	
Frt		0.93			1.00	0.85	1.00	1.00		1.00	0.99	
Flt Protected		1.00			1.00	1.00	0.95	1.00		0.95	1.00	
Satd. Flow (prot)		2947			3185	1425	3090	4577		3090	4544	
Flt Permitted		1.00			1.00	1.00	0.95	1.00		0.95	1.00	
Satd. Flow (perm)		2947			3185	1425	3090	4577		3090	4544	
Peak-hour factor, PHF	0.98	0.98	0.98	0.98	0.98	0.98	0.98	0.98	0.98	0.98	0.98	0.98
Adj. Flow (vph)	0	313	311	0	697	395	173	536	0	332	1233	50
RTOR Reduction (vph)	0	120	0	0	0	284	0	0	0	0	3	0
Lane Group Flow (vph)	0	504	0	0	697	111	173	536	0	332	1280	0
Confl. Peds. (#/hr)												10
Turn Type		NA			NA	Perm	Prot	NA		Prot	NA	
Protected Phases		4			8		1	5		6	2	
Permitted Phases						8						
Actuated Green, G (s)		38.0			38.0	38.0	13.0	45.0		41.0	73.0	
Effective Green, g (s)		38.0			38.0	38.0	13.0	45.0		41.0	73.0	
Actuated g/C Ratio		0.25			0.25	0.25	0.09	0.30		0.27	0.49	
Clearance Time (s)		9.0			9.0	9.0	8.0	8.0		9.0	9.0	
Vehicle Extension (s)		5.0			5.0	5.0	7.0	0.2		5.0	0.2	
Lane Grp Cap (vph)		746			806	361	267	1373		844	2211	
v/s Ratio Prot		0.17			c0.22		c0.06	0.12		0.11	c0.28	
v/s Ratio Perm						0.08						
v/c Ratio		0.68			0.86	0.31	0.65	0.39		0.39	0.58	
Uniform Delay, d1		50.4			53.5	45.3	66.3	41.6		44.4	27.5	
Progression Factor		1.00			1.00	1.00	1.00	1.00		1.00	1.00	
Incremental Delay, d2		4.9			11.9	2.2	9.9	0.8		1.4	1.1	
Delay (s)		55.3			65.5	47.5	76.2	42.5		45.8	28.6	
Level of Service		Е			Е	D	Е	D		D	С	
Approach Delay (s)		55.3			59.0			50.7			32.1	
Approach LOS		Е			Е			D			С	
Intersection Summary												
HCM 2000 Control Delay			46.2	H	CM 2000	Level of S	Service		D			_
HCM 2000 Volume to Capacity	ratio		0.67									
Actuated Cycle Length (s)			150.0		um of los				26.0			
Intersection Capacity Utilization			75.2%	IC	U Level	of Service			D			
Analysis Period (min)			15									
c Critical Lane Group												

HCM Unsignalized Intersection Capacity Analysis 1: Monroe St & E Middle Ln

04/14/2023

	→	\rightarrow	•	←	4	~
Movement	EBT	EBR	WBL	WBT	NBL	NBR
Lane Configurations	↑ ↑			^		7
Traffic Volume (veh/h)	435	4	0	322	0	51
Future Volume (Veh/h)	435	4	0	322	0	51
Sign Control	Free			Free	Stop	
Grade	0%			0%	0%	
Peak Hour Factor	0.87	0.87	0.87	0.87	0.87	0.87
Hourly flow rate (vph)	500	5	0	370	0	59
Pedestrians	12			2	38	
Lane Width (ft)	12.0			12.0	12.0	
Walking Speed (ft/s)	3.5			3.5	3.5	
Percent Blockage	1			0	4	
Right turn flare (veh)	•					
Median type	None			None		
Median storage veh)						
Upstream signal (ft)						
pX, platoon unblocked						
vC, conflicting volume			543		738	292
vC1, stage 1 conf vol			3. 3			
vC2, stage 2 conf vol						
vCu, unblocked vol			543		738	292
tC, single (s)			4.1		6.8	6.9
tC, 2 stage (s)					3.0	5.0
tF (s)			2.2		3.5	3.3
p0 queue free %			100		100	91
cM capacity (veh/h)			985		337	677
	FD 4	ED 0		VA/D O		
Direction, Lane #	EB 1	EB 2	WB 1	WB 2	NB 1	
Volume Total	333	172	185	185	59	
Volume Left	0	0	0	0	0	
Volume Right	0	5	0	0	59	
cSH	1700	1700	1700	1700	677	
Volume to Capacity	0.20	0.10	0.11	0.11	0.09	
Queue Length 95th (ft)	0	0	0	0	7	
Control Delay (s)	0.0	0.0	0.0	0.0	10.8	
Lane LOS					В	
Approach Delay (s)	0.0		0.0		10.8	
Approach LOS					В	
Intersection Summary						
Average Delay			0.7			
Intersection Capacity Utiliz	ation		24.5%	IC	U Level o	f Service
Analysis Period (min)			15			22
raidiyolo i cilou (iliili)			10			

HCM Unsignalized Intersection Capacity Analysis

2: Monroe St & E Montgomery Ave

04/14/2023

				_		,
	•	*	1	Ť	¥	*
Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations	W			†	†	
Sign Control	Stop			Stop	Stop	
Traffic Volume (vph)	0	0	0	0	0	0
Future Volume (vph)	0	0	0	0	0	0
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Hourly flow rate (vph)	0	0	0	0	0	0
Direction, Lane #	EB 1	NB 1	SB 1			
Volume Total (vph)	0	0	0			
Volume Left (vph)	0	0	0			
Volume Right (vph)	0	0	0			
Hadj (s)	0.00	0.00	0.00			
Departure Headway (s)	3.9	3.9	3.9			
Degree Utilization, x	0.00	0.00	0.00			
Capacity (veh/h)	917	917	917			
Control Delay (s)	6.9	6.9	6.9			
Approach Delay (s)	0.0	0.0	0.0			
Approach LOS	Α	Α	Α			
Intersection Summary						
Delay			0.0			
Level of Service			Α			
Intersection Capacity Utiliza	ation		0.0%	IC	U Level c	of Service
Analysis Period (min)			15			

HCM Unsignalized Intersection Capacity Analysis 3: Monroe St & Monroe Pl

04/14/2023

3. MOTIOE St & MO	IIIOE FI										U 4 / I	4/2023
	•	→	•	•	←	•	•	†	<i>></i>	>	ţ	4
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		↔			4			4	7		₩.	
Sign Control		Stop			Stop			Stop			Stop	
Traffic Volume (vph)	0	0	0	0	0	0	0	0	0	0	0	0
Future Volume (vph)	0	0	0	0	0	0	0	0	0	0	0	0
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Hourly flow rate (vph)	0	0	0	0	0	0	0	0	0	0	0	0
Direction, Lane #	EB 1	WB 1	NB 1	NB 2	SB 1							
Volume Total (vph)	0	0	0	0	0							
Volume Left (vph)	0	0	0	0	0							
Volume Right (vph)	0	0	0	0	0							
Hadj (s)	0.00	0.00	0.00	0.00	0.00							
Departure Headway (s)	3.9	3.9	4.5	4.5	4.0							
Degree Utilization, x	0.00	0.00	0.00	0.00	0.00							
Capacity (veh/h)	917	917	806	806	900							
Control Delay (s)	6.9	6.9	6.3	6.3	7.0							
Approach Delay (s)	0.0	0.0	0.0		0.0							
Approach LOS	Α	Α	Α		Α							
Intersection Summary												
Delay			0.0									
Level of Service			Α									
Intersection Capacity Utiliza	ition		0.0%	IC	U Level o	of Service			Α			
Analysis Period (min)			15									

HCM Signalized Intersection Capacity Analysis

4: Monroe St & E Jefferson St

04/14/2023

	۶	→	•	•	—	•	•	†	<i>></i>	/	↓	√
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	ň	↑ ↑		, J	∱ 1≽		¥	ĵ.		*	£	
Traffic Volume (vph)	47	744	37	53	652	30	65	106	183	62	97	96
Future Volume (vph)	47	744	37	53	652	30	65	106	183	62	97	96
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	5.5	5.5		5.5	5.5		6.0	6.0		6.0	6.0	
Lane Util. Factor	1.00	0.95		1.00	0.95		1.00	1.00		1.00	1.00	
Frpb, ped/bikes	1.00	1.00		1.00	1.00		1.00	0.96		1.00	0.95	
Flpb, ped/bikes	1.00	1.00		1.00	1.00		0.93	1.00		0.97	1.00	
Frt	1.00	0.99		1.00	0.99		1.00	0.90		1.00	0.93	
Flt Protected	0.95	1.00		0.95	1.00		0.95	1.00		0.95	1.00	
Satd. Flow (prot)	1591	3156		1590	3159		1482	1451		1543	1467	
Flt Permitted	0.32	1.00		0.25	1.00		0.57	1.00		0.40	1.00	
Satd. Flow (perm)	532	3156		411	3159		881	1451		645	1467	
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	51	809	40	58	709	33	71	115	199	67	105	104
RTOR Reduction (vph)	0	0	0	0	0	0	0	0	0	0	0	0
Lane Group Flow (vph)	51	849	0	58	742	0	71	314	0	67	209	0
Confl. Peds. (#/hr)	8		19	19		8	77		49	49		77
Turn Type	pm+pt	NA		pm+pt	NA		Perm	NA		Perm	NA	
Protected Phases	1	6		5	2			8			4	
Permitted Phases	6			2			8			4		
Actuated Green, G (s)	46.4	42.5		49.0	43.8		25.3	25.3		25.3	25.3	
Effective Green, g (s)	46.4	42.5		49.0	43.8		25.3	25.3		25.3	25.3	
Actuated g/C Ratio	0.52	0.47		0.54	0.49		0.28	0.28		0.28	0.28	
Clearance Time (s)	5.5	5.5		5.5	5.5		6.0	6.0		6.0	6.0	
Vehicle Extension (s)	3.0	3.0		3.0	3.0		3.0	3.0		3.0	3.0	
Lane Grp Cap (vph)	320	1490		291	1537		247	407		181	412	
v/s Ratio Prot	0.01	c0.27		c0.01	0.23			c0.22			0.14	
v/s Ratio Perm	0.08			0.10			0.08			0.10		
v/c Ratio	0.16	0.57		0.20	0.48		0.29	0.77		0.37	0.51	
Uniform Delay, d1	11.1	17.1		10.5	15.5		25.3	29.7		26.0	27.1	
Progression Factor	1.00	1.00		1.44	1.79		0.82	0.89		1.00	1.00	
Incremental Delay, d2	0.2	1.6		0.3	1.0		0.6	8.2		1.3	1.0	
Delay (s)	11.4	18.7		15.4	28.8		21.3	34.6		27.2	28.1	
Level of Service	В	В		В	С		С	С		С	С	
Approach Delay (s)		18.3			27.8			32.1			27.9	
Approach LOS		В			С			С			С	
Intersection Summary												
HCM 2000 Control Delay			24.9	Н	CM 2000	Level of S	Service		С			
HCM 2000 Volume to Capa	acity ratio		0.61									
Actuated Cycle Length (s)			90.0	S	um of lost	time (s)			17.0			
Intersection Capacity Utiliza	ation		79.5%			of Service			D			
Analysis Period (min)			15									
c Critical Lane Group												

Build Shared Use Path PM
Synchro 11 Report
Timing Plan: PM
Page 4

HCM Signalized Intersection Capacity Analysis 5: Monroe St & Fleet St

04/14/2023

	٠	→	*	•	←	4	4	†	~	\		1
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	7	ĵ.		7	ĵ»			4		7	ĵ.	
Traffic Volume (vph)	157	189	83	13	180	44	11	66	7	9	73	134
Future Volume (vph)	157	189	83	13	180	44	11	66	7	9	73	134
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	5.0	5.0		5.0	5.0			5.0		5.0	5.0	
Lane Util. Factor	1.00	1.00		1.00	1.00			1.00		1.00	1.00	
Frpb, ped/bikes	1.00	0.98		1.00	0.99			0.99		1.00	0.98	
Flpb, ped/bikes	0.99	1.00		0.97	1.00			1.00		0.97	1.00	
Frt	1.00	0.95		1.00	0.97			0.99		1.00	0.90	
Flt Protected	0.95	1.00		0.95	1.00			0.99		0.95	1.00	
Satd. Flow (prot)	1576	1564		1553	1615			1637		1545	1480	
Flt Permitted	0.51	1.00		0.46	1.00			0.74		0.62	1.00	
Satd. Flow (perm)	851	1564		747	1615			1222		1008	1480	
Peak-hour factor, PHF	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60
Adj. Flow (vph)	262	315	138	22	300	73	18	110	12	15	122	223
RTOR Reduction (vph)	0	12	0	0	6	0	0	5	0	0	93	0
Lane Group Flow (vph)	262	441	0	22	367	0	0	135	0	15	252	0
Confl. Peds. (#/hr)	9		23	23		9	7		19	19		7
Turn Type	Perm	NA		Perm	NA		Perm	NA		Perm	NA	
Protected Phases		6			2			8			4	
Permitted Phases	6			2			8			4		
Actuated Green, G (s)	59.5	59.5		59.5	59.5			20.5		20.5	20.5	
Effective Green, g (s)	59.5	59.5		59.5	59.5			20.5		20.5	20.5	
Actuated g/C Ratio	0.66	0.66		0.66	0.66			0.23		0.23	0.23	
Clearance Time (s)	5.0	5.0		5.0	5.0			5.0		5.0	5.0	
Vehicle Extension (s)	3.0	3.0		3.0	3.0			3.0		3.0	3.0	
Lane Grp Cap (vph)	562	1033		493	1067			278		229	337	
v/s Ratio Prot		0.28			0.23						c0.17	
v/s Ratio Perm	c0.31			0.03				0.11		0.01		
v/c Ratio	0.47	0.43		0.04	0.34			0.49		0.07	0.75	
Uniform Delay, d1	7.5	7.2		5.3	6.7			30.2		27.2	32.4	
Progression Factor	0.90	0.88		1.00	1.00			1.00		0.91	0.86	
Incremental Delay, d2	2.1	1.0		0.2	0.9			1.3		0.1	8.7	
Delay (s)	8.9	7.3		5.5	7.6			31.5		25.0	36.4	
Level of Service	Α	A		Α	Α			С		С	D	
Approach Delay (s)		7.9			7.5			31.5			35.9	
Approach LOS		Α			Α			С			D	
Intersection Summary												
HCM 2000 Control Delay			16.1	H	CM 2000	Level of S	Service		В			
HCM 2000 Volume to Capa	city ratio		0.54									
Actuated Cycle Length (s)			90.0		um of lost				10.0			
Intersection Capacity Utiliza	ation		70.3%	IC	U Level o	of Service			С			
Analysis Period (min)			15									
c Critical Lane Group												

HCM Signalized Intersection Capacity Analysis 6: Maryland Ave & Fleet St

04/14/2023

o. Marylana / Wo a 1	•		_	_	-	•	•	†	/ ►	<u>_</u>	1	1
Movement	EBL	EBT	EBR	₩BL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	LDL	4	LDIN	YVDL	VVDI	VVDI\ ₹	INDL		TION 7	JDL	JUI	JUIN
Traffic Volume (vph)	12	4	2	302	0	80	0	332	415	21	308	0
Future Volume (vph)	12	4	2	302	0	80	0	332	415	21	308	0
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	1300	4.5	1300	4.5	1500	4.5	1300	4.5	4.5	4.5	4.5	1300
Lane Util. Factor		1.00		1.00		1.00		1.00	1.00	1.00	1.00	
Frpb, ped/bikes		0.99		1.00		0.97		1.00	0.96	1.00	1.00	
Flpb, ped/bikes		1.00		1.00		1.00		1.00	1.00	1.00	1.00	
Frt		0.98		1.00		0.85		1.00	0.85	1.00	1.00	
Flt Protected		0.97		0.95		1.00		1.00	1.00	0.95	1.00	
Satd. Flow (prot)		1579		1593		1376		1676	1363	1593	1676	
Flt Permitted		0.97		0.95		1.00		1.00	1.00	0.18	1.00	
Satd. Flow (perm)		1579		1593		1376		1676	1363	301	1676	
Peak-hour factor, PHF	0.71	0.71	0.71	0.71	0.71	0.71	0.71	0.71	0.71	0.71	0.71	0.71
Adj. Flow (vph)	17	6	3	425	0	113	0	468	585	30	434	0
RTOR Reduction (vph)	0	3	0	0	0	77	0	0	469	0	0	0
Lane Group Flow (vph)	0	23	0	425	0	36	0	468	116	30	434	0
Confl. Peds. (#/hr)	5		5	5		5	5		8	8		5
Turn Type	Split	NA		Prot		Perm		NA	Perm	pm+pt	NA	
Protected Phases	3	3		4				2		1	6	
Permitted Phases	-	-		-		4		_	2	6		
Actuated Green, G (s)		2.6		28.8		28.8		17.8	17.8	45.1	45.1	
Effective Green, g (s)		2.6		28.8		28.8		17.8	17.8	45.1	45.1	
Actuated g/C Ratio		0.03		0.32		0.32		0.20	0.20	0.50	0.50	
Clearance Time (s)		4.5		4.5		4.5		4.5	4.5	4.5	4.5	
Vehicle Extension (s)		4.0		2.0		2.0		5.0	5.0	3.0	5.0	
Lane Grp Cap (vph)		45		509		440		331	269	478	839	
v/s Ratio Prot		c0.01		c0.27				c0.28		0.02	c0.26	
v/s Ratio Perm						0.03			0.08	0.02		
v/c Ratio		0.51		0.83		0.08		1.41	0.43	0.06	0.52	
Uniform Delay, d1		43.1		28.4		21.4		36.1	31.7	13.3	15.1	
Progression Factor		1.00		1.16		3.23		1.00	1.00	1.00	1.00	
Incremental Delay, d2		12.5		10.1		0.0		203.3	5.0	0.3	2.3	
Delay (s)		55.6		43.0		69.2		239.4	36.6	13.6	17.4	
Level of Service		Е		D		Ε		F	D	В	В	
Approach Delay (s)		55.6			48.5			126.7			17.1	
Approach LOS		Ε			D			F			В	
Intersection Summary												
HCM 2000 Control Delay			81.2	H	CM 2000	Level of S	Service		F			
HCM 2000 Volume to Capaci	ty ratio		0.88									
Actuated Cycle Length (s)			90.0		um of lost				18.0			
Intersection Capacity Utilization	on		51.8%	IC	U Level of	of Service			Α			
Analysis Period (min)			15									
c Critical Lane Group												

HCM Signalized Intersection Capacity Analysis

7: MD 355 & E Jefferson St

04/14/2023

7: MB 000 & E 0011010	<u> </u>										• ., .	
	۶	→	•	•	←	•	4	†	/	-	↓	4
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		∱ }			^	7	1,1	ተተተ		44	† †	
Traffic Volume (vph)	0	591	238	0	443	378	267	1003	0	535	847	61
Future Volume (vph)	0	591	238	0	443	378	267	1003	0	535	847	61
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)		9.0			9.0	9.0	8.0	8.0		9.0	9.0	
Lane Util. Factor		0.95			0.95	1.00	0.97	0.91		0.97	0.91	
Frpb, ped/bikes		1.00			1.00	1.00	1.00	1.00		1.00	1.00	
Flpb, ped/bikes		1.00			1.00	1.00	1.00	1.00		1.00	1.00	
Frt		0.96			1.00	0.85	1.00	1.00		1.00	0.99	
Flt Protected		1.00			1.00	1.00	0.95	1.00		0.95	1.00	
Satd. Flow (prot)		3048			3185	1425	3090	4577		3090	4523	
Flt Permitted		1.00			1.00	1.00	0.95	1.00		0.95	1.00	
Satd. Flow (perm)		3048			3185	1425	3090	4577		3090	4523	
Peak-hour factor, PHF	0.98	0.98	0.98	0.98	0.98	0.98	0.98	0.98	0.98	0.98	0.98	0.98
Adj. Flow (vph)	0	603	243	0	452	386	272	1023	0	546	864	62
RTOR Reduction (vph)	0	24	0	0	0	244	0	0	0	0	4	0
Lane Group Flow (vph)	0	822	0	0	452	142	272	1023	0	546	922	0
Confl. Peds. (#/hr)												5
Turn Type		NA			NA	Perm	Prot	NA		Prot	NA	
Protected Phases		4			8		1	5		6	2	
Permitted Phases						8						
Actuated Green, G (s)		51.0			51.0	51.0	25.0	76.0		27.0	78.0	
Effective Green, g (s)		51.0			51.0	51.0	25.0	76.0		27.0	78.0	
Actuated g/C Ratio		0.28			0.28	0.28	0.14	0.42		0.15	0.43	
Clearance Time (s)		9.0			9.0	9.0	8.0	8.0		9.0	9.0	
Vehicle Extension (s)		5.0			5.0	5.0	7.0	0.2		5.0	0.2	
Lane Grp Cap (vph)		863			902	403	429	1932		463	1959	,
v/s Ratio Prot		c0.27			0.14		0.09	c0.22		c0.18	0.20	
v/s Ratio Perm						0.10						
v/c Ratio		0.95			0.50	0.35	0.63	0.53		1.18	0.47	
Uniform Delay, d1		63.3			53.9	51.4	73.2	38.7		76.5	36.3	
Progression Factor		0.94			1.00	1.00	1.00	1.00		1.00	1.00	
Incremental Delay, d2		18.5			2.0	2.4	5.9	1.0		101.1	0.8	
Delay (s)		78.0			55.9	53.8	79.0	39.7		177.6	37.1	
Level of Service		Е			Е	D	Е	D		F	D	
Approach Delay (s)		78.0			54.9			48.0			89.2	
Approach LOS		Е			D			D			F	
Intersection Summary												
HCM 2000 Control Delay			68.6	Н	CM 2000	Level of S	Service		Е			
HCM 2000 Volume to Capacity	ratio		0.78									
Actuated Cycle Length (s)			180.0	Sı	um of lost	t time (s)			26.0			
Intersection Capacity Utilization			86.8%			of Service			Е			
Analysis Period (min)			15									
c Critical Lane Group												

Synchro 11 Report Page 7 Build Shared Use Path PM Timing Plan: PM

04/14/2023

Intersection: 1: Monroe St & E Middle Ln

Movement	EB	EB	WB	WB	NB
Directions Served	Т	TR	Т	Т	R
Maximum Queue (ft)	33	19	35	12	57
Average Queue (ft)	2	1	3	1	24
95th Queue (ft)	16	9	17	8	48
Link Distance (ft)	640	640	187	187	
Upstream Blk Time (%)					
Queuing Penalty (veh)					
Storage Bay Dist (ft)					
Storage Blk Time (%)					
Queuing Penalty (veh)					

Intersection: 2: Monroe St & E Montgomery Ave

Movement Directions Served Maximum Queue (ft) Average Queue (ft) 95th Queue (ft) Link Distance (ft) Upstream Blk Time (%) Queuing Penalty (veh) Storage Bay Dist (ft) Storage Blk Time (%) Queuing Penalty (veh)

Intersection: 3: Monroe St & Monroe PI

Novement
Directions Served
Maximum Queue (ft)
verage Queue (ft)
5th Queue (ft)
ink Distance (ft)
Ipstream Blk Time (%)
Queuing Penalty (veh)
Storage Bay Dist (ft)
Storage Blk Time (%)
Queuing Penalty (veh)

04/14/2023

Intersection: 4: Monroe St & E Jefferson St

Movement	EB	EB	EB	WB	WB	WB	NB	NB	SB	SB	
Directions Served	L	Т	TR	L	Т	TR	L	TR	L	TR	
Maximum Queue (ft)	66	194	231	149	391	495	112	190	56	165	
Average Queue (ft)	30	83	115	70	157	185	47	100	16	69	
95th Queue (ft)	63	149	192	152	337	384	87	171	46	130	
Link Distance (ft)		546	546		886	886		433			
Upstream Blk Time (%)						0					
Queuing Penalty (veh)						0					
Storage Bay Dist (ft)	250			125			225		150		
Storage Blk Time (%)				0	9			0		1	
Queuing Penalty (veh)				1	9			0		0	

Intersection: 5: Monroe St & Fleet St

Movement	EB	EB	WB	WB	NB	SB	SB
Directions Served	L	TR	L	TR	LTR	L	TR
Maximum Queue (ft)	125	206	33	191	151	85	156
Average Queue (ft)	61	93	7	81	75	30	56
95th Queue (ft)	116	174	27	149	128	68	109
Link Distance (ft)		361	580	580	528		433
Upstream Blk Time (%)							
Queuing Penalty (veh)							
Storage Bay Dist (ft)	100					175	
Storage Blk Time (%)	2	5					0
Queuing Penalty (veh)	9	7					0

Intersection: 6: Maryland Ave & Fleet St

Movement	EB	WB	WB	NB	NB	SB	SB
Directions Served	LTR	L	R	Т	R	L	Т
Maximum Queue (ft)	29	249	280	215	122	87	145
Average Queue (ft)	3	162	54	111	24	29	50
95th Queue (ft)	18	256	164	192	74	64	107
Link Distance (ft)	141		361	646			432
Upstream Blk Time (%)			0				
Queuing Penalty (veh)			1				
Storage Bay Dist (ft)		225			450	125	
Storage Blk Time (%)		3	0				0
Queuing Penalty (veh)		3	0				0

04/14/2023

Intersection: 7: MD 355 & E Jefferson St

Movement	EB	EB	WB	WB	WB	NB	NB	NB	NB	NB	SB	SB
Directions Served	T	TR	Т	Т	R	L	L	Т	Т	Т	L	L
Maximum Queue (ft)	218	284	393	370	61	132	176	263	221	161	224	257
Average Queue (ft)	108	120	261	231	4	45	90	150	135	73	100	156
95th Queue (ft)	179	232	367	342	27	124	158	219	196	163	213	236
Link Distance (ft)	886	886	941	941	941			760	760	760		
Upstream Blk Time (%)												
Queuing Penalty (veh)												
Storage Bay Dist (ft)						275	275				425	425
Storage Blk Time (%)								0				
Queuing Penalty (veh)								0				

Intersection: 7: MD 355 & E Jefferson St

Movement	SB	SB	SB
Directions Served	Т	Т	TR
Maximum Queue (ft)	352	328	289
Average Queue (ft)	248	233	172
95th Queue (ft)	339	312	263
Link Distance (ft)	658	658	658
Upstream Blk Time (%)			
Queuing Penalty (veh)			
Storage Bay Dist (ft)			
Storage Blk Time (%)			
Queuing Penalty (veh)			

Network Summary

Network wide Queuing Penalty: 30

Queuing Penalty (veh)

04/14/2023

Intersection: 1: Monroe St & E Middle Ln

Movement	EB	EB	WB	WB	NB
Directions Served	Т	TR	Т	Т	R
Maximum Queue (ft)	40	23	62	18	49
Average Queue (ft)	5	1	7	1	28
95th Queue (ft)	24	12	34	11	50
Link Distance (ft)	640	640	187	187	
Upstream Blk Time (%)					
Queuing Penalty (veh)					
Storage Bay Dist (ft)					
Storage Blk Time (%)					

Intersection: 2: Monroe St & E Montgomery Ave

Movement
Directions Served
Maximum Queue (ft)
Average Queue (ft)
95th Queue (ft)
Link Distance (ft)
Upstream Blk Time (%)
Queuing Penalty (veh)
Storage Bay Dist (ft)
Storage Blk Time (%)
Queuing Penalty (veh)
• , , ,

Intersection: 3: Monroe St & Monroe PI

ement
ctions Served
imum Queue (ft)
rage Queue (ft)
Queue (ft)
Distance (ft)
tream Blk Time (%)
uing Penalty (veh)
age Bay Dist (ft)
age Blk Time (%)
uing Penalty (veh)

04/14/2023

Intersection: 4: Monroe St & E Jefferson St

Movement	EB	EB	EB	WB	WB	WB	NB	NB	SB	SB	
Directions Served	L	Т	TR	L	Т	TR	L	TR	L	TR	
Maximum Queue (ft)	57	230	237	149	344	349	250	326	171	237	
Average Queue (ft)	27	138	127	58	203	228	66	180	56	109	
95th Queue (ft)	55	211	206	150	328	327	170	297	131	195	
Link Distance (ft)		546	546		886	886		433			
Upstream Blk Time (%)											
Queuing Penalty (veh)											
Storage Bay Dist (ft)	250			125			225		150		
Storage Blk Time (%)		0		0	13			9	0	5	
Queuing Penalty (veh)		0		0	7			6	1	3	

Intersection: 5: Monroe St & Fleet St

Movement	EB	EB	WB	WB	NB	SB	SB
Directions Served	L	TR	L	TR	LTR	L	TR
Maximum Queue (ft)	120	163	33	120	114	29	198
Average Queue (ft)	54	59	5	46	50	6	93
95th Queue (ft)	100	119	24	100	97	24	170
Link Distance (ft)		361	580	580	528		433
Upstream Blk Time (%)							
Queuing Penalty (veh)							
Storage Bay Dist (ft)	100					175	
Storage Blk Time (%)	1	1					1
Queuing Penalty (veh)	4	2					0

Intersection: 6: Maryland Ave & Fleet St

Movement	EB	WB	WB	NB	NB	SB	SB
Directions Served	LTR	L	R	Т	R	L	Т
Maximum Queue (ft)	54	245	206	359	50	50	166
Average Queue (ft)	13	173	42	183	5	11	67
95th Queue (ft)	37	253	122	306	26	35	135
Link Distance (ft)	141		361	646			432
Upstream Blk Time (%)							
Queuing Penalty (veh)							
Storage Bay Dist (ft)		225			450	125	
Storage Blk Time (%)		3		0			1
Queuing Penalty (veh)		3		0			0

04/14/2023

Intersection: 7: MD 355 & E Jefferson St

Movement	EB	EB	WB	WB	WB	NB	NB	NB	NB	NB	SB	SB
Directions Served	T	TR	Т	Т	R	L	L	Т	Т	Т	L	L
Maximum Queue (ft)	453	498	268	238	114	188	300	396	369	295	437	450
Average Queue (ft)	286	330	163	135	15	86	157	250	223	172	434	448
95th Queue (ft)	430	469	248	224	62	185	278	362	321	272	451	454
Link Distance (ft)	886	886	941	941	941			760	760	760		
Upstream Blk Time (%)												
Queuing Penalty (veh)												
Storage Bay Dist (ft)						275	275				425	425
Storage Blk Time (%)							0	4			11	73
Queuing Penalty (veh)							0	10			31	205

Intersection: 7: MD 355 & E Jefferson St

Movement	SB	SB	SB
Directions Served	Т	Т	TR
Maximum Queue (ft)	701	655	458
Average Queue (ft)	665	444	267
95th Queue (ft)	768	719	410
Link Distance (ft)	658	658	658
Upstream Blk Time (%)	71	0	
Queuing Penalty (veh)	0	0	
Storage Bay Dist (ft)			
Storage Blk Time (%)	2		
Queuing Penalty (veh)	9		

Network Summary

Network wide Queuing Penalty: 281

HCM Unsignalized Intersection Capacity Analysis 1: Monroe St & E Middle Ln

	→	•	•	←	4	~
Movement	EBT	EBR	WBL	WBT	NBL	NBR
Lane Configurations	↑ Ъ			^		7
Traffic Volume (veh/h)	229	14	0	350	0	42
Future Volume (Veh/h)	229	14	0	350	0	42
Sign Control	Free			Free	Stop	
Grade	0%			0%	0%	
Peak Hour Factor	0.86	0.86	0.86	0.86	0.86	0.86
Hourly flow rate (vph)	266	16	0	407	0	49
Pedestrians	11			1	29	
Lane Width (ft)	12.0			12.0	12.0	
Walking Speed (ft/s)	3.5			3.5	3.5	
Percent Blockage	1			0	3	
Right turn flare (veh)					-	
Median type	None			None		
Median storage veh)				3.1.0		
Upstream signal (ft)						
pX, platoon unblocked						
vC, conflicting volume			311		518	171
vC1, stage 1 conf vol						
vC2, stage 2 conf vol						
vCu, unblocked vol			311		518	171
tC, single (s)			4.1		6.8	6.9
tC, 2 stage (s)						
tF (s)			2.2		3.5	3.3
p0 queue free %			100		100	94
cM capacity (veh/h)			1212		469	819
	EB 1	EB 2		WB 2	NB 1	
Direction, Lane # Volume Total	177	105	WB 1 204	204	49	
Volume Left	0	0	204	0	0	
Volume Right	0	16	0	0	49	
cSH	1700	1700	1700	1700	819	
Volume to Capacity	0.10	0.06	0.12	0.12	0.06	
	0.10	0.00	0.12	0.12	5	
Queue Length 95th (ft)	0.0	0.0	0.0		9.7	
Control Delay (s) Lane LOS	0.0	0.0	0.0	0.0		
	0.0		0.0		A	
Approach LOS	0.0		0.0		9.7 A	
Approach LOS					A	
Intersection Summary						
Average Delay			0.6			
Intersection Capacity Utiliza	ation		21.5%	IC	U Level c	of Service
Analysis Period (min)			15			

HCM Unsignalized Intersection Capacity Analysis

2: Monroe St & E Montgomery Ave

	•	/	•	†	1	4
Mayamant	EDI	▼	NDL	NDT	CDT	CDD
Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations	W			↑	↑	
Sign Control	Stop			Stop	Stop	
Traffic Volume (vph)	0	0	0	0	0	0
Future Volume (vph)	0	0	0	0	0	0
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Hourly flow rate (vph)	0	0	0	0	0	0
Direction, Lane #	EB 1	NB 1	SB 1			
Volume Total (vph)	0	0	0			
Volume Left (vph)	0	0	0			
Volume Right (vph)	0	0	0			
Hadj (s)	0.00	0.00	0.00			
Departure Headway (s)	3.9	3.9	3.9			
Degree Utilization, x	0.00	0.00	0.00			
Capacity (veh/h)	917	917	917			
Control Delay (s)	6.9	6.9	6.9			
Approach Delay (s)	0.0	0.0	0.0			
Approach LOS	А	Α	Α			
Intersection Summary						
Delay			0.0			
Level of Service			Α			
Intersection Capacity Utiliz	zation		0.0%	IC	U Level c	f Service
Analysis Period (min)			15			

HCM Unsignalized Intersection Capacity Analysis 3: Monroe St & Monroe Pl

3. MOTITOE ST & MO											0-1/1	4/2023
	•	→	•	•	←	•	4	†	/	>	ţ	1
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		₩			4			ર્ન	7		€	
Sign Control		Stop			Stop			Stop			Stop	
Traffic Volume (vph)	0	0	0	0	0	0	0	0	0	0	0	0
Future Volume (vph)	0	0	0	0	0	0	0	0	0	0	0	0
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Hourly flow rate (vph)	0	0	0	0	0	0	0	0	0	0	0	0
Direction, Lane #	EB 1	WB 1	NB 1	NB 2	SB 1							
Volume Total (vph)	0	0	0	0	0							
Volume Left (vph)	0	0	0	0	0							
Volume Right (vph)	0	0	0	0	0							
Hadj (s)	0.00	0.00	0.00	0.00	0.00							
Departure Headway (s)	3.9	3.9	4.5	4.5	4.0							
Degree Utilization, x	0.00	0.00	0.00	0.00	0.00							
Capacity (veh/h)	917	917	806	806	900							
Control Delay (s)	6.9	6.9	6.3	6.3	7.0							
Approach Delay (s)	0.0	0.0	0.0		0.0							
Approach LOS	Α	Α	Α		Α							
Intersection Summary												
Delay			0.0									
Level of Service			Α									
Intersection Capacity Utiliza	ation		0.0%	IC	U Level o	of Service			Α			
Analysis Period (min)			15									

HCM Signalized Intersection Capacity Analysis

4: Monroe St & E Jefferson St

	٠	→	•	•	←	4	•	†	<u> </u>	\	+	4
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	*	↑ ↑		*	↑ ↑		7	1>		7	1>	
Traffic Volume (vph)	69	568	64	96	674	56	70	135	71	15	78	41
Future Volume (vph)	69	568	64	96	674	56	70	135	71	15	78	41
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	5.5	5.5		5.5	5.5		6.0	6.0		6.0	6.0	
Lane Util. Factor	1.00	0.95		1.00	0.95		1.00	1.00		1.00	1.00	
Frpb, ped/bikes	1.00	1.00		1.00	1.00		1.00	0.96		1.00	0.96	
Flpb, ped/bikes	1.00	1.00		1.00	1.00		0.90	1.00		0.93	1.00	
Frt	1.00	0.98		1.00	0.99		1.00	0.95		1.00	0.95	
Flt Protected	0.95	1.00		0.95	1.00		0.95	1.00		0.95	1.00	
Satd. Flow (prot)	1592	3123		1589	3140		1437	1527		1488	1520	
Flt Permitted	0.23	1.00		0.29	1.00		0.68	1.00		0.44	1.00	
Satd. Flow (perm)	391	3123		490	3140		1022	1527		693	1520	
Peak-hour factor, PHF	0.94	0.94	0.94	0.94	0.94	0.94	0.94	0.94	0.94	0.94	0.94	0.94
Adj. Flow (vph)	73	604	68	102	717	60	74	144	76	16	83	44
RTOR Reduction (vph)	0	0	0	0	0	0	0	0	0	0	0	0
Lane Group Flow (vph)	73	672	0	102	777	0	74	220	0	16	127	0
Confl. Peds. (#/hr)	8		16	16		8	66		59	59		66
Turn Type	pm+pt	NA		pm+pt	NA		Perm	NA		Perm	NA	
Protected Phases	1	6		5	2			8			4	
Permitted Phases	6			2			8			4		
Actuated Green, G (s)	36.7	32.7		36.7	32.7		15.3	15.3		15.3	15.3	
Effective Green, g (s)	36.7	32.7		36.7	32.7		15.3	15.3		15.3	15.3	
Actuated g/C Ratio	0.41	0.36		0.41	0.36		0.17	0.17		0.17	0.17	
Clearance Time (s)	5.5	5.5		5.5	5.5		6.0	6.0		6.0	6.0	
Vehicle Extension (s)	3.0	3.0		3.0	3.0		3.0	3.0		3.0	3.0	
Lane Grp Cap (vph)	212	1134		248	1140		173	259		117	258	
v/s Ratio Prot	0.02	0.22		c0.02	c0.25			c0.14			0.08	
v/s Ratio Perm	0.12			0.15			0.07			0.02		
v/c Ratio	0.34	0.59		0.41	0.68		0.43	0.85		0.14	0.49	
Uniform Delay, d1	17.4	23.2		17.3	24.2		33.4	36.2		31.7	33.8	
Progression Factor	1.00	1.00		1.00	1.00		0.85	0.88		1.00	1.00	
Incremental Delay, d2	1.0	2.3		1.1	3.3		1.5	19.8		0.5	1.5	
Delay (s)	18.3	25.5		18.5	27.5		30.0	51.8		32.3	35.3	
Level of Service	В	С		В	С		С	D		С	D	
Approach Delay (s)		24.8			26.5			46.3			35.0	
Approach LOS		С			С			D			С	
Intersection Summary												
HCM 2000 Control Delay			29.3	Н	CM 2000	Level of S	Service		С			
HCM 2000 Volume to Capa	city ratio		0.52									
Actuated Cycle Length (s)			90.0		um of lost				19.0			
Intersection Capacity Utiliza	ation		59.3%	IC	CU Level o	of Service			В			
Analysis Period (min)			15									
c Critical Lane Group												

HCM Signalized Intersection Capacity Analysis 5: Monroe St & Fleet St

	•	→	•	•	←	•	4	†	1	>	ļ	4
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBF
Lane Configurations	7	₽		ሻ	₽			- ↔		ሻ	₽	
Traffic Volume (vph)	148	314	62	10	275	81	43	69	21	43	43	83
Future Volume (vph)	148	314	62	10	275	81	43	69	21	43	43	83
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	5.0	5.0		5.0	5.0			5.0		5.0	5.0	
Lane Util. Factor	1.00	1.00		1.00	1.00			1.00		1.00	1.00	
Frpb, ped/bikes	1.00	0.99		1.00	0.99			1.00		1.00	0.93	
Flpb, ped/bikes	0.98	1.00		0.98	1.00			0.98		0.99	1.00	
Frt	1.00	0.98		1.00	0.97			0.98		1.00	0.90	
Flt Protected	0.95	1.00		0.95	1.00			0.98		0.95	1.00	
Satd. Flow (prot)	1567	1618		1567	1597			1576		1582	1407	
Flt Permitted	0.41	1.00		0.39	1.00			0.69		0.52	1.00	
Satd. Flow (perm)	676	1618		646	1597			1112		873	1407	
Peak-hour factor, PHF	0.66	0.66	0.66	0.66	0.66	0.66	0.66	0.66	0.66	0.66	0.66	0.66
Adj. Flow (vph)	224	476	94	15	417	123	65	105	32	65	65	126
RTOR Reduction (vph)	0	6	0	0	8	0	0	9	0	0	91	0
Lane Group Flow (vph)	224	564	0	15	532	0	0	193	0	65	100	0
Confl. Peds. (#/hr)	20		19	19		20	40		5	5		40
Turn Type	Perm	NA		Perm	NA		Perm	NA	-	Perm	NA	
Protected Phases	. 0	6		. 0	2		. 0	8		. 0	4	
Permitted Phases	6	· ·		2	_		8			4	•	
Actuated Green, G (s)	61.9	61.9		61.9	61.9			18.1		18.1	18.1	
Effective Green, g (s)	61.9	61.9		61.9	61.9			18.1		18.1	18.1	
Actuated g/C Ratio	0.69	0.69		0.69	0.69			0.20		0.20	0.20	
Clearance Time (s)	5.0	5.0		5.0	5.0			5.0		5.0	5.0	
Vehicle Extension (s)	3.0	3.0		3.0	3.0			3.0		3.0	3.0	
Lane Grp Cap (vph)	464	1112		444	1098			223		175	282	
v/s Ratio Prot	707	c0.35		7-7-7	0.33			220		170	0.07	
v/s Ratio Perm	0.33	00.00		0.02	0.00			c0.17		0.07	0.07	
v/c Ratio	0.48	0.51		0.02	0.48			0.87		0.37	0.35	
Uniform Delay, d1	6.6	6.7		4.5	6.6			34.8		31.0	30.9	
Progression Factor	0.85	0.84		1.00	1.00			1.00		0.87	0.80	
Incremental Delay, d2	3.1	1.4		0.1	1.5			27.8		1.2	0.7	
Delay (s)	8.7	7.1		4.6	8.1			62.6		28.2	25.5	
Level of Service	Α	A		4.0 A	Α			62.6 E		20.2 C	23.5 C	
Approach Delay (s)		7.5			8.0			62.6			26.2	
Approach LOS		Α			Α			62.0 E			C	
Intersection Summary												
HCM 2000 Control Delay			16.5	H	CM 2000	Level of S	Service		В			
HCM 2000 Volume to Capa	city ratio		0.59									
Actuated Cycle Length (s)	•		90.0	Sı	um of lost	time (s)			10.0			
Intersection Capacity Utiliza	tion		85.6%		U Level o				Е			
Analysis Period (min)			15									
c Critical Lane Group												

HCM Signalized Intersection Capacity Analysis 6: Maryland Ave & Fleet St

o. Maryland Ave & Fr	ʹ	→	`	•	←	4	•	†	<i>></i>	\	Ţ	4
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBF
Lane Configurations		4		*		7			7	*	+	
Traffic Volume (vph)	2	1	1	315	0	101	0	276	451	87	245	(
Future Volume (vph)	2	1	1	315	0	101	0	276	451	87	245	(
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)		4.5		4.5		4.5		4.5	4.5	4.5	4.5	
Lane Util. Factor		1.00		1.00		1.00		1.00	1.00	1.00	1.00	
Frpb, ped/bikes		0.98		1.00		0.97		1.00	0.97	1.00	1.00	
Flpb, ped/bikes		1.00		1.00		1.00		1.00	1.00	1.00	1.00	
Frt		0.97		1.00		0.85		1.00	0.85	1.00	1.00	
FIt Protected		0.97		0.95		1.00		1.00	1.00	0.95	1.00	
Satd. Flow (prot)		1545		1593		1384		1676	1388	1593	1676	
FIt Permitted		0.97		0.95		1.00		1.00	1.00	0.27	1.00	
Satd. Flow (perm)		1545		1593		1384		1676	1388	456	1676	
Peak-hour factor, PHF	0.79	0.79	0.79	0.79	0.79	0.79	0.79	0.79	0.79	0.79	0.79	0.79
Adj. Flow (vph)	3	1	1	399	0	128	0	349	571	110	310	0
RTOR Reduction (vph)	0	1	0	0	0	88	0	0	407	0	0	0
Lane Group Flow (vph)	0	4	0	399	0	40	0	349	164	110	310	0
Confl. Peds. (#/hr)	3		3	3		3	7		2	2		7
Turn Type	Split	NA		Prot		Perm		NA	Perm	pm+pt	NA	
Protected Phases	3	3		4				2		1	6	
Permitted Phases	•	•		•		4		_	2	6		
Actuated Green, G (s)		1.3		28.0		28.0		25.9	25.9	47.2	47.2	
Effective Green, g (s)		1.3		28.0		28.0		25.9	25.9	47.2	47.2	
Actuated g/C Ratio		0.01		0.31		0.31		0.29	0.29	0.52	0.52	
Clearance Time (s)		4.5		4.5		4.5		4.5	4.5	4.5	4.5	
Vehicle Extension (s)		4.0		2.0		2.0		5.0	5.0	3.0	5.0	
Lane Grp Cap (vph)		22		495		430		482	399	451	878	
v/s Ratio Prot		c0.00		c0.25		100		c0.21	000	0.05	c0.18	
v/s Ratio Perm		00.00		00.20		0.03		00.21	0.12	0.08	00.10	
v/c Ratio		0.18		0.81		0.09		0.72	0.41	0.24	0.35	
Uniform Delay, d1		43.8		28.5		22.0		28.8	25.9	12.4	12.5	
Progression Factor		1.00		1.06		1.40		1.00	1.00	1.00	1.00	
Incremental Delay, d2		5.4		8.0		0.0		9.1	3.1	1.3	1.1	
Delay (s)		49.2		38.3		30.9		38.0	29.0	13.7	13.6	
Level of Service		D		D		C		D	C	В	В	
Approach Delay (s)		49.2			36.5			32.4			13.6	
Approach LOS		D			D			C			В	
Intersection Summary												
HCM 2000 Control Delay			29.4	H	CM 2000	Level of S	Service		С			
HCM 2000 Volume to Capacity	ratio		0.67									
Actuated Cycle Length (s)			90.0	Sı	um of lost	time (s)			18.0			
Intersection Capacity Utilization	1		58.4%			of Service			В			
Analysis Period (min)			15									
Critical Lane Group												

HCM Signalized Intersection Capacity Analysis 7: MD 355 & E Jefferson St

	۶	→	•	•	←	•	4	†	<i>></i>	-	↓	4
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		∱ ∱			^	7	ሻሻ	ተተተ		14.54	ተተኈ	
Traffic Volume (vph)	0	307	305	0	683	387	170	525	0	325	1208	49
Future Volume (vph)	0	307	305	0	683	387	170	525	0	325	1208	49
ldeal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)		9.0			9.0	9.0	8.0	8.0		9.0	9.0	
Lane Util. Factor		0.95			0.95	1.00	0.97	0.91		0.97	0.91	
Frpb, ped/bikes		1.00			1.00	1.00	1.00	1.00		1.00	1.00	
Flpb, ped/bikes		1.00			1.00	1.00	1.00	1.00		1.00	1.00	
Frt		0.93			1.00	0.85	1.00	1.00		1.00	0.99	
Flt Protected		1.00			1.00	1.00	0.95	1.00		0.95	1.00	
Satd. Flow (prot)		2947			3185	1425	3090	4577		3090	4544	
Flt Permitted		1.00			1.00	1.00	0.95	1.00		0.95	1.00	
Satd. Flow (perm)		2947			3185	1425	3090	4577		3090	4544	
Peak-hour factor, PHF	0.98	0.98	0.98	0.98	0.98	0.98	0.98	0.98	0.98	0.98	0.98	0.98
Adj. Flow (vph)	0	313	311	0	697	395	173	536	0	332	1233	50
RTOR Reduction (vph)	0	120	0	0	0	284	0	0	0	0	3	0
Lane Group Flow (vph)	0	504	0	0	697	111	173	536	0	332	1280	0
Confl. Peds. (#/hr)												10
Turn Type		NA			NA	Perm	Prot	NA		Prot	NA	
Protected Phases		4			8		1	5		6	2	
Permitted Phases					-	8		-				
Actuated Green, G (s)		38.0			38.0	38.0	13.0	45.0		41.0	73.0	
Effective Green, g (s)		38.0			38.0	38.0	13.0	45.0		41.0	73.0	
Actuated g/C Ratio		0.25			0.25	0.25	0.09	0.30		0.27	0.49	
Clearance Time (s)		9.0			9.0	9.0	8.0	8.0		9.0	9.0	
Vehicle Extension (s)		5.0			5.0	5.0	7.0	0.2		5.0	0.2	
Lane Grp Cap (vph)		746			806	361	267	1373		844	2211	
v/s Ratio Prot		0.17			c0.22		c0.06	0.12		0.11	c0.28	
v/s Ratio Perm						0.08		• • • • • • • • • • • • • • • • • • • •			001_0	
v/c Ratio		0.68			0.86	0.31	0.65	0.39		0.39	0.58	
Uniform Delay, d1		50.4			53.5	45.3	66.3	41.6		44.4	27.5	
Progression Factor		1.00			1.00	1.00	1.00	1.00		1.00	1.00	
Incremental Delay, d2		4.9			11.9	2.2	9.9	0.8		1.4	1.1	
Delay (s)		55.3			65.5	47.5	76.2	42.5		45.8	28.6	
Level of Service		E			E	D	E	D		D	С	
Approach Delay (s)		55.3			59.0	_		50.7		_	32.1	
Approach LOS		E			E			D			С	
Intersection Summary												
HCM 2000 Control Delay			46.2	Н	CM 2000	Level of	Service		D			
HCM 2000 Volume to Capacity	ratio		0.67									
Actuated Cycle Length (s)			150.0	S	um of lost	time (s)			26.0			
Intersection Capacity Utilization			75.2%		U Level				D			
Analysis Period (min)			15									
c Critical Lane Group												

HCM Unsignalized Intersection Capacity Analysis 1: Monroe St & E Middle Ln

	→	•	•	←	•	~
Movement	EBT	EBR	WBL	WBT	NBL	NBR
Lane Configurations	↑ ↑			^		7
Traffic Volume (veh/h)	435	4	0	322	0	51
Future Volume (Veh/h)	435	4	0	322	0	51
Sign Control	Free			Free	Stop	
Grade	0%			0%	0%	
Peak Hour Factor	0.87	0.87	0.87	0.87	0.87	0.87
Hourly flow rate (vph)	500	5	0	370	0	59
Pedestrians	12			2	38	
Lane Width (ft)	12.0			12.0	12.0	
Walking Speed (ft/s)	3.5			3.5	3.5	
Percent Blockage	1			0	4	
Right turn flare (veh)						
Median type	None			None		
Median storage veh)						
Upstream signal (ft)						
pX, platoon unblocked						
vC, conflicting volume			543		738	292
vC1, stage 1 conf vol						
vC2, stage 2 conf vol						
vCu, unblocked vol			543		738	292
tC, single (s)			4.1		6.8	6.9
tC, 2 stage (s)						
tF (s)			2.2		3.5	3.3
p0 queue free %			100		100	91
cM capacity (veh/h)			985		337	677
	ED 4	ED 0		W/D O		-
Direction, Lane # Volume Total	EB 1 333	EB 2 172	WB 1 185	WB 2 185	NB 1 59	
Volume Left						
	0	0 5	0	0	0 59	
Volume Right			0	0		
cSH	1700	1700	1700	1700	677	
Volume to Capacity	0.20	0.10	0.11	0.11	0.09	
Queue Length 95th (ft)	0	0	0	0	7	
Control Delay (s)	0.0	0.0	0.0	0.0	10.8	
Lane LOS			0.0		В	
Approach Delay (s)	0.0		0.0		10.8	
Approach LOS					В	
Intersection Summary						
Average Delay			0.7			
Intersection Capacity Utiliza	tion		24.5%	IC	U Level o	f Service
Analysis Period (min)			15			

HCM Unsignalized Intersection Capacity Analysis

2: Monroe St & E Montgomery Ave

	•		•	•	1	J
		•	7	ı	*	~
Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations	, M			†	†	
Sign Control	Stop			Stop	Stop	
Traffic Volume (vph)	0	0	0	0	0	0
Future Volume (vph)	0	0	0	0	0	0
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Hourly flow rate (vph)	0	0	0	0	0	0
Direction, Lane #	EB 1	NB 1	SB 1			
Volume Total (vph)	0	0	0			
Volume Left (vph)	0	0	0			
Volume Right (vph)	0	0	0			
Hadj (s)	0.00	0.00	0.00			
Departure Headway (s)	3.9	3.9	3.9			
Degree Utilization, x	0.00	0.00	0.00			
Capacity (veh/h)	917	917	917			
Control Delay (s)	6.9	6.9	6.9			
Approach Delay (s)	0.0	0.0	0.0			
Approach LOS	Α	Α	Α			
Intersection Summary						
Delay			0.0			
Level of Service			Α			
Intersection Capacity Utiliz	ation		0.0%	IC	U Level c	f Service
Analysis Period (min)			15			

HCM Unsignalized Intersection Capacity Analysis 3: Monroe St & Monroe Pl

o. Monioc of a Mo											0 17 1	.,
	٠	→	•	•	+	•	•	†	<i>></i>	/	ļ	4
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		4			4			ન	7		4	
Sign Control		Stop			Stop			Stop			Stop	
Traffic Volume (vph)	0	0	0	0	0	0	0	0	0	0	0	0
Future Volume (vph)	0	0	0	0	0	0	0	0	0	0	0	0
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Hourly flow rate (vph)	0	0	0	0	0	0	0	0	0	0	0	0
Direction, Lane #	EB 1	WB 1	NB 1	NB 2	SB 1							
Volume Total (vph)	0	0	0	0	0							
Volume Left (vph)	0	0	0	0	0							
Volume Right (vph)	0	0	0	0	0							
Hadj (s)	0.00	0.00	0.00	0.00	0.00							
Departure Headway (s)	3.9	3.9	4.5	4.5	4.0							
Degree Utilization, x	0.00	0.00	0.00	0.00	0.00							
Capacity (veh/h)	917	917	806	806	900							
Control Delay (s)	6.9	6.9	6.3	6.3	7.0							
Approach Delay (s)	0.0	0.0	0.0		0.0							
Approach LOS	Α	Α	Α		Α							
Intersection Summary												
Delay			0.0									
Level of Service			Α									
Intersection Capacity Utiliza	ition		0.0%	IC	CU Level	of Service			Α			
Analysis Period (min)			15									

HCM Signalized Intersection Capacity Analysis

4: Monroe St & E Jefferson St

	٠	→	`	•	←	4	•	†	<i>></i>	\	Ţ	→
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	ሻ	∱ }		ች	ħβ		*	1>		ች	7	
Traffic Volume (vph)	47	744	37	53	652	30	65	106	183	62	97	96
Future Volume (vph)	47	744	37	53	652	30	65	106	183	62	97	96
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	5.5	5.5		5.5	5.5		6.0	6.0		6.0	6.0	
Lane Util. Factor	1.00	0.95		1.00	0.95		1.00	1.00		1.00	1.00	
Frpb, ped/bikes	1.00	1.00		1.00	1.00		1.00	0.94		1.00	0.93	
Flpb, ped/bikes	1.00	1.00		1.00	1.00		0.92	1.00		0.96	1.00	
Frt	1.00	0.99		1.00	0.99		1.00	0.90		1.00	0.93	
Flt Protected	0.95	1.00		0.95	1.00		0.95	1.00		0.95	1.00	
Satd. Flow (prot)	1591	3156		1591	3159		1462	1432		1535	1450	
Flt Permitted	0.26	1.00		0.18	1.00		0.49	1.00		0.25	1.00	
Satd. Flow (perm)	428	3156		296	3159		761	1432		410	1450	
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	51	809	40	58	709	33	71	115	199	67	105	104
RTOR Reduction (vph)	0	0	0	0	0	0	0	0	0	0	0	0
Lane Group Flow (vph)	51	849	0	58	742	0	71	314	0	67	209	0
Confl. Peds. (#/hr)	8		19	19		8	77		49	49		77
Turn Type	pm+pt	NA		pm+pt	NA		Perm	NA		Perm	NA	
Protected Phases	1	6		5	2			8			4	
Permitted Phases	6			2			8			4		
Actuated Green, G (s)	34.0	31.0		36.0	32.0		17.0	17.0		17.0	17.0	
Effective Green, g (s)	34.0	31.0		36.0	32.0		17.0	17.0		17.0	17.0	
Actuated g/C Ratio	0.38	0.34		0.40	0.36		0.19	0.19		0.19	0.19	
Clearance Time (s)	5.5	5.5		5.5	5.5		6.0	6.0		6.0	6.0	
Vehicle Extension (s)	3.0	3.0		3.0	3.0		3.0	3.0		3.0	3.0	
Lane Grp Cap (vph)	200	1087		175	1123		143	270		77	273	
v/s Ratio Prot	0.01	c0.27		c0.01	0.23			c0.22			0.14	
v/s Ratio Perm	0.09			0.12			0.09			0.16		
v/c Ratio	0.26	0.78		0.33	0.66		0.50	1.16		0.87	0.77	
Uniform Delay, d1	18.6	26.5		18.2	24.4		32.7	36.5		35.4	34.6	
Progression Factor	1.00	1.00		1.16	1.63		0.88	0.95		1.00	1.00	
Incremental Delay, d2	0.7	5.6		1.0	2.8		2.5	104.5		60.8	12.1	
Delay (s)	19.2	32.0		22.1	42.6		31.3	139.2		96.2	46.7	
Level of Service	В	С		С	D		С	F		F	D	
Approach Delay (s)		31.3			41.1			119.3			58.7	
Approach LOS		С			D			F			Е	
Intersection Summary												
HCM 2000 Control Delay			52.2	H	CM 2000	Level of S	Service		D			
HCM 2000 Volume to Capa	city ratio		0.64									
Actuated Cycle Length (s)			90.0		um of lost				19.0			
Intersection Capacity Utiliza	ation		73.7%	IC	U Level o	of Service			D			
Analysis Period (min)			15									
c Critical Lane Group												

HCM Signalized Intersection Capacity Analysis 5: Monroe St & Fleet St

	•	→	*	•	←	•	4	†	/	\	↓	1
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	7	ĵ.		7	ĵ.			4		7	ĵ.	
Traffic Volume (vph)	157	189	83	13	180	44	11	66	7	9	73	134
Future Volume (vph)	157	189	83	13	180	44	11	66	7	9	73	134
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	5.0	5.0		5.0	5.0			5.0		5.0	5.0	
Lane Util. Factor	1.00	1.00		1.00	1.00			1.00		1.00	1.00	
Frpb, ped/bikes	1.00	0.98		1.00	0.99			0.99		1.00	0.98	
Flpb, ped/bikes	0.99	1.00		0.97	1.00			1.00		0.97	1.00	
Frt	1.00	0.95		1.00	0.97			0.99		1.00	0.90	
Flt Protected	0.95	1.00		0.95	1.00			0.99		0.95	1.00	
Satd. Flow (prot)	1576	1564		1553	1615			1637		1545	1480	
Flt Permitted	0.51	1.00		0.46	1.00			0.74		0.62	1.00	
Satd. Flow (perm)	851	1564		747	1615			1222		1008	1480	
Peak-hour factor, PHF	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60
Adj. Flow (vph)	262	315	138	22	300	73	18	110	12	15	122	223
RTOR Reduction (vph)	0	12	0	0	6	0	0	5	0	0	93	0
Lane Group Flow (vph)	262	441	0	22	367	0	0	135	0	15	252	0
Confl. Peds. (#/hr)	9		23	23		9	7		19	19		7
Turn Type	Perm	NA		Perm	NA		Perm	NA		Perm	NA	
Protected Phases		6			2			8			4	
Permitted Phases	6			2			8			4		
Actuated Green, G (s)	59.5	59.5		59.5	59.5			20.5		20.5	20.5	
Effective Green, g (s)	59.5	59.5		59.5	59.5			20.5		20.5	20.5	
Actuated g/C Ratio	0.66	0.66		0.66	0.66			0.23		0.23	0.23	
Clearance Time (s)	5.0	5.0		5.0	5.0			5.0		5.0	5.0	
Vehicle Extension (s)	3.0	3.0		3.0	3.0			3.0		3.0	3.0	
Lane Grp Cap (vph)	562	1033		493	1067			278		229	337	
v/s Ratio Prot		0.28			0.23						c0.17	
v/s Ratio Perm	c0.31			0.03				0.11		0.01		
v/c Ratio	0.47	0.43		0.04	0.34			0.49		0.07	0.75	
Uniform Delay, d1	7.5	7.2		5.3	6.7			30.2		27.2	32.4	
Progression Factor	0.90	0.88		1.00	1.00			1.00		0.84	0.78	
Incremental Delay, d2	2.1	1.0		0.2	0.9			1.3		0.1	8.4	
Delay (s)	8.9	7.3		5.5	7.6			31.5		23.0	33.7	
Level of Service	Α	A		Α	A			C		С	C	
Approach Delay (s) Approach LOS		7.9 A			7.5 A			31.5 C			33.2 C	
Intersection Summary												
HCM 2000 Control Delay			15.5	H	CM 2000	Level of S	Service		В			
HCM 2000 Volume to Capa	city ratio		0.54									
Actuated Cycle Length (s)			90.0	Sı	um of lost	time (s)			10.0			
Intersection Capacity Utiliza	ation		70.3%		U Level o				С			
Analysis Period (min)			15									
c Critical Lane Group												

HCM Signalized Intersection Capacity Analysis 6: Maryland Ave & Fleet St

	۶	→	•	•	←	•	4	†	/	-	↓	1
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		₩.		ሻ		7		↑	7	ሻ	↑	
Traffic Volume (vph)	12	4	2	302	0	80	0	332	415	21	308	0
Future Volume (vph)	12	4	2	302	0	80	0	332	415	21	308	0
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)		4.5		4.5		4.5		4.5	4.5	4.5	4.5	
Lane Util. Factor		1.00		1.00		1.00		1.00	1.00	1.00	1.00	
Frpb, ped/bikes		0.99		1.00		0.97		1.00	0.96	1.00	1.00	
Flpb, ped/bikes		1.00		1.00		1.00		1.00	1.00	1.00	1.00	
Frt		0.98		1.00		0.85		1.00	0.85	1.00	1.00	
Flt Protected		0.97		0.95		1.00		1.00	1.00	0.95	1.00	
Satd. Flow (prot)		1579		1593		1376		1676	1363	1593	1676	
Flt Permitted		0.97		0.95		1.00		1.00	1.00	0.18	1.00	
Satd. Flow (perm)		1579		1593		1376		1676	1363	301	1676	
Peak-hour factor, PHF	0.71	0.71	0.71	0.71	0.71	0.71	0.71	0.71	0.71	0.71	0.71	0.71
Adj. Flow (vph)	17	6	3	425	0	113	0	468	585	30	434	0
RTOR Reduction (vph)	0	3	0	0	0	77	0	0	469	0	0	0
Lane Group Flow (vph)	0	23	0	425	0	36	0	468	116	30	434	0
Confl. Peds. (#/hr)	5		5	5		5	5		8	8		5
Turn Type	Split	NA		Prot		Perm		NA	Perm	pm+pt	NA	
Protected Phases	3	3		4				2		1	6	
Permitted Phases						4			2	6		
Actuated Green, G (s)		2.6		28.8		28.8		17.8	17.8	45.1	45.1	
Effective Green, g (s)		2.6		28.8		28.8		17.8	17.8	45.1	45.1	
Actuated g/C Ratio		0.03		0.32		0.32		0.20	0.20	0.50	0.50	
Clearance Time (s)		4.5		4.5		4.5		4.5	4.5	4.5	4.5	
Vehicle Extension (s)		4.0		2.0		2.0		5.0	5.0	3.0	5.0	
Lane Grp Cap (vph)		45		509		440		331	269	478	839	
v/s Ratio Prot		c0.01		c0.27				c0.28		0.02	c0.26	
v/s Ratio Perm						0.03			0.08	0.02		
v/c Ratio		0.51		0.83		0.08		1.41	0.43	0.06	0.52	
Uniform Delay, d1		43.1		28.4		21.4		36.1	31.7	13.3	15.1	
Progression Factor		1.00		1.16		3.26		1.00	1.00	1.00	1.00	
Incremental Delay, d2		12.5		10.1		0.0		203.3	5.0	0.3	2.3	
Delay (s)		55.6		43.0		69.7		239.4	36.6	13.6	17.4	
Level of Service		Е		D		Е		F	D	В	В	
Approach Delay (s)		55.6			48.6			126.7			17.1	
Approach LOS		Е			D			F			В	
Intersection Summary												
HCM 2000 Control Delay			81.2	H	CM 2000	Level of S	Service		F			
HCM 2000 Volume to Capacity	y ratio		0.88									
Actuated Cycle Length (s)			90.0		um of lost				18.0			
Intersection Capacity Utilizatio	n		51.8%	IC	U Level of	of Service			Α			
Analysis Period (min)			15									
c Critical Lane Group												

HCM Signalized Intersection Capacity Analysis 7: MD 255 % F. Jofferson St.

7: MD 355 & E Jefferson St 04/14/2023

	۶	→	•	•	←	•	•	†	~	/	↓	√
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		∱ }			^	7	1,1	ተተተ		ሻሻ	ተተኈ	
Traffic Volume (vph)	0	591	238	0	443	378	267	1003	0	535	847	61
Future Volume (vph)	0	591	238	0	443	378	267	1003	0	535	847	61
(1 1)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)		9.0			9.0	9.0	8.0	8.0		9.0	9.0	
Lane Util. Factor		0.95			0.95	1.00	0.97	0.91		0.97	0.91	
Frpb, ped/bikes		1.00			1.00	1.00	1.00	1.00		1.00	1.00	
Flpb, ped/bikes		1.00			1.00	1.00	1.00	1.00		1.00	1.00	
Frt		0.96			1.00	0.85	1.00	1.00		1.00	0.99	
Flt Protected		1.00			1.00	1.00	0.95	1.00		0.95	1.00	
Satd. Flow (prot)		3048			3185	1425	3090	4577		3090	4523	
Flt Permitted		1.00			1.00	1.00	0.95	1.00		0.95	1.00	
Satd. Flow (perm)		3048			3185	1425	3090	4577		3090	4523	
Peak-hour factor, PHF	0.98	0.98	0.98	0.98	0.98	0.98	0.98	0.98	0.98	0.98	0.98	0.98
Adj. Flow (vph)	0	603	243	0	452	386	272	1023	0	546	864	62
RTOR Reduction (vph)	0	24	0	0	0	244	0	0	0	0	4	0
Lane Group Flow (vph)	0	822	0	0	452	142	272	1023	0	546	922	0
Confl. Peds. (#/hr)												5
Turn Type		NA			NA	Perm	Prot	NA		Prot	NA	
Protected Phases		4			8		1	5		6	2	
Permitted Phases						8						
Actuated Green, G (s)		51.0			51.0	51.0	25.0	76.0		27.0	78.0	
Effective Green, g (s)		51.0			51.0	51.0	25.0	76.0		27.0	78.0	
Actuated g/C Ratio		0.28			0.28	0.28	0.14	0.42		0.15	0.43	
Clearance Time (s)		9.0			9.0	9.0	8.0	8.0		9.0	9.0	
Vehicle Extension (s)		5.0			5.0	5.0	7.0	0.2		5.0	0.2	
Lane Grp Cap (vph)		863			902	403	429	1932		463	1959	
v/s Ratio Prot		c0.27			0.14		0.09	c0.22		c0.18	0.20	
v/s Ratio Perm						0.10						
v/c Ratio		0.95			0.50	0.35	0.63	0.53		1.18	0.47	
Uniform Delay, d1		63.3			53.9	51.4	73.2	38.7		76.5	36.3	
Progression Factor		0.90			1.00	1.00	1.00	1.00		1.00	1.00	
Incremental Delay, d2		13.3			2.0	2.4	5.9	1.0		101.1	0.8	
Delay (s)		70.3			55.9	53.8	79.0	39.7		177.6	37.1	
Level of Service		E			Е	D	Е	D		F	D	
Approach Delay (s)		70.3			54.9			48.0			89.2	
Approach LOS		Е			D			D			F	
Intersection Summary												
HCM 2000 Control Delay			67.2	H	CM 2000	Level of S	Service		Е			
HCM 2000 Volume to Capacity	ratio		0.78									
Actuated Cycle Length (s)			180.0		um of lost				26.0			
Intersection Capacity Utilization			86.8%	IC	U Level	of Service			Е			
Analysis Period (min)			15									
c Critical Lane Group												

Build Exclusive Phase Opt 1 - PM Timing Plan: PM

04/14/2023

Intersection: 1: Monroe St & E Middle Ln

Movement	EB	WB	WB	NB
Directions Served	Т	Т	Т	R
Maximum Queue (ft)	31	44	6	57
Average Queue (ft)	1	4	0	26
95th Queue (ft)	12	25	5	52
Link Distance (ft)	640	187	187	
Upstream Blk Time (%)				
Queuing Penalty (veh)				
Storage Bay Dist (ft)				
Storage Blk Time (%)				
Queuing Penalty (veh)				

Intersection: 2: Monroe St & E Montgomery Ave

Movement
Directions Served
Maximum Queue (ft)
Average Queue (ft)
95th Queue (ft)
Link Distance (ft)
Upstream Blk Time (%)
Queuing Penalty (veh)
Storage Bay Dist (ft)
Storage Blk Time (%)
Queuing Penalty (veh)

Intersection: 3: Monroe St & Monroe PI

ement
ctions Served
imum Queue (ft)
rage Queue (ft)
Queue (ft)
Distance (ft)
tream Blk Time (%)
uing Penalty (veh)
age Bay Dist (ft)
age Blk Time (%)
uing Penalty (veh)

04/14/2023

Intersection: 4: Monroe St & E Jefferson St

Movement	EB	EB	EB	WB	WB	WB	NB	NB	SB	SB	
Directions Served	L	Т	TR	L	Т	TR	L	TR	L	TR	
Maximum Queue (ft)	92	198	261	150	394	419	148	232	60	143	
Average Queue (ft)	38	110	156	75	204	222	56	120	14	74	
95th Queue (ft)	77	182	233	155	368	380	110	197	45	127	
Link Distance (ft)		546	546		886	886		433			
Upstream Blk Time (%)											
Queuing Penalty (veh)											
Storage Bay Dist (ft)	250			125			225		150		
Storage Blk Time (%)		0		0	15			0		0	
Queuing Penalty (veh)		0		1	15			0		0	

Intersection: 5: Monroe St & Fleet St

Movement	EB	EB	WB	WB	NB	SB	SB
Directions Served	L	TR	L	TR	LTR	L	TR
Maximum Queue (ft)	124	245	33	176	165	90	120
Average Queue (ft)	60	90	5	71	77	31	50
95th Queue (ft)	112	185	23	136	138	68	95
Link Distance (ft)		361	580	580	528		433
Upstream Blk Time (%)							
Queuing Penalty (veh)							
Storage Bay Dist (ft)	100					175	
Storage Blk Time (%)	2	4					0
Queuing Penalty (veh)	6	6					0

Intersection: 6: Maryland Ave & Fleet St

Movement	EB	WB	WB	NB	NB	SB	SB
Directions Served	LTR	L	R	Т	R	L	Т
Maximum Queue (ft)	29	248	282	220	91	71	132
Average Queue (ft)	4	167	53	116	22	27	49
95th Queue (ft)	18	250	157	195	67	58	107
Link Distance (ft)	141		361	646			432
Upstream Blk Time (%)			0				
Queuing Penalty (veh)			0				
Storage Bay Dist (ft)		225			450	125	
Storage Blk Time (%)		3					0
Queuing Penalty (veh)		3					0

04/14/2023

Intersection: 7: MD 355 & E Jefferson St

Movement	EB	EB	WB	WB	WB	NB	NB	NB	NB	NB	SB	SB
Directions Served	T	TR	T	Т	R	L	L	Т	T	T	L	L
Maximum Queue (ft)	238	341	397	343	56	136	183	227	192	168	212	272
Average Queue (ft)	107	124	247	221	5	45	97	143	127	65	104	157
95th Queue (ft)	193	259	357	325	30	125	167	206	187	153	205	234
Link Distance (ft)	886	886	941	941	941			760	760	760		
Upstream Blk Time (%)												
Queuing Penalty (veh)												
Storage Bay Dist (ft)						275	275				425	425
Storage Blk Time (%)								0				
Queuing Penalty (veh)								0				

Intersection: 7: MD 355 & E Jefferson St

Movement	SB	SB	SB
Directions Served	Т	Т	TR
Maximum Queue (ft)	364	344	307
Average Queue (ft)	243	227	172
95th Queue (ft)	337	312	272
Link Distance (ft)	658	658	658
Upstream Blk Time (%)			
Queuing Penalty (veh)			
Storage Bay Dist (ft)			
Storage Blk Time (%)			
Queuing Penalty (veh)			

Network Summary

Network wide Queuing Penalty: 32

04/14/2023

Intersection: 1: Monroe St & E Middle Ln

Movement	EB	EB	WB	WB	NB
Directions Served	Т	TR	Т	Т	R
Maximum Queue (ft)	39	12	39	6	64
Average Queue (ft)	4	1	3	0	26
95th Queue (ft)	22	9	19	4	53
Link Distance (ft)	640	640	187	187	
Upstream Blk Time (%)					
Queuing Penalty (veh)					
Storage Bay Dist (ft)					
Storage Blk Time (%)					
Queuing Penalty (veh)					

ATTACHMENT A

Intersection: 2: Monroe St & E Montgomery Ave

Movement
Directions Served
Maximum Queue (ft)
Average Queue (ft)
95th Queue (ft)
Link Distance (ft)
Upstream Blk Time (%)
Queuing Penalty (veh)
Storage Bay Dist (ft)
Storage Blk Time (%)
Queuing Penalty (veh)

Intersection: 3: Monroe St & Monroe PI

Movement
Directions Served
Maximum Queue (ft)
Average Queue (ft)
95th Queue (ft)
Link Distance (ft)
Upstream Blk Time (%)
Queuing Penalty (veh)
Storage Bay Dist (ft)
Storage Blk Time (%)
Queuing Penalty (veh)

04/14/2023

Intersection: 4: Monroe St & E Jefferson St

Movement	EB	EB	EB	WB	WB	WB	NB	NB	SB	SB	
Directions Served	L	Т	TR	L	Т	TR	L	TR	L	TR	
Maximum Queue (ft)	106	283	299	150	323	350	250	426	174	254	
Average Queue (ft)	31	173	168	62	217	235	122	284	69	131	
95th Queue (ft)	77	255	260	152	313	327	285	460	148	226	
Link Distance (ft)		546	546		886	886		433			
Upstream Blk Time (%)								2			
Queuing Penalty (veh)								6			
Storage Bay Dist (ft)	250			125			225		150		
Storage Blk Time (%)		1		0	18		1	51	1	8	
Queuing Penalty (veh)		0		0	9		3	33	2	5	

Intersection: 5: Monroe St & Fleet St

Movement	EB	EB	WB	WB	NB	SB	SB
Directions Served	L	TR	L	TR	LTR	L	TR
Maximum Queue (ft)	122	165	29	153	121	67	201
Average Queue (ft)	55	66	6	50	50	9	80
95th Queue (ft)	109	131	25	111	101	41	154
Link Distance (ft)		361	580	580	528		433
Upstream Blk Time (%)							
Queuing Penalty (veh)							
Storage Bay Dist (ft)	100					175	
Storage Blk Time (%)	2	2					1
Queuing Penalty (veh)	6	3					0

Intersection: 6: Maryland Ave & Fleet St

Movement	EB	WB	WB	NB	NB	SB	SB
Directions Served	LTR	L	R	Т	R	L	Т
Maximum Queue (ft)	59	247	174	419	128	34	186
Average Queue (ft)	16	175	44	204	14	9	72
95th Queue (ft)	44	248	122	359	124	30	143
Link Distance (ft)	141		361	646			432
Upstream Blk Time (%)				0			
Queuing Penalty (veh)				0			
Storage Bay Dist (ft)		225			450	125	
Storage Blk Time (%)		2		0	0		1
Queuing Penalty (veh)		2		2	0		0

04/14/2023

Intersection: 7: MD 355 & E Jefferson St

Movement	EB	EB	WB	WB	WB	NB	NB	NB	NB	NB	SB	SB
Directions Served	Т	TR	Т	Т	R	L	L	Т	Т	Т	L	L
Maximum Queue (ft)	462	482	288	247	114	211	299	399	367	284	437	450
Average Queue (ft)	277	320	160	135	14	87	160	262	236	176	432	449
95th Queue (ft)	424	462	244	224	61	180	279	377	335	282	452	453
Link Distance (ft)	886	886	941	941	941			760	760	760		
Upstream Blk Time (%)												
Queuing Penalty (veh)												
Storage Bay Dist (ft)						275	275				425	425
Storage Blk Time (%)							0	5			16	72
Queuing Penalty (veh)							0	12			46	202

Intersection: 7: MD 355 & E Jefferson St

Movement	SB	SB	SB
Directions Served	Т	Т	TR
Maximum Queue (ft)	702	657	516
Average Queue (ft)	666	442	267
95th Queue (ft)	755	707	433
Link Distance (ft)	658	658	658
Upstream Blk Time (%)	72	0	
Queuing Penalty (veh)	0	0	
Storage Bay Dist (ft)			
Storage Blk Time (%)	0		
Queuing Penalty (veh)	2		

Network Summary

Network wide Queuing Penalty: 334

HCM Unsignalized Intersection Capacity Analysis 1: Monroe St & E Middle Ln

	-	\rightarrow	•	←	4	~
Movement	EBT	EBR	WBL	WBT	NBL	NBR
Lane Configurations	∱ Ъ			^		7
Traffic Volume (veh/h)	229	14	0	350	0	42
Future Volume (Veh/h)	229	14	0	350	0	42
Sign Control	Free			Free	Stop	
Grade	0%			0%	0%	
Peak Hour Factor	0.86	0.86	0.86	0.86	0.86	0.86
Hourly flow rate (vph)	266	16	0	407	0	49
Pedestrians	11			1	29	
Lane Width (ft)	12.0			12.0	12.0	
Walking Speed (ft/s)	3.5			3.5	3.5	
Percent Blockage	1			0	3	
Right turn flare (veh)						
Median type	None			None		
Median storage veh)						
Upstream signal (ft)						
pX, platoon unblocked						
vC, conflicting volume			311		518	171
vC1, stage 1 conf vol						
vC2, stage 2 conf vol						
vCu, unblocked vol			311		518	171
tC, single (s)			4.1		6.8	6.9
tC, 2 stage (s)						
tF (s)			2.2		3.5	3.3
p0 queue free %			100		100	94
cM capacity (veh/h)			1212		469	819
	ED 4	ED 0		WD 0		
Direction, Lane # Volume Total	EB 1 177	EB 2 105	WB 1 204	WB 2 204	NB 1 49	
Volume Total Volume Left					49	
	0	0 16	0	0	49	
Volume Right						
cSH	1700	1700	1700	1700	819	
Volume to Capacity	0.10	0.06	0.12	0.12	0.06	
Queue Length 95th (ft)	0	0	0	0	5	
Control Delay (s)	0.0	0.0	0.0	0.0	9.7	
Lane LOS	0.0		0.0		A	
Approach Delay (s)	0.0		0.0		9.7	
Approach LOS					Α	
Intersection Summary						
Average Delay			0.6			
Intersection Capacity Utiliza	ation		21.5%	IC	U Level o	f Service
Analysis Period (min)			15			

HCM Unsignalized Intersection Capacity Analysis

2: Monroe St & E Montgomery Ave

•							
	•	\rightarrow	1	†	↓	4	
Movement	EBL	EBR	NBL	NBT	SBT	SBR	
Lane Configurations	M			†	†		
Sign Control	Stop			Stop	Stop		
Traffic Volume (vph)	0	0	0	0	0	0	
Future Volume (vph)	0	0	0	0	0	0	
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92	
Hourly flow rate (vph)	0	0	0	0	0	0	
Direction, Lane #	EB 1	NB 1	SB 1				
Volume Total (vph)	0	0	0				
Volume Left (vph)	0	0	0				
Volume Right (vph)	0	0	0				
Hadj (s)	0.00	0.00	0.00				
Departure Headway (s)	3.9	3.9	3.9				
Degree Utilization, x	0.00	0.00	0.00				
Capacity (veh/h)	917	917	917				
Control Delay (s)	6.9	6.9	6.9				
Approach Delay (s)	0.0	0.0	0.0				
Approach LOS	Α	Α	Α				
Intersection Summary							
Delay			0.0				
Level of Service			Α				
Intersection Capacity Utiliz	ation		0.0%	IC	U Level o	f Service	
Analysis Period (min)			15				

HCM Unsignalized Intersection Capacity Analysis 3: Monroe St & Monroe Pl

3. MOTITOE ST & MO											0-1/1	4/2023
	•	→	•	•	←	•	4	†	/	>	ţ	1
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		₩			4			ર્ન	7		€	
Sign Control		Stop			Stop			Stop			Stop	
Traffic Volume (vph)	0	0	0	0	0	0	0	0	0	0	0	0
Future Volume (vph)	0	0	0	0	0	0	0	0	0	0	0	0
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Hourly flow rate (vph)	0	0	0	0	0	0	0	0	0	0	0	0
Direction, Lane #	EB 1	WB 1	NB 1	NB 2	SB 1							
Volume Total (vph)	0	0	0	0	0							
Volume Left (vph)	0	0	0	0	0							
Volume Right (vph)	0	0	0	0	0							
Hadj (s)	0.00	0.00	0.00	0.00	0.00							
Departure Headway (s)	3.9	3.9	4.5	4.5	4.0							
Degree Utilization, x	0.00	0.00	0.00	0.00	0.00							
Capacity (veh/h)	917	917	806	806	900							
Control Delay (s)	6.9	6.9	6.3	6.3	7.0							
Approach Delay (s)	0.0	0.0	0.0		0.0							
Approach LOS	Α	Α	Α		Α							
Intersection Summary												
Delay			0.0									
Level of Service			Α									
Intersection Capacity Utiliza	ation		0.0%	IC	U Level o	of Service			Α			
Analysis Period (min)			15									

HCM Signalized Intersection Capacity Analysis

4: Monroe St & E Jefferson St

	۶	→	•	•	+	4	1	†	<u> </u>	/	 	4
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	*	↑ ↑		*	↑ ↑			†	7	ሻ	1>	
Traffic Volume (vph)	69	568	64	96	674	56	0	135	71	15	78	41
Future Volume (vph)	69	568	64	96	674	56	0	135	71	15	78	41
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	5.5	5.5		5.5	5.5			6.0	6.0	6.0	6.0	
Lane Util. Factor	1.00	0.95		1.00	0.95			1.00	1.00	1.00	1.00	
Frpb, ped/bikes	1.00	1.00		1.00	1.00			1.00	0.92	1.00	0.94	
Flpb, ped/bikes	1.00	1.00		1.00	1.00			1.00	1.00	0.94	1.00	
Frt	1.00	0.98		1.00	0.99			1.00	0.85	1.00	0.95	
Flt Protected	0.95	1.00		0.95	1.00			1.00	1.00	0.95	1.00	
Satd. Flow (prot)	1591	3123		1589	3140			1676	1311	1502	1501	
Flt Permitted	0.25	1.00		0.29	1.00			1.00	1.00	0.67	1.00	
Satd. Flow (perm)	422	3123		493	3140			1676	1311	1052	1501	
Peak-hour factor, PHF	0.94	0.94	0.94	0.94	0.94	0.94	0.94	0.94	0.94	0.94	0.94	0.94
Adj. Flow (vph)	73	604	68	102	717	60	0	144	76	16	83	44
RTOR Reduction (vph)	0	0	0	0	0	0	0	0	0	0	0	0
Lane Group Flow (vph)	73	672	0	102	777	0	0	144	76	16	127	0
Confl. Peds. (#/hr)	8		16	16		8	66		59	59		66
Turn Type	pm+pt	NA		pm+pt	NA			NA	Perm	Perm	NA	
Protected Phases	1	6		5	2			8			4	
Permitted Phases	6			2					8	4		
Actuated Green, G (s)	39.5	34.0		40.9	34.7			32.8	32.8	11.8	11.8	
Effective Green, g (s)	39.5	34.0		40.9	34.7			32.8	32.8	11.8	11.8	
Actuated g/C Ratio	0.44	0.38		0.45	0.39			0.36	0.36	0.13	0.13	
Clearance Time (s)	5.5	5.5		5.5	5.5			6.0	6.0	6.0	6.0	
Vehicle Extension (s)	3.0	3.0		3.0	3.0			3.0	3.0	3.0	3.0	
Lane Grp Cap (vph)	256	1179		299	1210			610	477	137	196	
v/s Ratio Prot	0.02	0.22		c0.02	c0.25			c0.09			c0.08	
v/s Ratio Perm	0.11			0.13					0.06	0.02		
v/c Ratio	0.29	0.57		0.34	0.64			0.24	0.16	0.12	0.65	
Uniform Delay, d1	15.5	22.2		14.8	22.6			19.9	19.3	34.5	37.1	
Progression Factor	1.00	1.00		1.00	1.00			0.80	0.80	1.00	1.00	
Incremental Delay, d2	0.6	2.0		0.7	2.6			0.2	0.1	0.4	7.2	
Delay (s)	16.1	24.2		15.5	25.2			16.1	15.6	34.9	44.3	
Level of Service	В	С		В	С			В	В	С	D	
Approach Delay (s)		23.4			24.1			15.9			43.3	
Approach LOS		С			С			В			D	
Intersection Summary												
HCM 2000 Control Delay			24.3	Н	CM 2000	Level of S	Service		С			
HCM 2000 Volume to Capa	acity ratio		0.51						4			
Actuated Cycle Length (s)			90.0		um of lost				19.0			
Intersection Capacity Utiliza	ation		62.7%	IC	CU Level of	of Service			В			
Analysis Period (min)			15									
c Critical Lane Group												

HCM Signalized Intersection Capacity Analysis 5: Monroe St & Fleet St

	ၨ	-	•	•	←	•	4	†	/	\	ļ	4
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	ሻ	₽		ሻ	1>		ሻ	₽		ሻ	₽	
Traffic Volume (vph)	148	314	62	10	320	45	73	39	21	43	43	83
Future Volume (vph)	148	314	62	10	320	45	73	39	21	43	43	83
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	5.0	5.0		5.0	5.0		5.0	5.0		5.0	5.0	
Lane Util. Factor	1.00	1.00		1.00	1.00		1.00	1.00		1.00	1.00	
Frpb, ped/bikes	1.00	0.99		1.00	0.99		1.00	0.99		1.00	0.93	
Flpb, ped/bikes	0.98	1.00		0.98	1.00		0.94	1.00		0.99	1.00	
Frt	1.00	0.98		1.00	0.98		1.00	0.95		1.00	0.90	
Flt Protected	0.95	1.00		0.95	1.00		0.95	1.00		0.95	1.00	
Satd. Flow (prot)	1567	1618		1566	1633		1497	1571		1578	1407	
Flt Permitted	0.41	1.00		0.40	1.00		0.49	1.00		0.70	1.00	
Satd. Flow (perm)	677	1618		660	1633		769	1571		1159	1407	
Peak-hour factor, PHF	0.66	0.66	0.66	0.66	0.66	0.66	0.66	0.66	0.66	0.66	0.66	0.66
Adj. Flow (vph)	224	476	94	15	485	68	111	59	32	65	65	126
RTOR Reduction (vph)	0	5	0	0	4	0	0	26	0	0	94	0
Lane Group Flow (vph)	224	565	0	15	549	0	111	65	0	65	97	0
Confl. Peds. (#/hr)	20		19	19		20	40		5	5		40
Turn Type	Perm	NA		Perm	NA		Perm	NA		Perm	NA	
Protected Phases		6			2			8			4	
Permitted Phases	6			2			8			4		
Actuated Green, G (s)	63.9	63.9		63.9	63.9		16.1	16.1		16.1	16.1	
Effective Green, g (s)	63.9	63.9		63.9	63.9		16.1	16.1		16.1	16.1	
Actuated g/C Ratio	0.71	0.71		0.71	0.71		0.18	0.18		0.18	0.18	
Clearance Time (s)	5.0	5.0		5.0	5.0		5.0	5.0		5.0	5.0	
Vehicle Extension (s)	3.0	3.0		3.0	3.0		3.0	3.0		3.0	3.0	
Lane Grp Cap (vph)	480	1148		468	1159		137	281		207	251	
v/s Ratio Prot		c0.35			0.34			0.04			0.07	
v/s Ratio Perm	0.33			0.02			c0.14			0.06		
v/c Ratio	0.47	0.49		0.03	0.47		0.81	0.23		0.31	0.39	
Uniform Delay, d1	5.7	5.8		3.9	5.7		35.5	31.6		32.1	32.6	
Progression Factor	0.83	0.81		1.00	1.00		1.00	1.00		0.90	0.86	
Incremental Delay, d2	2.8	1.3		0.1	1.4		29.1	0.4		0.8	0.9	
Delay (s)	7.5	6.0		4.0	7.1		64.6	32.1		29.7	29.0	
Level of Service	Α	A		Α	Α		E	C		С	С	
Approach Delay (s)		6.4			7.0		_	49.9			29.2	
Approach LOS		А			Α			D			С	
Intersection Summary												
HCM 2000 Control Delay	·		14.6	H	CM 2000	Level of S	Service		В			
HCM 2000 Volume to Capa	city ratio		0.56									
Actuated Cycle Length (s)			90.0	Sı	um of lost	time (s)			10.0			
Intersection Capacity Utiliza	ation		80.5%	IC	U Level o	of Service			D			
Analysis Period (min)			15									
c Critical Lane Group												

HCM Signalized Intersection Capacity Analysis 6: Maryland Ave & Fleet St

	ၨ	→	•	•	←	4	•	†	~	\		1
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		44		ň		7		†	7	ሻ	^	
Traffic Volume (vph)	2	1	1	315	0	171	0	276	451	87	245	0
Future Volume (vph)	2	1	1	315	0	171	0	276	451	87	245	0
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)		4.5		4.5		4.5		4.5	4.5	4.5	4.5	
Lane Util. Factor		1.00		1.00		1.00		1.00	1.00	1.00	1.00	
Frpb, ped/bikes		0.98		1.00		0.97		1.00	0.97	1.00	1.00	
Flpb, ped/bikes		1.00		1.00		1.00		1.00	1.00	1.00	1.00	
Frt		0.97		1.00		0.85		1.00	0.85	1.00	1.00	
Flt Protected		0.97		0.95		1.00		1.00	1.00	0.95	1.00	
Satd. Flow (prot)		1545		1593		1384		1676	1388	1593	1676	
Flt Permitted		0.97		0.95		1.00		1.00	1.00	0.27	1.00	
Satd. Flow (perm)		1545		1593		1384		1676	1388	456	1676	
Peak-hour factor, PHF	0.79	0.79	0.79	0.79	0.79	0.79	0.79	0.79	0.79	0.79	0.79	0.79
Adj. Flow (vph)	3	1	1	399	0	216	0	349	571	110	310	0
RTOR Reduction (vph)	0	1	0	0	0	149	0	0	407	0	0	0
Lane Group Flow (vph)	0	4	0	399	0	67	0	349	164	110	310	0
Confl. Peds. (#/hr)	3		3	3		3	7		2	2		7
Turn Type	Split	NA		Prot		Perm		NA	Perm	pm+pt	NA	
Protected Phases	3	3		4				2		1	6	
Permitted Phases						4			2	6		
Actuated Green, G (s)		1.3		28.0		28.0		25.9	25.9	47.2	47.2	
Effective Green, g (s)		1.3		28.0		28.0		25.9	25.9	47.2	47.2	
Actuated g/C Ratio		0.01		0.31		0.31		0.29	0.29	0.52	0.52	
Clearance Time (s)		4.5		4.5		4.5		4.5	4.5	4.5	4.5	
Vehicle Extension (s)		4.0		2.0		2.0		5.0	5.0	3.0	5.0	
Lane Grp Cap (vph)		22		495		430		482	399	451	878	
v/s Ratio Prot		c0.00		c0.25				c0.21		0.05	c0.18	
v/s Ratio Perm						0.05			0.12	0.08		
v/c Ratio		0.18		0.81		0.16		0.72	0.41	0.24	0.35	
Uniform Delay, d1		43.8		28.5		22.4		28.8	25.9	12.4	12.5	
Progression Factor		1.00		1.13		1.90		1.00	1.00	1.00	1.00	
Incremental Delay, d2		5.4		8.0		0.1		9.1	3.1	1.3	1.1	
Delay (s)		49.2		40.4		42.7		38.0	29.0	13.7	13.6	
Level of Service		D		D	44.0	D		D	С	В	В	
Approach Delay (s) Approach LOS		49.2 D			41.2 D			32.4 C			13.6 B	
Intersection Summary												
HCM 2000 Control Delay			31.2	Н	CM 2000	Level of	Service		С			
HCM 2000 Volume to Capacity	v ratio		0.67			_0.5.01	3					
Actuated Cycle Length (s)	,		90.0	Sı	um of lost	time (s)			18.0			
Intersection Capacity Utilizatio	n		58.4%			of Service			В			
Analysis Period (min)			15									
c Critical Lane Group												

HCM Signalized Intersection Capacity Analysis 7: MD 355 & E Jefferson St

	۶	→	•	•	←	•	4	†	<i>></i>	\	↓	4
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		∱ ∱			^	7	ሻሻ	ተተተ		14.54	ተተኈ	
Traffic Volume (vph)	0	307	305	0	683	387	170	525	0	325	1208	49
Future Volume (vph)	0	307	305	0	683	387	170	525	0	325	1208	49
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)		9.0			9.0	9.0	8.0	8.0		9.0	9.0	
Lane Util. Factor		0.95			0.95	1.00	0.97	0.91		0.97	0.91	
Frpb, ped/bikes		1.00			1.00	1.00	1.00	1.00		1.00	1.00	
Flpb, ped/bikes		1.00			1.00	1.00	1.00	1.00		1.00	1.00	
Frt		0.93			1.00	0.85	1.00	1.00		1.00	0.99	
Flt Protected		1.00			1.00	1.00	0.95	1.00		0.95	1.00	
Satd. Flow (prot)		2947			3185	1425	3090	4577		3090	4544	
Flt Permitted		1.00			1.00	1.00	0.95	1.00		0.95	1.00	
Satd. Flow (perm)		2947			3185	1425	3090	4577		3090	4544	
Peak-hour factor, PHF	0.98	0.98	0.98	0.98	0.98	0.98	0.98	0.98	0.98	0.98	0.98	0.98
Adj. Flow (vph)	0	313	311	0	697	395	173	536	0	332	1233	50
RTOR Reduction (vph)	0	120	0	0	0	284	0	0	0	0	3	0
Lane Group Flow (vph)	0	504	0	0	697	111	173	536	0	332	1280	0
Confl. Peds. (#/hr)												10
Turn Type		NA			NA	Perm	Prot	NA		Prot	NA	
Protected Phases		4			8		1	5		6	2	
Permitted Phases					-	8		-				
Actuated Green, G (s)		38.0			38.0	38.0	13.0	45.0		41.0	73.0	
Effective Green, g (s)		38.0			38.0	38.0	13.0	45.0		41.0	73.0	
Actuated g/C Ratio		0.25			0.25	0.25	0.09	0.30		0.27	0.49	
Clearance Time (s)		9.0			9.0	9.0	8.0	8.0		9.0	9.0	
Vehicle Extension (s)		5.0			5.0	5.0	7.0	0.2		5.0	0.2	
Lane Grp Cap (vph)		746			806	361	267	1373		844	2211	
v/s Ratio Prot		0.17			c0.22		c0.06	0.12		0.11	c0.28	
v/s Ratio Perm						0.08		• • • • • • • • • • • • • • • • • • • •			001_0	
v/c Ratio		0.68			0.86	0.31	0.65	0.39		0.39	0.58	
Uniform Delay, d1		50.4			53.5	45.3	66.3	41.6		44.4	27.5	
Progression Factor		1.00			1.00	1.00	1.00	1.00		1.00	1.00	
Incremental Delay, d2		4.9			11.9	2.2	9.9	0.8		1.4	1.1	
Delay (s)		55.3			65.5	47.5	76.2	42.5		45.8	28.6	
Level of Service		E			E	D	E	D		D	С	
Approach Delay (s)		55.3			59.0	_		50.7		_	32.1	
Approach LOS		E			E			D			С	
Intersection Summary												
HCM 2000 Control Delay			46.2	Н	CM 2000	Level of	Service		D			
HCM 2000 Volume to Capacity	ratio		0.67									
Actuated Cycle Length (s)			150.0	S	um of lost	time (s)			26.0			
Intersection Capacity Utilization			75.2%		U Level				D			
Analysis Period (min)			15									
c Critical Lane Group												

HCM Unsignalized Intersection Capacity Analysis 1: Monroe St & E Middle Ln

	→	•	•	←	4	<i>></i>
Movement	EBT	EBR	WBL	WBT	NBL	NBR
Lane Configurations	↑ ↑			^		7
Traffic Volume (veh/h)	435	4	0	322	0	51
Future Volume (Veh/h)	435	4	0	322	0	51
Sign Control	Free			Free	Stop	
Grade	0%			0%	0%	
Peak Hour Factor	0.87	0.87	0.87	0.87	0.87	0.87
Hourly flow rate (vph)	500	5	0	370	0	59
Pedestrians	12			2	38	
Lane Width (ft)	12.0			12.0	12.0	
Walking Speed (ft/s)	3.5			3.5	3.5	
Percent Blockage	1			0	4	
Right turn flare (veh)						
Median type	None			None		
Median storage veh)						
Upstream signal (ft)						
pX, platoon unblocked						
vC, conflicting volume			543		738	292
vC1, stage 1 conf vol						
vC2, stage 2 conf vol						
vCu, unblocked vol			543		738	292
tC, single (s)			4.1		6.8	6.9
tC, 2 stage (s)						
tF (s)			2.2		3.5	3.3
p0 queue free %			100		100	91
cM capacity (veh/h)			985		337	677
Direction, Lane #	EB 1	EB 2	WB 1	WB 2	NB 1	
Volume Total	333	172	185	185	59	
Volume Left	0	0	0	0	0	
Volume Right	0	5	0	0	59	
cSH	1700	1700	1700	1700	677	
Volume to Capacity	0.20	0.10	0.11	0.11	0.09	
Queue Length 95th (ft)	0.20	0.10	0.11	0.11	7	
Control Delay (s)	0.0	0.0	0.0	0.0	10.8	
Lane LOS	0.0	0.0	0.0	0.0	10.6 B	
Approach Delay (s)	0.0		0.0		10.8	
Approach LOS	0.0		0.0		В	
• •					D	
Intersection Summary						
Average Delay			0.7			
Intersection Capacity Utiliz	zation		24.5%	IC	U Level c	f Service
Analysis Period (min)			15			
maryolo i onou (iiiii)			10			

HCM Unsignalized Intersection Capacity Analysis

2: Monroe St & E Montgomery Ave

	•	/	•	†	1	4
Mayamant	EDI	▼	NDL	NDT	CDT	CDD
Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations	W			↑	↑	
Sign Control	Stop			Stop	Stop	
Traffic Volume (vph)	0	0	0	0	0	0
Future Volume (vph)	0	0	0	0	0	0
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Hourly flow rate (vph)	0	0	0	0	0	0
Direction, Lane #	EB 1	NB 1	SB 1			
Volume Total (vph)	0	0	0			
Volume Left (vph)	0	0	0			
Volume Right (vph)	0	0	0			
Hadj (s)	0.00	0.00	0.00			
Departure Headway (s)	3.9	3.9	3.9			
Degree Utilization, x	0.00	0.00	0.00			
Capacity (veh/h)	917	917	917			
Control Delay (s)	6.9	6.9	6.9			
Approach Delay (s)	0.0	0.0	0.0			
Approach LOS	А	Α	Α			
Intersection Summary						
Delay			0.0			
Level of Service			Α			
Intersection Capacity Utiliz	zation		0.0%	IC	U Level c	f Service
Analysis Period (min)			15			

HCM Unsignalized Intersection Capacity Analysis 3: Monroe St & Monroe Pl

3. MOTIOE OF A MO											0 17 1	7/2020
	٠	→	•	•	←	•	4	†	<i>></i>	/	ţ	4
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		4			4			4	7		₩	
Sign Control		Stop			Stop			Stop			Stop	
Traffic Volume (vph)	0	0	0	0	0	0	0	0	0	0	0	0
Future Volume (vph)	0	0	0	0	0	0	0	0	0	0	0	0
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Hourly flow rate (vph)	0	0	0	0	0	0	0	0	0	0	0	0
Direction, Lane #	EB 1	WB 1	NB 1	NB 2	SB 1							
Volume Total (vph)	0	0	0	0	0							
Volume Left (vph)	0	0	0	0	0							
Volume Right (vph)	0	0	0	0	0							
Hadj (s)	0.00	0.00	0.00	0.00	0.00							
Departure Headway (s)	3.9	3.9	4.5	4.5	4.0							
Degree Utilization, x	0.00	0.00	0.00	0.00	0.00							
Capacity (veh/h)	917	917	806	806	900							
Control Delay (s)	6.9	6.9	6.3	6.3	7.0							
Approach Delay (s)	0.0	0.0	0.0		0.0							
Approach LOS	Α	Α	Α		Α							
Intersection Summary												
Delay			0.0									
Level of Service			Α									
Intersection Capacity Utiliza	ation		0.0%	IC	U Level o	of Service			Α			
Analysis Period (min)			15									

HCM Signalized Intersection Capacity Analysis 4: Monroe St & E Jefferson St

	۶	→	•	•	—	4	1	†	~	-	↓	4
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	7	∱ ∱		7	∱ î≽			†	7	7	f)	
Traffic Volume (vph)	47	744	37	53	652	30	0	106	183	62	97	96
Future Volume (vph)	47	744	37	53	652	30	0	106	183	62	97	96
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	5.5	5.5		5.5	5.5			6.0	6.0	6.0	6.0	
Lane Util. Factor	1.00	0.95		1.00	0.95			1.00	1.00	1.00	1.00	
Frpb, ped/bikes	1.00	1.00		1.00	1.00			1.00	0.93	1.00	0.93	
Flpb, ped/bikes	1.00	1.00		1.00	1.00			1.00	1.00	0.95	1.00	
Frt	1.00	0.99		1.00	0.99			1.00	0.85	1.00	0.93	
Flt Protected	0.95	1.00		0.95	1.00			1.00	1.00	0.95	1.00	
Satd. Flow (prot)	1591	3156		1591	3159			1676	1328	1515	1443	
Flt Permitted	0.27	1.00		0.18	1.00			1.00	1.00	0.68	1.00	
Satd. Flow (perm)	445	3156		308	3159			1676	1328	1089	1443	
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	51	809	40	58	709	33	0	115	199	67	105	104
RTOR Reduction (vph)	0	0	0	0	0	0	0	0	0	0	0	0
Lane Group Flow (vph)	51	849	0	58	742	0	0	115	199	67	209	0
Confl. Peds. (#/hr)	8		19	19		8	77		49	49		77
Turn Type	pm+pt	NA		pm+pt	NA			NA	Perm	Perm	NA	
Protected Phases	1	6		5	2			8			4	
Permitted Phases	6			2					8	4		
Actuated Green, G (s)	35.0	32.0		37.4	33.2			36.8	36.8	15.8	15.8	
Effective Green, g (s)	35.0	32.0		37.4	33.2			36.8	36.8	15.8	15.8	
Actuated g/C Ratio	0.39	0.36		0.42	0.37			0.41	0.41	0.18	0.18	
Clearance Time (s)	5.5	5.5		5.5	5.5			6.0	6.0	6.0	6.0	
Vehicle Extension (s)	3.0	3.0		3.0	3.0			3.0	3.0	3.0	3.0	
Lane Grp Cap (vph)	211	1122		187	1165			685	543	191	253	
v/s Ratio Prot	0.01	c0.27		c0.01	0.23			0.07			c0.14	
v/s Ratio Perm	0.09			0.11					c0.15	0.06		
v/c Ratio	0.24	0.76		0.31	0.64			0.17	0.37	0.35	0.83	
Uniform Delay, d1	17.9	25.6		17.3	23.4			16.9	18.5	32.6	35.8	
Progression Factor	1.00	1.00		1.16	1.65			0.65	0.66	1.00	1.00	
Incremental Delay, d2	0.6	4.8		0.9	2.4			0.1	0.4	1.1	19.3	
Delay (s)	18.5	30.3		20.9	41.1			11.0	12.7	33.7	55.1	
Level of Service	В	С		С	D			В	В	С	Е	
Approach Delay (s)		29.7			39.6			12.1			49.9	
Approach LOS		С			D			В			D	
Intersection Summary												
HCM 2000 Control Delay			33.2	H	CM 2000	Level of S	Service		С			_
HCM 2000 Volume to Cap			0.64									
Actuated Cycle Length (s)			90.0		um of lost				19.0			
Intersection Capacity Utiliz	zation		62.4%	IC	CU Level of	of Service			В			
Analysis Period (min)			15									
c Critical Lane Group												

HCM Signalized Intersection Capacity Analysis 5: Monroe St & Fleet St

	۶	→	•	•	←	•	4	†	/	-	ļ	1
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBF
Lane Configurations	7	f)		7	ĵ»		7	f)		7	ĵ»	
Traffic Volume (vph)	157	189	83	13	210	14	46	31	7	9	73	134
Future Volume (vph)	157	189	83	13	210	14	46	31	7	9	73	134
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	5.0	5.0		5.0	5.0		5.0	5.0		5.0	5.0	
Lane Util. Factor	1.00	1.00		1.00	1.00		1.00	1.00		1.00	1.00	
Frpb, ped/bikes	1.00	0.98		1.00	1.00		1.00	0.99		1.00	0.98	
Flpb, ped/bikes	0.99	1.00		0.97	1.00		0.99	1.00		0.96	1.00	
Frt	1.00	0.95		1.00	0.99		1.00	0.97		1.00	0.90	
Flt Protected	0.95	1.00		0.95	1.00		0.95	1.00		0.95	1.00	
Satd. Flow (prot)	1576	1564		1553	1657		1582	1611		1533	1480	
Flt Permitted	0.51	1.00		0.46	1.00		0.24	1.00		0.72	1.00	
Satd. Flow (perm)	851	1564		747	1657		406	1611		1154	1480	
Peak-hour factor, PHF	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60
Adj. Flow (vph)	262	315	138	22	350	23	77	52	12	15	122	223
RTOR Reduction (vph)	0	12	0	0	2	0	0	9	0	0	93	0
Lane Group Flow (vph)	262	441	0	22	371	0	77	55	0	15	252	0
Confl. Peds. (#/hr)	9		23	23		9	7		19	19		7
Turn Type	Perm	NA		Perm	NA		Perm	NA		Perm	NA	
Protected Phases		6			2			8			4	
Permitted Phases	6			2			8			4		
Actuated Green, G (s)	59.5	59.5		59.5	59.5		20.5	20.5		20.5	20.5	
Effective Green, g (s)	59.5	59.5		59.5	59.5		20.5	20.5		20.5	20.5	
Actuated g/C Ratio	0.66	0.66		0.66	0.66		0.23	0.23		0.23	0.23	
Clearance Time (s)	5.0	5.0		5.0	5.0		5.0	5.0		5.0	5.0	
Vehicle Extension (s)	3.0	3.0		3.0	3.0		3.0	3.0		3.0	3.0	
Lane Grp Cap (vph)	562	1033		493	1095		92	366		262	337	
v/s Ratio Prot		0.28			0.22			0.03			0.17	
v/s Ratio Perm	c0.31			0.03			c0.19			0.01		
v/c Ratio	0.47	0.43		0.04	0.34		0.84	0.15		0.06	0.75	
Uniform Delay, d1	7.5	7.2		5.3	6.7		33.2	27.8		27.2	32.4	
Progression Factor	0.90	0.88		1.00	1.00		1.00	1.00		0.84	0.78	
Incremental Delay, d2	2.1	1.0		0.2	0.8		45.2	0.2		0.1	8.4	
Delay (s)	8.9	7.3		5.5	7.5		78.4	28.0		22.9	33.7	
Level of Service	А	Α		Α	Α		Е	С		С	С	
Approach Delay (s)		7.9			7.4			55.5			33.2	
Approach LOS		Α			Α			Е			С	
Intersection Summary												
HCM 2000 Control Delay			17.6	H	CM 2000	Level of S	Service		В			
HCM 2000 Volume to Capa	city ratio		0.56									
Actuated Cycle Length (s)			90.0		um of lost				10.0			
Intersection Capacity Utiliza	ation		77.1%	IC	U Level o	of Service			D			
Analysis Period (min)			15									
c Critical Lane Group												

HCM Signalized Intersection Capacity Analysis 6: Maryland Ave & Fleet St

	ၨ	→	•	•	←	•	4	†	<i>></i>	-	↓	4
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		₩.		ሻ		7		↑	7	ሻ	↑	
Traffic Volume (vph)	12	4	2	302	0	145	0	332	415	21	308	0
Future Volume (vph)	12	4	2	302	0	145	0	332	415	21	308	0
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)		4.5		4.5		4.5		4.5	4.5	4.5	4.5	
Lane Util. Factor		1.00		1.00		1.00		1.00	1.00	1.00	1.00	
Frpb, ped/bikes		0.99		1.00		0.97		1.00	0.96	1.00	1.00	
Flpb, ped/bikes		1.00		1.00		1.00		1.00	1.00	1.00	1.00	
Frt		0.98		1.00		0.85		1.00	0.85	1.00	1.00	
Flt Protected		0.97		0.95		1.00		1.00	1.00	0.95	1.00	
Satd. Flow (prot)		1579		1593		1376		1676	1363	1593	1676	
Flt Permitted		0.97		0.95		1.00		1.00	1.00	0.18	1.00	
Satd. Flow (perm)		1579		1593		1376		1676	1363	301	1676	
Peak-hour factor, PHF	0.71	0.71	0.71	0.71	0.71	0.71	0.71	0.71	0.71	0.71	0.71	0.71
Adj. Flow (vph)	17	6	3	425	0	204	0	468	585	30	434	0
RTOR Reduction (vph)	0	3	0	0	0	139	0	0	469	0	0	0
Lane Group Flow (vph)	0	23	0	425	0	65	0	468	116	30	434	0
Confl. Peds. (#/hr)	5		5	5		5	5		8	8		5
Turn Type	Split	NA		Prot		Perm		NA	Perm	pm+pt	NA	
Protected Phases	3	3		4				2		1	6	
Permitted Phases						4			2	6		
Actuated Green, G (s)		2.6		28.8		28.8		17.8	17.8	45.1	45.1	
Effective Green, g (s)		2.6		28.8		28.8		17.8	17.8	45.1	45.1	
Actuated g/C Ratio		0.03		0.32		0.32		0.20	0.20	0.50	0.50	
Clearance Time (s)		4.5		4.5		4.5		4.5	4.5	4.5	4.5	
Vehicle Extension (s)		4.0		2.0		2.0		5.0	5.0	3.0	5.0	
Lane Grp Cap (vph)		45		509		440		331	269	478	839	
v/s Ratio Prot		c0.01		c0.27				c0.28		0.02	c0.26	
v/s Ratio Perm						0.05			0.08	0.02		
v/c Ratio		0.51		0.83		0.15		1.41	0.43	0.06	0.52	
Uniform Delay, d1		43.1		28.4		21.8		36.1	31.7	13.3	15.1	
Progression Factor		1.00		1.19		3.79		1.00	1.00	1.00	1.00	
Incremental Delay, d2		12.5		10.1		0.1		203.3	5.0	0.3	2.3	
Delay (s)		55.6		43.9		82.9		239.4	36.6	13.6	17.4	
Level of Service		Е		D		F		F	D	В	В	
Approach Delay (s)		55.6			56.6			126.7			17.1	
Approach LOS		Е			Е			F			В	
Intersection Summary												
HCM 2000 Control Delay			82.1	H	CM 2000	Level of S	Service		F			
HCM 2000 Volume to Capacity	/ ratio		0.88									
Actuated Cycle Length (s)			90.0		um of lost				18.0			
Intersection Capacity Utilization	n		51.8%	IC	U Level	of Service	!		Α			
Analysis Period (min)			15									
c Critical Lane Group												

HCM Signalized Intersection Capacity Analysis 7: MD 355 & E Jefferson St

	۶	-	•	•	←	•	•	†	/	>	ţ	✓
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		ተ ኈ			^	7	ሽሻ	ተተተ		14	↑ ↑₽	
Traffic Volume (vph)	0	591	238	0	443	378	267	1003	0	535	847	61
Future Volume (vph)	0	591	238	0	443	378	267	1003	0	535	847	61
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)		9.0			9.0	9.0	8.0	8.0		9.0	9.0	
Lane Util. Factor		0.95			0.95	1.00	0.97	0.91		0.97	0.91	
Frpb, ped/bikes		1.00			1.00	1.00	1.00	1.00		1.00	1.00	
Flpb, ped/bikes		1.00			1.00	1.00	1.00	1.00		1.00	1.00	
Frt		0.96			1.00	0.85	1.00	1.00		1.00	0.99	
Flt Protected		1.00			1.00	1.00	0.95	1.00		0.95	1.00	
Satd. Flow (prot)		3048			3185	1425	3090	4577		3090	4523	
Flt Permitted		1.00			1.00	1.00	0.95	1.00		0.95	1.00	
Satd. Flow (perm)		3048			3185	1425	3090	4577		3090	4523	
Peak-hour factor, PHF	0.98	0.98	0.98	0.98	0.98	0.98	0.98	0.98	0.98	0.98	0.98	0.98
Adj. Flow (vph)	0	603	243	0	452	386	272	1023	0	546	864	62
RTOR Reduction (vph)	0	24	0	0	0	244	0	0	0	0	4	0
Lane Group Flow (vph)	0	822	0	0	452	142	272	1023	0	546	922	0
Confl. Peds. (#/hr)												5
Turn Type		NA			NA	Perm	Prot	NA		Prot	NA	
Protected Phases		4			8		1	5		6	2	
Permitted Phases						8						
Actuated Green, G (s)		51.0			51.0	51.0	25.0	76.0		27.0	78.0	
Effective Green, g (s)		51.0			51.0	51.0	25.0	76.0		27.0	78.0	
Actuated g/C Ratio		0.28			0.28	0.28	0.14	0.42		0.15	0.43	
Clearance Time (s)		9.0			9.0	9.0	8.0	8.0		9.0	9.0	
Vehicle Extension (s)		5.0			5.0	5.0	7.0	0.2		5.0	0.2	
Lane Grp Cap (vph)		863			902	403	429	1932		463	1959	
v/s Ratio Prot		c0.27			0.14		0.09	c0.22		c0.18	0.20	
v/s Ratio Perm						0.10						
v/c Ratio		0.95			0.50	0.35	0.63	0.53		1.18	0.47	
Uniform Delay, d1		63.3			53.9	51.4	73.2	38.7		76.5	36.3	
Progression Factor		0.84			1.00	1.00	1.00	1.00		1.00	1.00	
Incremental Delay, d2		17.6			2.0	2.4	5.9	1.0		101.1	0.8	
Delay (s)		71.0			55.9	53.8	79.0	39.7		177.6	37.1	
Level of Service		E			E	D	E	D		F	D	
Approach Delay (s)		71.0			54.9			48.0			89.2	
Approach LOS		E			D			D			F	
Intersection Summary												
HCM 2000 Control Delay			67.3	H	CM 2000	Level of S	Service		Ε			
HCM 2000 Volume to Capacity	ratio		0.78									
Actuated Cycle Length (s)			180.0		um of lost				26.0			
Intersection Capacity Utilization			86.8%	IC	U Level o	of Service			Е			
Analysis Period (min)			15									
c Critical Lane Group												

04/14/2023

Intersection: 1: Monroe St & E Middle Ln

Movement	EB	EB	WB	WB	NB	
Directions Served	Т	TR	T	Т	R	
Maximum Queue (ft)	23	12	37	18	40	
Average Queue (ft)	1	0	4	1	22	
95th Queue (ft)	12	6	24	9	46	
Link Distance (ft)	640	640	187	187		
Upstream Blk Time (%)						
Queuing Penalty (veh)						
Storage Bay Dist (ft)						
Storage Blk Time (%)						
Queuing Penalty (veh)						

Intersection: 2: Monroe St & E Montgomery Ave

Movement
Directions Served
Maximum Queue (ft)
Average Queue (ft)
95th Queue (ft)
Link Distance (ft)
Upstream Blk Time (%)
Queuing Penalty (veh)
Storage Bay Dist (ft)
Storage Blk Time (%)
Queuing Penalty (veh)

Intersection: 3: Monroe St & Monroe PI

ovement
rections Served
aximum Queue (ft)
erage Queue (ft)
th Queue (ft)
sk Distance (ft)
stream Blk Time (%)
euing Penalty (veh)
orage Bay Dist (ft)
orage Blk Time (%)
euing Penalty (veh)

04/14/2023

Intersection: 4: Monroe St & E Jefferson St

Movement	EB	EB	EB	WB	WB	WB	NB	NB	SB	SB	
Directions Served	L	Т	TR	L	Т	TR	Т	R	L	TR	
Maximum Queue (ft)	88	222	276	150	375	386	136	108	73	162	
Average Queue (ft)	36	104	139	69	177	199	59	39	14	80	
95th Queue (ft)	69	181	240	148	335	350	111	80	47	135	
Link Distance (ft)		546	546		883	883		432			
Upstream Blk Time (%)											
Queuing Penalty (veh)											
Storage Bay Dist (ft)	250			125			225		150		
Storage Blk Time (%)		0		0	13					0	
Queuing Penalty (veh)		0		1	12					0	

Intersection: 5: Monroe St & Fleet St

Movement	EB	EB	WB	WB	NB	NB	SB	SB
Directions Served	L	TR	L	TR	L	TR	L	TR
Maximum Queue (ft)	124	246	29	196	74	144	68	125
Average Queue (ft)	59	95	6	87	46	46	26	54
95th Queue (ft)	108	192	24	164	78	107	60	101
Link Distance (ft)		361	580	580		528		432
Upstream Blk Time (%)		0						
Queuing Penalty (veh)		0						
Storage Bay Dist (ft)	100				50		175	
Storage Blk Time (%)	1	4			21	8		
Queuing Penalty (veh)	5	7			12	6		

Intersection: 6: Maryland Ave & Fleet St

Movement	EB	WB	WB	NB	NB	SB	SB
Directions Served	LTR	L	R	Т	R	L	Т
Maximum Queue (ft)	33	246	297	223	123	77	118
Average Queue (ft)	4	166	73	117	26	24	47
95th Queue (ft)	19	252	176	192	81	54	98
Link Distance (ft)	141		361	646			432
Upstream Blk Time (%)			0				
Queuing Penalty (veh)			0				
Storage Bay Dist (ft)		225			450	125	
Storage Blk Time (%)		2	0				0
Queuing Penalty (veh)		4	0				0

04/14/2023

Intersection: 7: MD 355 & E Jefferson St

Movement	EB	EB	WB	WB	WB	NB	NB	NB	NB	NB	SB	SB
Directions Served	Т	TR	T	Т	R	L	L	Т	T	T	L	L
Maximum Queue (ft)	264	314	379	354	33	128	184	250	230	183	223	259
Average Queue (ft)	109	126	246	221	3	34	81	160	138	73	106	158
95th Queue (ft)	201	246	351	334	18	107	153	235	217	168	208	224
Link Distance (ft)	883	883	941	941	941			760	760	760		
Upstream Blk Time (%)												
Queuing Penalty (veh)												
Storage Bay Dist (ft)						275	275				425	425
Storage Blk Time (%)								0				
Queuing Penalty (veh)								0				

Intersection: 7: MD 355 & E Jefferson St

Movement	SB	SB	SB
Directions Served	Т	T	TR
Maximum Queue (ft)	382	365	300
Average Queue (ft)	256	240	175
95th Queue (ft)	356	328	259
Link Distance (ft)	658	658	658
Upstream Blk Time (%)			
Queuing Penalty (veh)			
Storage Bay Dist (ft)			
Storage Blk Time (%)			
Queuing Penalty (veh)			

Network Summary

Network wide Queuing Penalty: 49

Queuing Penalty (veh)

04/14/2023

Intersection: 1: Monroe St & E Middle Ln

Movement	EB	EB	WB	WB	NB
Directions Served	T	TR	T	Т	R
Maximum Queue (ft)	39	12	40	18	55
Average Queue (ft)	3	1	5	1	27
95th Queue (ft)	20	8	25	8	50
Link Distance (ft)	640	640	187	187	
Upstream Blk Time (%)					
Queuing Penalty (veh)					
Storage Bay Dist (ft)					
Storage Blk Time (%)					

Intersection: 2: Monroe St & E Montgomery Ave

Movement Directions Served Maximum Queue (ft) Average Queue (ft) 95th Queue (ft) Link Distance (ft) Upstream Blk Time (%) Queuing Penalty (veh) Storage Bay Dist (ft) Storage Blk Time (%) Queuing Penalty (veh)

Intersection: 3: Monroe St & Monroe PI

ovement
rections Served
aximum Queue (ft)
erage Queue (ft)
th Queue (ft)
sk Distance (ft)
stream Blk Time (%)
euing Penalty (veh)
orage Bay Dist (ft)
orage Blk Time (%)
euing Penalty (veh)

04/14/2023

Intersection: 4: Monroe St & E Jefferson St

Movement	EB	EB	EB	WB	WB	WB	NB	NB	SB	SB	
Directions Served	L	Т	TR	L	Т	TR	Т	R	L	TR	
Maximum Queue (ft)	134	280	277	150	368	371	104	169	142	225	
Average Queue (ft)	29	160	149	58	216	236	44	76	51	120	
95th Queue (ft)	80	245	240	145	322	335	96	142	105	201	
Link Distance (ft)		546	546		883	883		432			
Upstream Blk Time (%)											
Queuing Penalty (veh)											
Storage Bay Dist (ft)	250			125			225		150		
Storage Blk Time (%)		1		0	16					6	
Queuing Penalty (veh)		0		0	8					4	

Intersection: 5: Monroe St & Fleet St

Movement	EB	EB	WB	WB	NB	NB	SB	SB
Directions Served	L	TR	L	TR	L	TR	L	TR
Maximum Queue (ft)	121	203	42	150	71	83	67	230
Average Queue (ft)	55	60	6	49	35	28	6	78
95th Queue (ft)	105	130	27	111	67	68	37	158
Link Distance (ft)		361	580	580		528		432
Upstream Blk Time (%)								
Queuing Penalty (veh)								
Storage Bay Dist (ft)	100				50		175	
Storage Blk Time (%)	1	1			10	6		1
Queuing Penalty (veh)	4	2			4	3		0

Intersection: 6: Maryland Ave & Fleet St

Movement	EB	WB	WB	NB	NB	SB	SB
Directions Served	LTR	L	R	Т	R	L	Т
Maximum Queue (ft)	56	248	278	353	68	59	184
Average Queue (ft)	15	171	71	186	10	11	71
95th Queue (ft)	42	257	181	303	42	40	146
Link Distance (ft)	141		361	646			432
Upstream Blk Time (%)			0				
Queuing Penalty (veh)			0				
Storage Bay Dist (ft)		225			450	125	
Storage Blk Time (%)		3					2
Queuing Penalty (veh)		5					0

04/14/2023

Intersection: 7: MD 355 & E Jefferson St

Movement	EB	EB	WB	WB	WB	NB	NB	NB	NB	NB	SB	SB
Directions Served	Т	TR	Т	Т	R	L	L	Т	Т	Т	L	L
Maximum Queue (ft)	525	568	299	281	150	198	300	449	378	286	437	450
Average Queue (ft)	280	325	164	138	22	89	164	262	236	174	426	444
95th Queue (ft)	454	504	261	236	89	185	289	399	345	277	475	475
Link Distance (ft)	883	883	941	941	941			760	760	760		
Upstream Blk Time (%)												
Queuing Penalty (veh)												
Storage Bay Dist (ft)						275	275				425	425
Storage Blk Time (%)						0	0	6			10	67
Queuing Penalty (veh)						0	0	15			28	190

Intersection: 7: MD 355 & E Jefferson St

Movement	SB	SB	SB
Directions Served	Т	Т	TR
Maximum Queue (ft)	704	652	452
Average Queue (ft)	628	422	256
95th Queue (ft)	858	706	414
Link Distance (ft)	658	658	658
Upstream Blk Time (%)	68	0	
Queuing Penalty (veh)	0	0	
Storage Bay Dist (ft)			
Storage Blk Time (%)	1		
Queuing Penalty (veh)	5		


Network Summary


Network wide Queuing Penalty: 268


Fleet and Monroe Streets, Complete Streets Study APPENDICES




Appendix C: Conceptual Plans













RFP #27-25 Fleet Street and Monroe Complete Streets Project









RFP #27-25
Fleet Street and Monroe Complete Streets Project
ATTACHMENT A






RFP #27-25
Fleet Street and Monroe Complete Streets Project
ATTACHMENT A



RFP #27-25 Fleet Street and Monroe Complete Streets Project



Fleet and Monroe Streets, Complete Streets Study APPENDICES



Appendix D: Cost Breakdown

			units					
				units				
Construction Element	Unit	Unit Cost	bike path	cycletrack	combination			
10' wide path with 4' grass buffer	LF	\$ 100.00	2350	530	1600			
Relocate Utility Pole or Light Pole	each	\$ 10,000.00	2	2	2			
Relocate sign pole	each	\$ 100.00	10	10	10			
Curb and Gutter	LF	\$ 50.00	2500	600	1750			
Sidewalk Removal	SF	\$ 5.00	0	0	0			
Pavement Removal	SF	\$ 7.00	32000	7000	20000			
Prefab Concrete curb buffer	LF	\$ 65.00	0	1750	750			
Inlet Relocation	each	\$ 25,000.00	8	2	6			
Driveway reconstruction	each	\$ 5,000.00	9	0	5			
Pedestrian Signals	each	\$ 10,000.00	0	2	0			
SUBTOTAL								
MOT	10% of total							
Landscaping	5% of total							
Mobilization	5% of total		_		_			

Planning Level Construction Cost										
bike path		cycletrack	combination							
\$ 235,000.00	\$	53,000.00	\$	160,000.00						
\$ 20,000.00	\$	20,000.00	\$	20,000.00						
\$ 1,000.00	\$	1,000.00	\$	1,000.00						
\$ 125,000.00	\$	30,000.00	\$	87,500.00						
\$ -	\$	-	\$	-						
\$ 224,000.00	\$	49,000.00	\$	140,000.00						
\$ -	\$	113,750.00	\$	48,750.00						
\$ 200,000.00	\$	50,000.00	\$	150,000.00						
\$ 45,000.00	\$	-	\$	25,000.00						
\$ -	\$	20,000.00	\$	-						
\$ 850,000.00	\$	336,750.00	\$	632,250.00						
\$ 85,000.00	\$	33,675.00	\$	63,225.00						
\$ 42,500.00	\$	16,837.50	\$	31,612.50						
\$ 42,500.00	\$	16,837.50	\$	31,612.50						

Grand Total

\$ 1,020,000.00 \$ 404,100.00 \$ 758,700.00

Fleet and Monroe Streets, Complete Streets Study APPENDICES



Appendix E: Public Presentation

Fleet and Monroe Streets

Complete Streets



May 4th, 2023



Introduction / Presentation Outline

Funding Source: MWCOG TLC grant


- Purpose & Need / Project Limits
- Constraints & Opportunities
- Concepts
- Impacts
- Next Steps
- Q&A





Purpose & Need

- Expansion of biking & walking facilities from Town Center core
- Connecting Middle Lane Protected Bike Lanes to Fleet Street and to RMHS and Rockville Metro Station
- Providing dedicated walking and biking facilities, separated from vehicle traffic
 - · Sidewalk and bike path
 - Wide shared use path
 - Sidewalk and protected cycletrack
- Goal: Buy-in on a concept
 - 1) Confirm general design concept
 - 1) <u>Proof of concept</u> (no fatal flaws, traffic congestion mitigated, etc.)
 - 2) Design assumptions addressed during next stage





Constraints & Opportunities

- Constraints
 - Narrow Public Right-of-Way
 - Narrow travel lanes (11' to 12')
 - Curbside on-street parking in Town Center is desirable
- Opportunities
 - Select areas of extra roadway capacity → Opportunity for repurposing travel lanes
 - Grid network allows traffic diversions

Improved safety & connectivity will reduce vehicle demand for

short trips






MONROE ST

5

General Discussion of Options

- Side path to replace travel lane
- 2-way cycletrack to replace travel lane
- Combination of each
 - Path on Monroe St
 - driveway conflicts
 - increased activity density
 - Cycletrack on Fleet St





Curbside bike lanes on each side of road was dismissed. Too narrow.
Unbuffered. unprotected

Concepts

- General layout of Each Facility Type
 - Bike-only side path
 - Two-way Cycletrack
- Preserves existing sidewalk
- Dedicated facility for bikes and micromobility, e.g., scooters
- Lane Repurposing to calm vehicle traffic



Page 184 of 210


Details and Options for Discussion

- Driveways
- Intersection crossings
 - Fleet St. / Monroe St.
 - Jefferson St. / Monroe St.
- Termination points / Tying into existing infrastructure
- Bus stop
- Traffic impacts
- Construction Cost
- Curbside parking spaces



Backing up onto Fleet St

- Adjustments to vertical barriers as need to reflect Turning Movement
 - Drivers will need wider clearance to execute backing maneuvers from driveway



Crossing Fleet / Monroe with WALK

Shared pedestrian-bike crossing / no signal phase changes

- Geometric changes desirable to push cyclists into viewshed of southbound right-turning vehicles. Add LPI
- Separated (but simultaneous) bike & pedestrian crossings
 - Protected intersection & LPI
 - · Slows vehicles and cyclists at conflict point





Applicable where turn volumes are low





9

Crossing Jefferson (MD 28)



- Bike signals not currently permitted on MDOT SHA roads.
- Per Current SHA standards, bikes can cross with a protected WALK phase. NB protected Left-turn and SB through-rights would have to be held.
 - 1) allow NB through-rights concurrently / SB left permitted
 - 2) restrict left turns and NB is 1 through and 1 right lane
- Shared pedestrian-bike crossing
 - Geometric changes desirable to push cyclists to be more in the viewshed of southbound right-turning vehicles
 - Leading Pedestrian Interval
 - Still would need SHA Concurrence








Southern Termini

At Fleet/Maryland

 All bike lane/path options have infrastructure terminating at a raised and widened landing area at the southeast corner of Fleet/Maryland

At RMHS

 Side path or 2-way facility turns blends into existing side path, just to the west of existing crosswalk across Fleet St and Richard Montgomery High School









Terminus Options at East Middle Lane

- Both options employ a side path north of Monroe Place
 - However, Curbside Parking on both sides and two-traffic limit space
- North of Montgomery Ave only 100 cars/day southbound
 - Remove SB lane / Retains curbside parking
 - Optionally, keep SB travel lanes at expense of curbside parking








Accommodating Bus Stop Crossings

- All bus stops remain at current locations
- Bus stops are:
 - widened to allow alighting from both bus doors
 - raised to provide a bus stop level with sidewalk
- Bus boarders cross sidewalk and side path / bicycle lanes
 - raised bus stop, pavement markings, and signs indicate that bicyclists are encroaching on bus stop space and must yield to transit riders





Traffic Impacts: LOS AM (PM)

Intersection	Existing Conditions	Bike Path	2-way Cycletrack e <i>xclusive</i> WALK at MD 28	Cycletrack with concurrent NB traffic at MD 28
Monroe St & E Middle Ln	A (B)	A (B)	A (B)	A (B)
Monroe St & E Montgomery Ave	A (A)	A (A)	A (A)	A (A)
Monroe St & Monroe PI	A (A)	A (A)	A (A)	A (A)
Monroe St & E Jefferson St	B (C)	B (C)	C (D)	C (C)
Monroe St & Fleet St	B (B)	B (B)	B (B)	B (B)
Maryland Ave & Fleet St	C (E)	C (E)	C (E)	C (E)







Spare Capacity on Monroe allows for conversion to one lane in each direction with a center left-turn lane and minimal impact

Construction Cost

- Path Only Option
 - \$1,000,000
- Primary 2-way Cycletrack Option
 - \$400,000


Lost Parking

- All Options will remove 7 spaces on Fleet St, east of Monroe St
- Option for 4 spaces removed on Monroe St between Monroe Place and Montgomery Ave
- Option for 5 spaces removed on Monroe St between Montgomery Ave and Middle Lane

Optionally-lost spaces would be due to retaining two-way driving operations



Next Steps / Project Flow



Federal and State Grant Opportunities



Questions & Feedback

- City of Rockville, Project Manager
 - Bryan Barnett-Woodsbbwoods@rockvillemd.gov (240) 314-8527
- Mead & Hunt, Engineering Consultant
 - Bryon White, PEbryon.white@meadhunt.com, (443) 741-3652
- MWCOG Liasion
 - Justine Velez <u>jvelez@mwcog.org</u>





CITY OF ROCKVILLE MARYLAND GENERAL CONDITIONS AND INSTRUCTIONS

1. <u>TERMS AND CONDITIONS</u> The terms and conditions of this **Attachment B** govern in event of conflict with any terms of the offeror's proposal and are not subject to change by reasons of written or verbal statement by the Contractor unless accepted in writing. Words and abbreviations that have well known technical or trade meanings are used in accordance with such meanings.

In the event of a conflict between the terms, conditions and instructions of this **Attachment B** and the Federal And State Of Maryland General Conditions contained on Page 4 of this document, the Federal and State of Maryland terms, conditions and instructions shall prevail.

- 2. <u>SEVERABILITY</u> If one or more provisions of any subsequent agreement, or the application of any provision to any party or circumstance, is held invalid, unenforceable, or illegal in any respect, the remainder of the agreement and the application of the provision to other parties or circumstances shall remain valid and in full force and effect.
- 3. <u>PREPARATION</u> All bids are to be submitted electronically, in a pdf format file, via a City designated bid receipt software solution. File name of the pdf document must contain the RFP Number, Offeror's Name and the Proposal Due Date.

Conditional bids/proposals and bids/proposals containing escalator clauses will not be accepted. Bids/proposals must be signed (electronic signature is acceptable) by an individual authorized to bind the offeror.

- **4.** <u>LATE BIDS/PROPOSALS</u> It is the offeror's responsibility to assure delivery of the proposal at the proper time via the designated electronic, software solution. Proposals delivered in any other fashion will not be considered.
- 5. PROPOSAL AWARD The award will be made to the offeror whose proposal, in the opinion of the City is the best taking into consideration all aspects of the offeror's responses. In the event that the offeror to whom the award is made does not execute a contract within 15 days from receipt of the contract, the City may give notice to such offeror of intent to award the contract to the next most qualified offeror, or to call for new proposals.
- **ADDENDUM** In the event that any addenda to this solicitation is issued, all solicitation terms and conditions will retain in effect unless they are specifically changed in the addendum. It is the responsibility of the bidder/proposer to make inquiry as to addenda issued. Oral answers to questions relative to interpretation of specifications or the proposal process will not be binding on the City. Such addendums, if issued, will posted at: https://www.rockvillemd.gov/bids.aspx and https://emma.maryland.gov/.

Please note, that it is the bidder's/proposer's responsibility to check this site frequently for Addendums, which may impact pricing, this document's requirements, terms and/or conditions. Failure to

acknowledge an addendum on the proposal form or to sign and return an Addendum with your response may result in disqualification of proposal.

- 7. ACCEPTANCE/REJECTION OF BIDS The City reserves the right to reject any or all bids in part or full and to waive any technicalities or informalities as may best serve the interests of the City. Bids shall be valid for a minimum of 120 days following the deadline for submitting offers. Bids may not be withdrawn during that period. If an award is not made during that period, all offers shall be automatically extended for another 120 days. Offers will be automatically renewed until such time as either an award is made or proper notice is given to the Purchasing Agent of Offeror's intent to withdraw its offer. Offers may only be canceled by submitting Notice at least 15 days before the expiration of the then current 120-day period.
- **8.** <u>MULTI-YEAR BIDS</u> Multi-year contracts may be continued each fiscal year only after funding appropriations have been granted. In the event necessary funding appropriation is not granted, the multi year contract shall be null and void, effective July 1st of the affected year.
- 9. <u>BID/PROPOSAL WITHDRAWAL</u> Proposals may be electronically withdrawn (deleted) or modified by deleting the initial file uploaded and replacing it with a modified file using the City's electronic, software solution before the time specified.
- 10. <u>MISTAKES</u> Offerors/proposers are expected to be thoroughly familiar with all solicitation documents, including all addenda. No consideration will be granted for any alleged misunderstanding of the intent of the specifications. Each bidder/proposer shall carefully and thoroughly examine these documents for completeness. No claim of any bidder/proposer will be allowed on the basis that these documents are incomplete.
- 11. SENSITIVE DOCUMENTS Sensitive documents (either electronic or hardcopy documents dealing with critical facilities or sensitive information) received from the City must be handled consistent with the terms of non-disclosure required for application. Contractor is responsible to restrict use of sensitive documents to project participants only and shall take appropriate measure to prevent distribution of sensitive document to anyone inside or outside of the Contractor's company except Contractor's project participants. After completion of the project, all sensitive documents remaining in the Contractor's possession shall continue to be governed under the terms of non-disclosure and must continue to be store in a secure manner. After such records are no longer need for record purposes, the records shall be destroyed or returned to the City.

Where services require the Contractor to access the City's electronic information resources and/or its electronic data assets, the Contractor shall adhere to all requirements, terms and conditions of the City's Contractor/Vendor On-Site and Remote Access Confidentiality Agreement, which can be viewed at the following web address:

https://www.rockvillemd.gov/DocumentCenter/View/36407/IT-ACCESS-CONFIDENTIALITY-POLICY?bidId=

12. <u>DOCUMENTS, MATERIALS AND DATA</u> All documents materials or data developed as a result of this contract are the City's property. The City has the right to use and reproduce any documents, materials and data, including confidential information, used in the performance of, or developed as a result of this contract. The City may use this information for its own purposes, including reporting to state and federal agencies. The contractor warrants that it has title to or right to use all documents, materials or data used or developed in connection with this contract. The Contractor must keep confidential all documents, materials and data prepared or developed by the contractor or supplied by the City.

- 13. <u>PUBLICITY</u> Contractor agrees that it shall not publicize any subsequent agreement or disclose, confirm or deny any details thereof to third parties or use any photographs or video recordings of the City of Rockville's name in connection with any sales promotion or publicity event without the prior express written approval of the City.
- 14. INTEREST IN MORE THAN ONE BID/PROPOSAL AND COLLUSION Multiple proposals uploaded/received in response to a single solicitation from an individual, firm, partnership, corporation, affiliate, or association under the same or different names will be rejected. Reasonable grounds for believing that an offeror is interested in more than one proposal for a solicitation both as an offeror and as a subcontractor for another offeror, will result in rejection of all proposals in which the offeror is interested. However, a firm acting only as a subcontractor may be included as a subcontractor for two or more offerors submitting a proposal for the work. Any or all proposals may be rejected if reasonable grounds exist for believing that collusion exists among any offerors. Offerors rejected under the above provisions shall be disqualified if they respond to a re-solicitation for the same work.
- **15. EXECUTION OF CONTRACT** The Contractor shall be required to execute a formal agreement with the City within fifteen days from the award.
- **16. COMPENSATION** Refer to Section 4 Payment
- 17. <u>INVOICING</u> The Contractor shall submit invoices, in duplicate, which shall include a detailed breakdown of all charges for that monthly period including employee names, date of services, itemized cost (hours and hourly rates) for service.

Invoices shall be based upon completion of tasks and deliverables consistent with the schedule of payments stipulated in the Contract, and shall reference a City Purchase Order number. All such invoices will be paid promptly by the City of Rockville unless any items thereon are disputed in which event payment will be withheld pending verification of the amount claimed and the validity of the claim. The firm shall provide complete cooperation during any such investigation. All invoices shall be forwarded to the following address: City of Rockville, Attn: (Project Manager),111 Maryland Avenue, Rockville, MD 20850 or via email to the project manager.

18. ELECTRONIC PAYMENT OPTION The Vendor ACH Payment Program of the City allows payments to be deposited directly to a designated financial institution account. Funds will be deposited into the account of your choice automatically and on time. All transactions are conducted in a secure environment. The program is totally free as part of the Finance Department's efforts to improve customer services. Program information and registration can be viewed at the following web address:

http://www.rockvillemd.gov/index.aspx?nid=234

- 19. <u>PAYMENT TO SUBCONTRACTOR</u> Within seven (7) days after receipt of amounts paid by the City for work performed by a subcontractor under this contract, the Contractor shall either: Pay the Subcontractor for the proportionate share of the total payment received from the City of Rockville attributable to the work performed by the Subcontractor under this contract; or Notify the City of Rockville and Subcontractor, in writing, of his/her intention to withhold all or a part of the Subcontractor's payment and the reason for non-payment.
- **20.** <u>PERSONNEL</u> Principal or key personnel included in the proposal may not be substituted without written approval of the City of Rockville. Replacements for key personnel under the contract must have equivalent professional qualifications and experience as those individuals listed in the proposal.

The Consultant must submit written professional qualifications and experience for approval within ten working days prior to replacement for City review and approval or rejection.

- 21. PRICE ADJUSTMENTS (CPI) Unless otherwise stated in the RFP document, rates quoted are to be firm for two (2) years after award of a contract. These rates will apply to additional work, change orders and contract modifications. A request for price adjustment after the 2-year period is subject to approval or rejection by the Purchasing Agent. The Consultant shall submit to the Purchasing Agent sufficient justification to support the Consultant's request. A request for price adjustment may not be approved which exceeds the amount of the annual percentage change of the Consumer Price Index (CPI) for the twelve-month period immediately prior to the date of the request.
- **22. INTERPRETATION** Any questions concerning general instruction and specifications shall be directed in writing to the Procurement Division. The submission of a bid/proposal shall be prima facie evidence that bidder/proposer thoroughly understands the terms of the specification. The Contractor shall take no advantage of any error or omission in the specifications.
- 23. <u>DELIVERY</u> All time limits stated in the contract documents are of the essence. The Contractor shall expedite the work and achieve substantial completion within the contract time. If time limits are not specified, state the number of days required to make delivery/completion in the space provided. Defective or unsuitable materials or workmanship shall be rejected and shall be made good by the Contractor, notwithstanding that such materials/workmanship have been previously overlooked and accepted.
- **24. <u>DELAYS/EXTENSION OF TIME</u>** If the Contractor is delayed in the delivery of the supplies, equipment or services by any act or neglect of the City or by a separate Contractor employed by the City, or by any changes, strikes, lockouts, fires, unusual delays in transportation or delay authorized by the City, the City shall review the cause of such delay and shall make an extension if warranted.
 - All claims for extensions must be a written notice sent to the Purchasing Agent within ten (10) calendar days after the date when such alleged cause for extension of time occurred. All such claims shall state specifically the amount of the delay the Contractor believes to have suffered. If statement is not received within the prescribed time the claim shall be forfeited and invalidated.
- **25. TERMINATION FOR DEFAULT** The contract may be cancelled or annulled by the City in whole or in part by written notice of default to the Contractor upon nonperformance or violation of contract terms and an award may be made to second ranked proposer, if default occurs within the initial contract period and the second ranked proposer agrees to hold its proposal price, or the work may be purchased on the open market similar to those so terminated. In either event, the defaulting Contractor (or his surety) shall be liable to the City for costs to the City in excess of the defaulted contract prices.
- **26.** TERMINATION FOR CONVENIENCE The performance of work or services under this contract may be terminated in whole or part, upon five (5) calendar day's written notice when the City determines that such termination is in its best interest. The City shall be liable only for those accepted goods and/or services furnished prior to the effective date of such termination.
- **27. ABANDONMENT, DISSOLUTION AND RESTRUCTING** A Contractor who abandons or defaults the work on this contract and causes this contract to be re-bid will not be considered in future bids for the same type of work unless the scope of the work is significantly changed. Written notification of changes to company name, address, telephone number, etc. shall be provided to the City of Rockville as soon as possible but not later than thirty (30) days from date of change.

28. <u>CHANGES</u> The City, without invalidating the contract, may order written changes in the scope of work consisting of additions, deletions or modification with the contract sum and time being adjusted accordingly. All such changes shall be made in writing by the Purchasing Agent.

Costs shall be limited to the following: cost of materials, cost of labor and additional costs of supervision and field office personnel directly attributable to the change.

The cost or credit to the City from a change in the scope of work shall be determined by mutual agreement. The Contractor shall do all work that may be required to complete the work contemplated at the unit prices or lump sum to be agreed upon.

No alterations or variables in the terms of the contract shall be valid or binding upon the City unless made in writing and signed by the City.

29. EXTRA COSTS If the Contractor claims that any instructions by drawings or otherwise involve extra cost or extension of time, a written request must be submitted to the Project Manager within ten (10) calendar days after receipt of such instructions and before proceeding to execute the work, stating in detail the basis for objection. No such claim will be considered unless so made.

Any discrepancies which may be discovered between actual conditions and those represented by the specifications and/or drawings shall be reported to the City and work shall not proceed, until written instruction has been received by the Contractor from the City. On drawings the figured dimensions shall govern in the case of discrepancy between the scales and figures.

Anything shown on applicable plans and not mentioned in the specifications or mentioned in the specifications and not shown on the plans have the same effect as if shown or mentioned respectively on both.

30. GUARANTEE All guarantees and warranties required shall be furnished by the Contractor and shall be delivered to the Project Manager before final payment is made.

The Contractor guarantees that the items conform to the design and specifications and to drawings, samples or other descriptions referred to in this document. The Contractor further guarantees the items will be free from defects in materials and workmanship, latent or patent and are suitable for the intended purpose as far as the Contractor knows or has reason to know. The guarantee contained herein shall remain in full force and effect for a minimum of one year after initial delivery to the City unless another effective period is specified.

- 31. **RIGHT TO AUDIT** At any time during the term of any subsequent agreement and for a period of four (4) years thereafter the City of Rockville or duly authorized audit representative of the City, at its expense and at reasonable times, reserves the right to incrementally audit Contractor's records. In the event such an audit by the City reveals any errors/overpayments by the City, Contractor shall refund the City the full amount of such overpayments within thirty (30) days of such audit findings, or the City at its option, reserves the right to deduct such amounts owing the City from any payments due Contractor.
- **32.** <u>DEFECTIVE SUPPLIES/SERVICE</u> Defective or unsuitable materials or workmanship shall be rejected and shall be made good by the Contractor. Contractor shall be responsible for the professional quality, technical accuracy, timely completion, and the coordination of all its effort and other services furnished by Contractor under the Agreement. Without additional compensation, Contractor shall correct or revise any errors, omissions, or other deficiencies in all products of its efforts and other

services provided. This shall include resolving any deficiencies arising out of the acts or omissions of Contractor found during or after the course of the services performed by or for Contractor under this Agreement, regardless of City having knowledge of or condoning/accepting the products or the services. Correction of such deficiencies shall be at no cost to City.

- **33.** <u>LEGAL REQUIREMENTS</u> All materials, equipment, supplies and services shall conform to applicable Federal, State County and City laws, statutes, rules and regulations. The Contractor shall observe and comply with all Federal, State, County and City laws, statutes, rules and regulations that affect the work to be done. The provisions of this contract shall be governed by the laws of the State of Maryland.
- **34.** <u>SUBCONTRACTING</u> When allowed, proposers who intend to subcontract any portion of the work including delivery, installation or maintenance will submit to the City prior to the start of work: 1) a description of the items to be subcontracted; 2) all subcontractor names, addresses and telephone numbers; and 3) the nature and extent of the work utilized during the life of the contract.

This does not relieve the Contractor from the prime responsibility of full and complete performance under the contract. There shall be no contractual relationship between the City and any subcontractor.

35. RESERVATIONS The City reserves the right to add or delete any item(s) from the proposal in whole or in part at the City's discretion without affecting the proposal prices for any item or remaining work.

The City may waive minor differences in specifications in proposals provided these differences do not violate the specifications' intent nor materially affect the operation for which the items are being purchased.

- 36. <u>AUTHORITY OF THE CITY MANAGER IN DISPUTES</u> Except as may otherwise be provided by the final agreement, any dispute concerning a question of fact arising under the agreement signed by the City and the Contractor which is not disposed of by the final agreement shall be decided by the City Manager who shall notify the Contractor in writing of his determination. The Contractor shall be afforded the opportunity to be heard and offer evidence in support of the claim. Pending final decision of the dispute herein, the Contractor shall proceed diligently with performance under the agreement signed by the City and the Contractor. The decision of the City Manager shall be final and conclusive unless an appeal is taken pursuant to City Purchasing Ordinance.
- **37. INDEMNIFICATION OF THE COUNCIL** The Contractor shall indemnify and save harmless the Mayor and Council from all suits, actions and damages or costs, of every name and description to which the Mayor and Council may be subjected or put by reason of injury to persons or property as a result of the work, whether caused by negligence or carelessness on part of the Contractor, or subcontractors or agents of the Contractor.
- **38. NO LIMITATION OF LIABILITY** The mention of any specific duty or liability of the Contractor in any part of the specification shall not be construed as a limitation or restriction upon any general liability or duty imposed upon the Contractor.
- 39. PROPRIETARY INFORMATION The City agrees, to the extent permitted by law, to hold all material and information belonging to the offeror, which it deems to be confidential, in strictest confidence. The Contractor agrees to hold all material and information belonging to the City or the City's agents in strictest confidence and not to make use thereof other than for the performance of contractual obligations, to release it only to employees requiring such information. Reasonable precautions will be exercised for the protection of any proprietary data included in the proposal.

- **40. RELEASE OF INFORMATION** During the term of the final agreement, the successful Contractor shall not release any information related to the services or the performance of the services under the agreement nor publish any final reports or documents without the prior written approval of the City.
- 41. <u>PATENTS AND ROYALTIES</u> Whenever any article, material, appliance, process composition, means or things called for by these specifications is covered by Letter of Patent, the successful offeror must secure, before using or employing such materials, the assent in writing of the owner or licensee of such letters of patent, and file the same with the City.

The Contractor will defend, at its own expense, and will pay the cost and damages awarded in any action brought against the City based on any allegation that the items provided by the Contractor infringe on a patent and copyright license or trade secret. In the event that an injunction shall be obtained against the City's use of items by reason of infringement of any patent, copyright, license or trade secret, the Contractor will, at its expense, procure for the City the right to continue using the items, replace or modify the same so that it becomes non-infringing.

42. MISCELLANEOUS PROVISIONS The City and the Contractor each bind themselves, their partners, successors, assign and legal representatives of such other parties in respect to all covenants, agreements, and obligations contained in the contract document. Neither party to the contract shall assign the contract or sublet it as a whole without the written consent of the other, nor shall the Contractor assign any monies due or to become due hereunder without the previous written consent of the City. Written notice shall be deemed to have been duly served if delivered in person to the individual or member of the firm or to any officer of the corporation for whom it was intended if delivered or sent by registered or certified mail to the last known address.

Duties and obligations imposed by the contract documents and the rights and remedies available thereunder shall be in addition to and not a limitation of the duties, obligations, rights and remedies otherwise imposed or available by law, unless so indicated.

- 43. ETHICS REQUIREMENTS In accordance with the City's financial disclosure and ethical conduct policy and/or ordinances a prerequisite for payment pursuant to the terms of this contract is that the Contractor may be required to furnish explicit statements, under oath, that the City Manager, and/or any other officer, agent, and/or employee of the City, and any member of the governing body of the City of Rockville or any member or employee of a Commission, Board, or Corporation controlled or appointed by the City Council, Rockville, Maryland has not received or has not been promised directly or indirectly any financial benefit by way of fee, commission, finder's fee, or in any other manner, remuneration arising from directly or indirectly related to this contract, and that upon request by the City Manager, or other authorized agent, as a prerequisite to payment pursuant to the terms of this contract, the Contractor will furnish to the Mayor and Council of the City of Rockville, under oath, answers to any interrogatories to a possible conflict of interest has herein embodied.
- **44. BROKERING** The Contractor warrants that only an established commercial or selling agency maintained by the Contractor for the purpose of securing business may be retained to solicit or secure this contract. Any brokerage arrangements must be disclosed in the proposal. For violation of this warranty, the City shall have the right to terminate or suspend this contract without liability to the City.
- **45. EQUAL EMPLOYMENT OPPORTUNITY** The Contractor will not discriminate against any employee or applicant for employment because of age (in accordance with applicable law), ancestry, color, national origin, race, ethnicity, religion, disability, genetics, marital status, pregnancy, presence of children, gender, sexual orientation, gender identity or expression, or veteran status. The Contractor will take affirmative action to ensure that applicants are employed, and the employees are treated fairly

and equally during employment with regard to the above. Such action shall include, but not be limited to, the following: employment, upgrading, demotion or transfer; recruitment, layoff or termination, rates of pay or other form of compensation; and selection for training, including apprenticeship. The Contractor agrees to post in conspicuous places, available to employees and applicants for employment, notices setting forth the provisions of this nondiscrimination clause. Contractors must also include the same nondiscrimination language in all subcontracts.

If the Contractor fails to comply with nondiscrimination clauses of this contract or fails to include such contract provisions in all subcontracts that subcontractors will not discriminate against any employee or applicant for employment in the manner described above, this contract may be declared void AB INITIO, cancelled, terminated or suspended in whole or in part and the Contractor may be declared ineligible for further contracts with the City of Rockville. Any employee, applicant for employment, or prospective employee with information concerning any breach of these requirements may communicate such information to the City Manager who shall commence a prompt investigation of the alleged violation. Pursuant to such investigation, the Contractor will permit access to the Contractor's books, records, and accounts. If the City Manager concludes that the Contractor has failed to comply with nondiscrimination clauses, the remedies set out above may be invoked.

- **46. LANGUAGE** If applicable, the Contractor shall appoint one or more crew members or supervisors to act as liaison with the City and emergency service personnel. All liaisons shall be fluently bilingual in English and the Contractor's employees' language(s), and at least one liaison shall be present at each work site at all times when any of the Contractor's employees or agents are at the site.
- 47. IMMIGRATION REFORM AND CONTROL ACT Contractor warrants that it does not and shall not hire, recruit or refer for a fee, for employment under the Contract, an individual knowing the individual is an unauthorized individual and hire any individual without complying with the requirements of the Immigration Reform and Control Act of 1986 ("the Act"), including but not limited to any verification and record keeping requirements. Contractor further assures the City that, in accordance with the Act, it does not and will not discriminate against an individual with respect to hiring, or recruitment or referral for a fee, of the individual for employment or the discharging of the individual from employment because of such individual's national origin or in the case of a citizen or intending citizen, because of such individual's citizenship status.
- **48.** <u>ASSIGNMENT</u> Neither this contract nor any interest therein nor claim thereunder shall be assigned or transferred by the Contractor except as expressly authorized in writing by the City.
- **49. EXCLUSION** As part of the contract, the offeror must warrant that it will not engage in providing consulting or other services to any private entity regarding any property within the study area during the term of the project. This requirement is intended to avoid the appearance of any conflict of interest that may arise. This exclusion also applies to all subcontractors.
- **50. OWNERSHIP OF DOCUMENTS** Any and all deliverables, including but not limited to reports, specifications, blueprints, plans, negatives, electronic files and documents, as well as, any other documents prepared by the Contractor in the performance of its obligations under the resulting contract shall be the exclusive property of the City. The Contractor shall not use, willingly allow, or cause such materials to be used for any purpose other than performance of all Contractors' obligations under the resulting contract without the prior written consent of City. Documents and materials developed by the Contractor under the resulting contract shall be the property of City of Rockville; however, the Contractor may retain file copies, which cannot be used without prior written consent of the City. The City agrees that the Contractor shall not be liable for any damage, loss, or injury resulting from the

future use of the provided documents for other than the project specified, when the Contractor is not the firm of record.

- 51. NON-DISCLOSURE Contractor and the City of Rockville acknowledge that they or their employees may, in the performance of any subsequent agreement come into the possession of proprietary or confidential information owned by or in the possession of the other. Neither party shall use any such information for its own benefit or make such information available to any person, firm, corporation, or other organizations, whether or not directly or indirectly affiliated with Contractor or the City unless required by law.
- **52.** COOPERATIVE PROCUREMENT The Contractor may extend all of the terms, conditions, specifications, and unit or other prices of any award resulting from this solicitation to any and all other public bodies, subdivisions, school districts, community colleges, colleges, and universities. The City assumes no authority, liability or obligation, on behalf of any other public entity that may use any contract resulting from this solicitation.

CITY INSURANCE REQUIREMENTS

Prior to execution of the contract by the City, the Contractor must obtain at their own cost and expense and keep in force and effect during the term of the contract including all extensions, the following insurance with an insurance company/companies licensed to do business in the State of Maryland evidenced by a certificate of insurance and/or copies of the insurance policies. The Contractor's insurance shall be primary. The Contractor must electronically submit to the Procurement Division a certificate of insurance prior to the start of any work.

In no event may the insurance coverage be less than shown below.

Unless otherwise described in this contract the successful contractor and subcontractors will be required to maintain for the life of the contract and to furnish the City evidence of insurance as follows:

	Type of Insurance	Amounts of Insurance	Endorsements and Provisions
1. 2.	Workers' Compensation Employers' Liability	Bodily Injury by Accident: \$100,000 each accident Bodily Injury by Disease: \$500,000 policy limits Bodily Injury by Disease: \$100,000 each employee	Waiver of Subrogation: WC 00 03 13 Waiver of Our Rights to Recover From Others Endorsement - signed and dated.
a. b. c. d. e. f.	Commercial General Liability Bodily Injury Property Damage Contractual Liability Premise/Operations Independent Contractors Products/Completed Operations Personal Injury	Each Occurrence: \$1,000,000	City to be listed as additional insured and provided 30 day notice of cancellation or material change in coverage. CG 20 37 07 04 and CG 20 10 07 04 forms to be both signed and dated.
a. b. c.	Automobile Liability All Owned Autos Hired Autos Non-Owned Autos	Combined Single Limit for Bodily Injury and Property Damage - (each accident): \$1,000,000	City to be listed as additional insured and provided 30 day notice of cancellation or material change in coverage. Form CA20 48 02 99 form to be both signed and dated.
5.	Excess/Umbrella Liability	Each Occurrence/Aggregate: \$1,000,000	City to be listed as additional insured and provided 30 day notice of cancellation or material change in coverage.
6.	Professional Liability (if applicable)	Each Occurrence/Aggregate: \$1,000,000	

Policy Cancellation

No change, cancellation or non-renewal shall be made in any insurance coverage without thirty (30) days written notice to the City's Procurement Division. The Contractor shall electronically furnish a new certificate prior to any change or cancellation date. The failure of the Contractor to deliver a new and valid certificate will result in suspension of all payments and cessation of on-site work activities until a new certificate is furnished.

Additional Insured

The Mayor and Council of Rockville, which includes its elected and appointed officials, officers, consultants, agents and employees must be named as an additional insured on the Contractor's Commercial and Excess/Umbrella Insurance for liability arising out of contractor's products, goods, and services provided under the contract. Additionally, the Mayor and Council of Rockville must be named as additional insured on the Contractor's Automobile and General Liability Policies. Endorsements reflecting the Mayor and Council of Rockville as an additional insured are required to be submitted with the insurance certificate.

Subcontractors

If applicable, all subcontractors shall meet the requirements of this section before commencing work. In addition, the Contractor shall include all subcontractors as insured under its policies or shall furnish separate certificates and endorsements for each subcontractor. All coverages for subcontractors shall be subject to all of the requirements stated herein.

Example:
Certificate Holder
The Mayor and Council of Rockville
City Hall
111 Maryland Avenue
Rockville, MD. 20850

Maryland Department of Transportation State Highway Administration

Certification for Contracts, Grants, Loans, and Cooperative Agreements

The undersigned certifies, to the best of their knowledge and belief, that:

- 1) No federally appropriated funds have been paid or will be paid, by or on behalf of the undersigned, to any person for influencing or attempting to influence an officer or employee of an agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with the awarding of any Federal contract, the making of any Federal grant, the making of any federal loan, the entering into of any cooperative agreement, and the extension, continuation, renewal, amendment, or modification of any federal contract, grant, loan, or cooperative agreement.
- 2) If any funds other than federal appropriated funds have been paid or will be paid to any person for influencing or attempting to influence an officer or employee of any agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with this federal contract, grant, loan, or cooperative agreement, the undersigned shall complete and submit Standard Form-LLL, "Disclosure Form to Report Lobbying," in accordance with its instructions.
- 3) The undersigned shall require that the language of this certification be included in the award documents for all subawards at all tiers (including subcontracts, subgrants, and contracts under grants, loans, and cooperative agreements) and that all subrecipients shall certify and disclose accordingly.

This certification is a material representation of fact upon which reliance was placed when this transaction was made or entered into. Submission of this certification is a prerequisite for making or entering into this transaction imposed by section 1352, title 31, U.S. Code. Any person who fails to file the required certification shall be subject to a civil penalty of not less than \$10,000 and not more than \$100,000 for each such failure.

Contractor/Consultant Name	Date	
Signatory position		
Contractor/Consultant Company		

CITY OF ROCKVILLE OFFEROR REFERENCE FORM

The City of Rockville reserves the right to reject bids from any company not meeting the minimum qualifications. The Offeror shall be a competent and experienced contractor with an established reputation within the community performing the type of work required for this contract. The offeror shall have performed similar work for a minimum period of five (5) years. Indicate below a listing of three recent projects completed by your firm that can substantiate past work performance and experience in the type of work required for this contract. The City may make such investigations as it deems necessary to determine the ability of the offeror to perform the work, and the offeror shall furnish to the City all such information and data for this purpose as the City may request.

1. Company Name	
Address:	
Contact Person:	Current phone #:
Email Address:	
Contract Amount:	Name of your project supervisor:
Description of Work Performed:	
2. Company Name	
Address:	
Contact Person:	
Email Address:	
Contract Amount:	Name of your project supervisor:
Description of Work Performed:	
3. Company Name	
Address:	
Contact Person:	Current phone #:
Email Address:	
Contract Amount:	
Description of Work Performed:	

NAME OF OFFEROR/PROPOSER RETURN THIS FORM WITH PROPOSAL

ATTACHMENT F A F F I D A V I T

I hereby affirm that:	DAVII
-	authorized representative of the firm of
and that I possess the legal authority to make this affidavit on behalf	
I further affirm:	·
AFFIDAVIT OF QUALIFICATION TO CONTRACT WITH A PUBLIC BODY 1. Except as described in Paragraph 2 below, neither I nor the	of the State Finance and Procurement Article of the Annotated Code of Maryland, will provide, directly or indirectly, supplies, services, architectural services, construction related services, leases of real property, or construction.
above firm nor, to the best of my knowledge, any of its controlling stockholders, officers, directors, or partners, performing contracts with any public body (the State or any unit thereof, or any local governmental entity in the state, including any bi-county or multi-county entity), has:	I acknowledge that this Affidavit is to be furnished to the Mayo and Council of Rockville and, where appropriate, to the State Board of Public Works and to the Attorney General. I acknowledge that am executing this Affidavit in compliance with the provisions of Title 16 of the State Finance and Procurement Article of the Annotated
 A. been convicted under the laws of the State of Maryland, any other state, or the United States of any of the following: bribery, attempted bribery, or conspiracy to bribe. a criminal offense incident to obtaining, attempting to obtain, or performing a public or private contract. fraud, embezzlement, theft, forgery, falsification or destruction of records, or receiving stolen property. a criminal violation of an anti-trust statute. 	Code of Maryland which provides that persons who have engaged in certain prohibited activity may be disqualified, either by operation in law or after a hearing, from entering into contracts with the Mayo and Council of Rockville. I further acknowledge that if the representations set forth in this Affidavit are not true and correct, the Mayor and Council of Rockville may terminate any contract awarded and take any other appropriate action.
(5) a violation of the Racketeer Influenced and Corrupt Organization act, or the Mail Fraud Act, for acts in	NON—COLLUSION AFFIDAVIT
connection with the submission of bids or proposals for a public or private contract. (6) a violation of Section 14-308 of the State Finance and Procurement Article of the Annotated Code of Maryland. (7) conspiracy to commit any of the foregoing.	1. Am fully informed respecting the preparation and contents o the attached bid and of all pertinent circumstances respecting such bid; 2. Such bid is genuine and is not a collusive or sham bid
B. pled nolo contendere to, or received probation before verdict	3. Neither the said bidder nor any of its officers, partners
for, a charge of any offense set forth in subsection A of this paragraph. C. been found civilly liable under an anti-trust statute of the State of Maryland, another state, or the United States for acts or omissions in connection with the submission of bids or proposals for a public or private contract.	owners, agents, representatives, employees or parties in interest including this affiant, has in any way colluded, conspired, conniver or agreed, directly or indirectly with any other bidder, firm or persor to submit a collusive or sham bid in connection with the Contract for which the attached bid has been submitted or to refrain from bidding
D. during the course of an official investigation or other proceeding, admitted, in writing or under oath, an act or omission that would constitute grounds for conviction or liability under any law or statute described in subsection A or C of this paragraph.	in connection with Contract, or has in any manner, directly of indirectly, sought by agreement or collusion or communication of conference with any other bidder, firm or person to fix the price of prices in the attached bid or of any other bidder, or to fix any overhead, profit or cost element of the bid price or the bid price or
2. [State "none," or as appropriate, list any conviction, plea or admission as described in Paragraph 1 above, with the date, court, official or administrative body, the individuals involved and their position with the firm, and the sentence or disposition, if any].	any other bidder, or to secure through any collusion, conspiracy connivance or unlawful agreement any advantage against the Mayo and Council of Rockville, Maryland (Local Public Agency) or any person interested in the proposed Contract; and
3. I further affirm that neither I nor the above firm shall knowingly enter into a contract with the Mayor and Council of Rockville under which a person or business debarred or suspended from contracting with a public body under Title 16	4. The price or prices quoted in the attached bid are fair and proper and are not tainted by any collusion, conspiracy, connivance or unlawful agreement on the part of the bidder or any of its agents, representatives, owners, employees, or parties in interest, including this affiant.
I do solemnly declare and affirm under the penalties of perjury that	the contents of these affidavits are true and correct.
Signature and Title	Date
NAME OF OFFEROR/PROPOSER	

RETURN THIS FORM WITH PROPOSAL

RESPONDENT'S QUESTIONNAIRE

The Respondent recognizes that in selecting a company/agent, The City of Rockville will rely, in part, on the answers provided in response to this Questionnaire. Accordingly, Respondent warrants to the best of its knowledge that all responses are true, correct and complete. The City of Rockville reserves the right to contact each and every reference listed on the reference form and shall be free from any liability to respondent for conducting such inquiry.

Company Pro	file
1.	Number of Years in Business:
2.	Type of Operation: Individual Partnership Corporation Government
	Number of Employees:(company wide) Number of Employees:(servicing location)
	Annual Sales Volume:(company wide) Annual Sales Volume:(servicing location)
3.	State that you will provide a copy of your company's audited financial statements for the past two (2) years, if requested by the City of Rockville.
4.	Is your company currently for sale or involved in any transaction to expend or to become acquired by another business entity? If yes, please explain the impact both in organizational and directional terms.
5.	Is your company currently in default on any loan agreement or financing agreement with any bank, financial institution, or other entity? If yes, specify date(s), details, circumstances, and prospects for resolution.

NAME OF OFFEROR/PROPOSER

RETURN THIS FORM WITH PROPOSAL